

**ORDINANCE
ROCK COUNTY BOARD OF SUPERVISORS**

TIM BANWELL
INITIATED BY



JEROME A. LONG
DRAFTED BY

BOARD OF HEALTH
SUBMITTED BY

JULY 17, 2012
DATE DRAFTED

AMENDMENTS TO CHAPTER XIII-ROCK COUNTY PUBLIC HEALTH ORDINANCE

1 The Board of Supervisors of the County of Rock, at its regular meeting this 27 day of
2 September, 2012, does ordain as follows:

3
4 I. That section 13.01 (A) of the Rock County Public Health Ordinance is amended to read as follows:

5
6 **13.01 DEFINITIONS**

7
8 (A) Definitions Enumerated – the following definitions apply throughout the entire Ordinance:

9 ...

10 (9) Farmer's Market – refrigerated and/or frozen foods individually packaged at an approved
11 processor and are labeled for resale. Product is sold from a refrigerator(s) and/or freezer(s) at a
12 farmer's market and/or directly off the farm.

13
14 (910) Full Service Grocery Store - means a retail food establishment that includes pre-packaged
15 food, delicatessen, and bakery sales and meat processing services that also sells, serves or prepares
16 meals as defined in HFS 196, Restaurants.

17
18 (4011) Groundwater - means any of the waters of the state, as defined under s. 160.01(4), stats.,
19 found beneath the surface of Rock County occurring in a saturated subsurface geological formation of
20 rock or soil. [See SPS 381.01(114) Definitions].

21
22 (4112) Health Hazard - means a substance, activity or condition that is known to have the
23 potential to cause acute or chronic illness or death if exposure to the substance, activity or condition is not
24 abated or removed.[See HFS 140.03 Definitions.]

25
26 (4213) Health Officer - means the legally designated Health Officer of Rock County or a
27 designee of the Health Officer. [See 13.09(1)]

28
29 (4314) Immediate Health Hazard - means a health hazard which should, in the opinion of the
30 Health Officer, be abated or corrected immediately, or not later than within a 24 hour period, to
31 prevent possible severe damage to human health and/or the environment.

32
33 (4415) Independent Operation - means a separate restaurant facility that operates on the
34 property of a licensed restaurant.

35
36 (4516) Land Division - means any division of land that results in the creation of one or more lots
37 as defined in Chapter 15 of the Rock County Ordinances, the Rock County Land Division Regulations,
38 with any changes in the definition of "lot" in Chapter 15 to be incorporated into the meaning given in this
39 Chapter.

40
41 (4617) Licensing Year - means the twelve month interval from July 1 through the next
42 following June 30th.

43
44 (4718) Limited Food Service - means any restaurant establishment with the food operation and
45 utensils restricted to tongs, spatulas, cutting or spreading knives, approved heating units, with the food
46 stored in the original package and served using only single service materials.

12-9A-099

47

48 (1819) Limited Retail Eating Establishment - means any retail food establishment with the food
49 operation and utensils restricted to tongs, spatulas, cutting or spreading knives, approved heating units,
50 with the food stored in the original package and served using only single service materials.

51

52 (1920) Lot - means "lot" as defined in Chapter 15 of the Rock County Ordinances, the Rock
53 County Land Division Regulations, with any changes in the definition of "lot" in Chapter 15 to be
54 incorporated into the meaning given in this Chapter.

55

56 (2021) Mobile Restaurant Vehicle – means a restaurant operating from a moveable vehicle, push
57 cart, trailer or boat which periodically or continuously changes location and wherein retail food is sold to
58 the consumer for consumption, except those vehicles used in delivery of pre-ordered food prepared in a
59 licensed food establishment.

60

61 (2122) Mobile Restaurant Vehicle, Limited – means a mobile restaurant vehicle that meets the
62 requirements of a limited food service.

63

64 (2223) Mobile Restaurant Service Base – means a service base for mobile restaurants to clean,
65 store and service a mobile restaurant vehicle.

66

67 (2324) Mobile Retail Food Establishment Vehicle – means a retail food establishment operating
68 from a moveable vehicle, push cart, trailer or boat which periodically or continuously changes location
69 and wherein retail food is sold to the consumer for consumption, excepting those vehicles used in delivery
70 of pre-ordered food prepared in a licensed food establishment.

71

72 (2425) Mobile Retail Food Establishment Vehicle, Limited – means a mobile retail food
73 establishment vehicle that meets the requirements of a limited retail eating establishment.

74

75 (2526) Mobile Retail Food Service Base – means a service base for mobile retail food
76 establishment to clean, store and service.

77

78 (27) Novelty Ice Cream Sales – individually packaged novelty ice cream products that are
79 processed from an approved manufacturer and are labeled for resale. Products are sold from a freezer(s)
80 or commercial merchandiser(s).

81

82 (2628) Ordinance - means the "Rock County Public Health Ordinance".

83

84 (2729) Person - means any individual, firm, corporation, society, association, institution, public
85 body or any other entity.

86

87 (2830) Pollution - means the contaminating or rendering unclean or impure the air, land or waters
88 of the County, or making the same injurious to public health, harmful for commercial or recreational use
89 or deleterious to fish, bird, animal or plant life.

90

91 (2931) Practitioner- means a tattooist or body piercer, also includes a person who is both a
92 tattooist and a body piercer.

93

94 (3032) Premises - means, with regard to tattooing or body piercing, a building, structure, area,
95 or location where tattooing or body piercing is performed.

96

97 (3133) Private Dwelling - means any building used only for living purposes and occupied by one
98 or two families.

99

100 (3234) Private Sewage System - Also referred to as a Private Onsite Wastewater Treatment
101 System (POWTS), means as defined in Section 145.01 (12), Wis. Stats., a sewage treatment and disposal
102 system serving a single structure with a septic tank and soil absorption field located on the same parcel as
103 the structure. This term also means an alternative sewage system approved by the Department of Safety
104 and Professional Services (SPS) including a substitute for the septic tank or soil absorption field, a
105 holding tank, a system serving more than one structure or a system located on a different parcel than the
106 structure.

107

108 (3335) Privy - means an outdoor structure used for disposition of human excrement.

109

110 (3436) Public - 1) means affecting or having the potential to affect the people and/or the
 111 environment outside the limits of ones personally owned and personally occupied structure. 2) means all
 112 persons outside of ones personally owned and personally occupied structure.

113

114 (3537) Public Bathing Beach - means any designated body of water used for public swimming,
 115 diving or recreational bathing, not contained within a structure, chamber or tank, together with the
 116 associated land area and appurtenances designated for bather usage and serving one or any of the
 117 following: a licensed campground, recreational and educational camp, hotel, motel, club, association,
 118 housing development, school, religious, charitable or youth organization and including such designated
 119 body of water with associated land area controlled by a local government or political subdivision
 120 thereof. If an area is advertised as a beach and/or a fee is accepted from the public, it shall be
 121 considered a public beach.

122

123 (3638) Public Building - means any structure used in whole or in part as a place of resort,
 124 assemblage, lodging, trade, traffic, occupancy or use by the public. In most cases anything other than a
 125 one or two family residence

126

127 (3739) Public Facility - means any facility used by the public that requires a license or permit
 128 under this Ordinance or a state code adopted by reference in this Ordinance.

129

130 (3840) Public Nuisance (Nuisance) - means a thing, act, condition or use of property which is
 131 dangerous or has the potential to be dangerous, to human life or health; and whatever renders or has the
 132 potential to render, the soil, air, water or any article of food or drink unwholesome or impure, is a
 133 nuisance.

134

135 (3941) Restaurant - means any building, room or place where meals are prepared, served or sold
 136 to transients or the general public, and all places used in connection with the building, room or place and
 137 includes any public or private school lunchroom for which food service is provided by contract.
 138 Restaurant is further defined in the State of Wisconsin Administrative code Chapter HFS 196
 139 Restaurants.

140

141 (4042) Restricted Food Service - means a restaurant where meals are prepared, served or sold
 142 with the food operation and utensils restricted to tongs, spatulas, cutting or spreading knives, approved
 143 heating units, with the food stored in the original package and served using only single service materials.

144

145 (4143) Retail Eating Establishment - means any retail food establishment that sells, serves or
 146 prepares meals, excluding full service grocery stores and specialty grocery stores.

147

148 (4244) Sanitary Permit - a State sanitary permit issued by the Rock County Health Department in
 149 conformity with the State Statute Section 145.19 (1) for the installation, modification or replacement of a
 150 private sewage system or any major component thereof within the County of Rock.

151

152 (4345) Sanitary Survey - means an inspection and water sampling of the swimming area or the
 153 review of data for the entire watershed contributing to the body of water on which the beach is located in
 154 order to determine the bacteriological, biological, chemical and physical quality of the water using
 155 generally accepted parameters and, specifically, those included in this Ordinance.

156

157 (4446) Scum - means the lighter than water material in a septic tank which floats on the liquid
 158 surface.

159

160 (4547) Sludge - means the heavier than water material in a septic tank which settles to the
 161 bottom of the tank.

162

163 (4648) Solid Waste - means garbage, refuse and all other discarded or salvageable solid materials,
 164 including solid waste materials resulting from industrial, commercial and agricultural operations and from
 165 domestic use and public service activities, but does not include solids or dissolved material in waste water
 166 effluent or other common water pollutants

167

168 (4749) Special Event - means a show, bazaar, fair or other occurrence, subject to the provisions
 169 of this Ordinance, lasting up to a maximum of seven (7) consecutive days at a single location, whether
 170 public or private premises.

171

172 (4850) Special Organization - means a licensed restaurant or retail food establishment operated
 173 by a church, fraternal, youth or patriotic organization or a service club or civic organization that prepares,
 174 serves or sells meals to which members of the general public are invited, for at least 4 but not more than
 175 12 days during any 12 month period. Special Organization serving meals is further defined in State of
 176 Wisconsin Administrative Code Chapter HFS 196 Restaurants.

177

178 (4951) Specialty Grocery Store - means a retail food establishment that includes prepackaged
 179 food, produce, or bulk food sales and may include one of the following: delicatessen, bakery or meat
 180 processing.

181

182 (5052) State - means the State of Wisconsin.

183

184 (5153) State-Approved Disinfectant - means a chemical that is capable of destroying disease
 185 causing organisms on inanimate objects, with the exception of bacterial spores, which is approved for
 186 use as a sanitizer by the Wisconsin Division of Public Health.

187

188 (5254) Sterilization - means the killing of all organisms and spores through the use of an
 189 autoclave operated at a minimum of 250°F (121°C) at pressure of at least 15 pounds per square inch for
 190 not less than 30 minutes or through use of an autoclave approved by the Wis. Dept. of Health and
 191 Family Services that is operated at different temperature and pressure levels but is equally effective in
 192 killing all organisms and spores.

193

194 (5355) Structure or Building - means a building or structure having walls and a roof erected or set
 195 upon an individual foundation or slab constructed base designed or used for the housing, shelter,
 196 enclosure, or support of persons, animals or property of any kind. This definition includes mobile homes.

197

198 (5456) Tattoo - as a verb, means to insert pigment under the surface of the skin of a person, by
 199 pricking with a needle or otherwise, so as to produce an indelible mark or figure through the skin;
 200 includes the making of any permanent cosmetic enhancement to the human body which is not
 201 performed by a licensed physician or dentist.

202

203 (5557) Temporary Annual - means a temporary restaurant which operates in conjunction with
 204 single events such as a fair, carnival, circus, public exhibition, anniversary sale or occasional sales
 205 promotion and operates more than six days during any twelve month period.

206

207 (5658) Temporary Tattoo Establishment - means a single building structure, special event, area
 208 or location where a tattooist or body piercer performs tattooing or body piercing for a maximum of
 209 seven days per event

210

211 (5759) Temporary Non-Profit- means a temporary restaurant operated by a church, or a religious,
 212 fraternal, youth or patriotic organization or a service club or a civic organization that operates more than
 213 four days in any twelve month period.

214

215 (5860) Temporary Retail Annual – means a temporary retail establishment which operates in
 216 conjunction with single events such as a fair, carnival, circus, public exhibition, anniversary sale or
 217 occasional sales promotion and operates more than six days during any twelve month period.

218

219 (5961) Temporary Retail Non-profit – means a temporary retail establishment operated by a
 220 church, or a religious, fraternal, youth or patriotic organization or a service club or a civic organization
 221 that operates more than four days in any twelve month period.

222

223 (6062) Temporary Retail Six Day – means a temporary retail establishment which operates in
 224 conjunction with single events such as a fair, carnival, circus, public exhibition, anniversary sale or
 225 occasional sales promotion and is limited to six days of operation during any twelve month period

226

227 (6163) Temporary Retail Three Day – means a temporary retail establishment which operates in
 228 conjunction with single events such as a fair, carnival, circus, public exhibition anniversary sale or
 229 occasional sales promotion and is limited to three days of operation during any twelve month period.

230

231 (6264) Temporary Six Day- means a temporary restaurant which operates in conjunction with a
 232 single event such as a fair, carnival, circus, public exhibition, anniversary sale or occasional sales
 233 promotion and is limited to six days of operation during any twelve month period.

234

235 (6365) Temporary Three Day- means a temporary restaurant that operates in conjunction with
 236 single events such as a fair, carnival, circus, public exhibition, anniversary sale or occasional sales
 237 promotion and is limited to fewer than four days operation during any twelve month period.

238
 239 (6466) Toxic and Hazardous Materials - any chemical and/or biological material that is or has the
 240 potential to create a public health hazard.

241
 242
 243 II. That section 13.03 of the Rock County Public Health Ordinance is amended to read as follows:

244
 245 **13.03 AUTHORITY**

246
 247 This Ordinance is adopted pursuant to the authority granted by Sections 59.70(5), 59.70(6), 93.06,
 248 97.41, 145.20, 251.04, 252.245(6), 254.74, 280.21 and 823.01 of the Wisconsin Statutes.

249
 250
 251 III. That section 13.08(1) of the Rock County Public Health Ordinance is amended to read as follows:

252
 253 **13.08 INCORPORATION OF PROVISIONS BY REFERENCE**

254
 255 (1) Provisions Enumerated - This Ordinance incorporates by reference all or parts of the
 256 following State Administrative Code: ATCP 75, SPS 326, SPS 381, SPS 383, SPS 385, SPS
 257 387, SPS 390, SPS 391, SPS 395, HFS172, HFS173, HFS175, HFS178, HFS195, HFS196,
 258 HFS197 and HFS198, NR812, NR845 and all changes and amendments made thereto.
 259 These rules, regulations and laws shall be construed, read and interpreted as though fully set
 260 forth herein and shall apply until amended and then apply as amended. Provisions of this
 261 Ordinance shall control where more restrictive as determined by the Health Officer.

262
 263
 264 IV. That sections 13.10 (1) and (7) of the Rock County Public Health Ordinance are amended to read
 265 as follows:

266
 267 **13.10 PERMIT AND LICENSE REQUIREMENTS AND FEES**

268
 269 (1) Department Permits - The Department must collect and remit to the State the amount of
 270 State fees imposed on certain activities which are subject to County fees under this
 271 Ordinance, which fees are sometimes expressed as a percentage of the County fee. Should
 272 said percentage and/or the amount of such State fees increase during the year, the
 273 Department permit fee shall automatically increase, in an amount to the nearest five dollar
 274 (\$5.00) figure so as to ensure no loss of Department revenue.

275
 276 The application for a permit or a permit renewal covered in this Ordinance shall be made on
 277 forms provided by the Department and shall be accompanied with the appropriate fee and
 278 preinspection fee, where applicable, payable to the Rock County Health Department. The
 279 Rock County Board of Supervisors shall establish the cost of permits, licenses and other
 280 fees to be collected under this Ordinance, as part of the annual budget for the County. If
 281 the amount of any fee established as part of the current annual budget for Rock County
 282 shall conflict with any amount set forth in any published version of this Ordinance, the
 283 amount set forth in the current annual budget shall prevail and any portion of the
 284 published Ordinance inconsistent therewith shall be deemed to have been amended to
 285 conform to the current annual budget, including any amendments thereto, as adopted. A
 286 schedule of costs for permits, licenses, preinspections and other fees is available from the
 287 Department. The required permits, licenses, preinspections and other fees are as follows:

288
 289 (a) Public beaches (Section 13.25)

290
 291 ...

292
 293 (l) Retail Food Establishments (Section 13.21)

294 The following permits are established by the Rock County Board of Supervisors and
 295 applicable fees must be paid before any permit is issued:

- 296 1. Full Service Grocery
 297 2. Specialty Grocery

- 298 3. Retail Eating Establishment
- 299 4. Limited Retail Eating Establishment
- 300 5. Temporary Retail Annual
- 301 6. Temporary Retail Six Day
- 302 7. Temporary Retail Three Day
- 303 8. Temporary Retail Non-Profit
- 304 9. Mobile Retail Food Establishment
- 305 10. Mobile Retail Food Establishment Service Base
- 306 11. Farmer's Market
- 307 12. Novelty Ice Cream Sales

309 ...

310

311 (7) Permit Expiration and Penalty Fee - All Annual permits issued by the Department under

312 sections 13.10 (1) (a) to (f), (j), (k) and (l) expire on June 30. An additional penalty fee of

313 ~~\$20.00-75.00~~ for permits issued under section 13.10 (1) (a) to (f), (j), (k), and (l) shall be

314 required for each permit whenever the annual fee for renewal is not paid before the permit

315 expires. The penalty fee is established by the Rock County Board of Supervisors as part

316 of the annual budget for the county. No annual permit will be renewed after June 30 unless

317 payment of the renewal and penalty fee is received by the Department on or before July

318 15. No person may conduct, manage, maintain or operate any of the public facilities

319 requiring annual permits if the person has not been issued a current permit; or, in the case

320 of renewal of an annual permit, if the person has not renewed the permit on or before July

321 15.

322

323 ...

324

325

326 V. That section 13.23(5)(e) of the Rock County Public Health Ordinance is amended to read as

327 follows:

328

329 **13.23 PRIVATE SEWAGE SYSTEMS**

330

331 ...

332 (5) Private Sewage Systems

333

334 ...

335

336 (e) Holding tanks may be used as a system of last resort to serve as the private

337 sewage system for an existing building, ~~only~~. Holding tanks will not be allowed

338 for new construction ~~nor can they be designated as the only possible replacement~~

339 ~~system on the contingency plan for new construction on a property where other~~

340 onsite wastewater treatment system options exist. If a person feels that

341 mitigating circumstances exist where a holding tank should be allowed for new

342 construction, or in lieu of another approved system, the person may seek a

343 variance from the Rock County Board of Health. Holding tanks may be used as

344 a replacement system of choice, without a variance, ~~in a floodplain district~~

345 ~~unless soils allow the installation of a below ground system in the following~~

346 circumstances.

- 347
- 348 1. In a flood fringe and in compliance with the County Ordinance Chapter 32
- 349 Floodplain Zoning, unless soils allow the installation of a conventional
- 350 system.
- 351 2. Commercial venues for public restroom in situations where a conventional
- 352 system cannot be installed.
- 353 3. Agricultural use (milk house, shop, etc.) where a conventional system cannot
- 354 be installed.
- 355 4. To divert kitchen waste from a private onsite wastewater treatment system.
- 356 5. Restroom facilities for outbuildings where connection to an existing system
- 357 or installation of a conventional system is not practical.
- 358 6. Toilet room use for employees where a conventional system cannot be
- 359 installed.

360

361 ...

362

363

364 VI. That section 13.25 of the Rock County Public Health Ordinance is amended to read as follows:

365

366 **13.25 PUBLIC BEACHES**

367

368 (1) Sanitary Survey.

369

370 ...

371 (2) Beach Water Sampling.

372

373 (a) Frequency. At least one set of bacteriological samples shall be collected from
 374 representative locations throughout the swimming area four times per month during
 375 the swimming season or during the peak risk periods as identified by past water
 376 quality tests. The samples shall be submitted to the State Laboratory of Hygiene or
 377 other laboratory certified under Chapter HFS165 to perform water microbiological
 378 analysis. ~~A set of samples shall be collected during any one day.~~ The required
 379 samples shall be collected by the Rock County Health Department and tested by a
 380 certified laboratory unless the beach operator is required by the Rock County Health
 381 Department to collect and submit samples of water to a certified laboratory at their
 382 expense.

383

384 (b) Sampling procedure. Samples shall be collected ~~within one foot of the surface in~~
 385 ~~water having a depth range of 3 to 6 feet.~~ 6 to 12 inches below the water surface
 386 where a 24 to 30 inch water depth is first encountered unless beach conditions
 387 warrant otherwise.

388

389 (3) ~~Beach Advisory/Closing Criteria for a Beach. When one or more of the following~~
 390 ~~subsections, (5) through (7), are not complied with, the beach shall be closed to the public~~
 391 ~~until compliance is achieved.~~

392

393 (a) Advisory Criteria - A beach shall be posted with approved advisory signs under the
 394 following criteria (i) through (iv). Beach advisory signs may be removed when a
 395 sample result is below the established criteria or the human health hazard no longer
 396 exists.

397

398 (i) Whenever a single beach E. Coli sample result exceeds 235 cfu/100ml.

399 (ii) Whenever a human health hazard exists as determined by the Health Department

400 (iii) Whenever a pollution event exists that may potentially cause human health
 401 hazards.

402 (iv) Whenever a significant weather event adversely impacts a beach area.

403

404 (b) Closure Criteria - Beach Closure Criteria. A beach shall be posted with approved
 405 closure signs under the following criteria (i) through (iv). Beach closure signs may
 406 be removed when a sample result is below the established criteria or the human
 407 health hazard no longer exists.

408

409 (i) Whenever a single beach E. Coli sample result exceeds 1000 cfu/100ml.

410 (ii) Whenever a human health hazard exists as determined by the Health Department

411 (iii) Whenever a pollution event exists that may potentially cause human health
 412 hazards.

413 (iv) Whenever a significant weather event adversely impacts a beach area.

414

415 (4) Microbiological Quality. ~~The beach water fecal coliform density from the last four~~
 416 ~~successive sets of samples collected on four different days within a 30 day period shall not~~
 417 ~~exceed a geometric mean of 400 per 100 milliliters (ml) nor shall the fecal coliform~~
 418 ~~density of any sample exceed 1,000 per 100 ml. The beach may be reopened if the fecal~~
 419 ~~coliform density in two consecutive daily samples is less than 400 per 100 ml. If the~~
 420 ~~beach is suspected to be the cause of communicable level disease it shall be posted with an~~
 421 ~~advisory or closed until the source of disease is identified and removed and/or the above~~
 422 ~~bacteriological quality indicates the water is safe for swimming.~~

423

424 (a) Advisory. A beach shall be required to post approved signs whenever a single beach
 425 sample result for E. coli exceeds 235 cfu/100 ml as a geometric mean of at least 5 samples
 426 over a 30-day period. Advisory signs can be removed when sample results are below the
 427 established criteria.

428
 429 (b) Beach closure. All beaches shall post approved closure signs whenever the E. coli in
 430 the beach water sample exceeds 1000 cfu/100 ml. The beach closure signs may be
 431 removed when a sample is below the established closure criteria.

432
 433 ...
 434 (8) Design.

435
 436 ...
 437 (o) Bathhouse. When a bathhouse is constructed it shall be in accordance with ~~chapters~~
 438 ~~Comm 50 to 64~~ appropriate administrative codes of the State of Wisconsin
 439 Department of Safety and Professional Services. New beaches shall provide a
 440 bathhouse meeting specifications of ~~Comm 50 to 64~~ appropriate administrative
 441 codes of the State of Wisconsin Department of Safety and Professional Services.
 442 Where a bathhouse is not required (See Waiver) portable toilets may be used for
 443 less than 200 bathers. The number of toilets shall be two times the requirements in
 444 Appendix A.

445 Waiver: Bathhouses are not required when dressing, shower and toilet facilities,
 446 such as exist at motels, hotels, apartments, country clubs, housing developments
 447 and campgrounds are otherwise provided and are readily available.

448
 449 (9) Safety.

450
 451 ...
 452 (d) Equipment.


- 453 1. If a beach serves over 200 bathers each lifeguard stand shall be provided with a
- 454 whistle or megaphone and an umbrella.
- 455 2. At least one 24 unit Red Cross first aid kit shall be provided at each swimming
- 456 beach when lifeguards are provided.
- 457 3. A spine board and 2 durable blankets shall be provided at each beach.
- 458 4. Each lifeguard stand shall be provided with at least one of the following: a ring
- 459 buoy not less than 20 inches in outside diameter, a rescue buoy, a rescue tube or
- 460 a torpedo buoy. The ring buoy shall be attached to a 75 foot length of 1/4 inch
- 461 rope.
- 462 5. Where swimming is permitted a distance greater than 150 feet from the beach
- 463 shoreline, a lifesaving patrol boat or offshore lifesaving station shall be provided.
- 464 At least one square stern boat, 12 feet or more in length shall be provided for
- 465 each 900 linear feet of beach shoreline. The boat or boats shall be located so as
- 466 to be immediately available, shall be used for their intended purpose only and
- 467 shall be equipped with pin oars, and at least one shepherd's crook type of pole
- 468 and one ring buoy attached to a 75 foot length of 1/4 inch rope.
- 469 6. All lifesaving equipment shall be maintained in good repair and be readily
- 470 available.

471 ...
 472
 473
 474 VII. That Appendix A of the Rock County Public Health Ordinance is amended to read as follows:


475
 476 ...
 477
 478 Bathhouse Construction – The bathhouse construction shall comply with ~~Chapters COMM 90.16~~
 479 SPS 390.16 and COMM 50 to 64, Wisconsin Administrative Code ~~other appropriate administrative~~
 480 codes of the State of Wisconsin Department of Safety and Professional Services.


Respectfully submitted:

BOARD OF HEALTH


Sandra Kraft, Chair


Louis Peer, Vice Chair


Richard Bostwick



Mike Rundle

Absent
Dr. Aaron Best


Dr. Dean Peterson, DVM


Absent
James Rooney, RPH


Judith Wade


Dr. Connie Winter, DDS

LEGAL NOTE:

These ordinance changes are allowable pursuant to §§ 59.70, 145.20, 251.04, 252.245, 280.21 and 823.01 Wis. Stats.



Jerome A. Long
Deputy Corporation Counsel


FISCAL NOTE:

No fiscal impact.


Sherry Oja
Finance Director

ADMINISTRATIVE NOTE:

Recommended.


Craig Knutson
County Administrator