

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in the


T. 2 N., R. 12 E

CORNER CODE INDEX

	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
A																								
B																								
C	6																							
D		5																						
E			4																					
F				3																				
G					2																			
H																								
I																								
J	7																							
K		8																						
L			9																					
M				10																				
N					11																			
O						12																		
P	19																							
Q		17																						
R			16																					
S				15																				
T					14																			
U						13																		
V																								
W																								
X																								
Y	30																							
Z		29																						
			28																					
				27																				
					26																			
						25																		
							30																	
								29																
									28															
										27														
											26													
												25												
													30											
														31										
															32									
																33								
																	34							
																		35						
																			36					

PLACE MONUMENT SYMBOL (◆) AT PROPER LOCATION ON ABOVE INDEX

EXAMPLE



ROCK TWP
ROCK COUNTY WI

IF AVAILABLE
STATE PLANE COORDINATES

North (Y) _____ Eleve. (Z) _____
 East (X) _____ Zone _____
 Hor. Datum _____ Vert. Datum _____

(a.)

◆ CORNER MONUMENT

○ WITNESS MONUMENT

ALUM MONUMENT
2.5' DEEP

WCLO MAST

N 26-47-38 W
15,908.9

FOUND 2" PIPE

Plowed
FIELD

N 0-40-43 W
13,177.5

2645.81
S 89-45-41 E

2567.62
S 89-07-32 E

SW COR
SEC 13

SE COR
SEC 13

Plowed
FIELD

S 55-02-20 W
16,900

SOUTH STACK
POWER GENERATOR PLANT

BEARINGS ARE BASED ON:

FIELD BOOK 2 PAGE # 35

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH. THE CORNER MONUMENT SHALL HAVE THE FOLLOWING CHARACTERISTICS: 1) HAVE AT LEAST TWO PREDETERMINED BREAK-OFF POINTS. 2) IF BROKEN, LEAVE A PERMANENTLY MAGNETIZED REMNANT AT THE ORIGINAL POINT. 3) MUST BE EXTENDABLE. 4) THE CAP IS INSCRIBED: ROCK COUNTY SURVEY MONUMENT - PENALTY FOR DISTURBING MARKER. 5) OR AN EXISTING CUT LIMESTONE. AN IRON PIPE 1 1/2" x 4'0" (MINIMUM) MAY BE USED IN AREAS WHERE GROUND WATER IS WITHIN ONE FOOT OF THE SURFACE. IF THE CORNER IS OCCUPIED BY AN IMPROVEMENT (MANHOLE, BURIED CABLE, ETC.) ANY DURABLE, DISTINCT MONUMENT MAY BE USED. CORNERS SHALL BE REFERENCED WITH AT LEAST 4 DURABLE WITNESS MONUMENTS. WITNESS MONUMENTS SHALL BE MADE OF CONCRETE, NATURAL STONE, IRON OR OTHER EQUALLY DURABLE MATERIAL, EXCEPT WOOD. DESCRIBE THE CORNER AND THE WITNESS MONUMENTS.

CORNER CODE:

N23

(b.) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

SEE SHEET 2

(c.) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


ACCEPTED FOUND PERPETUATED LOCATION

(d.) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(e.) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning in determining the corner location.

NO

I, Ronald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on JAN 13 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.



COUNTY SURVEYOR FILING DATA

Date of Computer Entry _____

Date Received _____

Date Microfilmed _____

Treasurer's Receipt No. _____

Number of Included Sheets 1

AFFIX YOUR LAND SURVEYOR SEAL. CORNER CODE N23



(6)

- 1869 LEE VOL 1 PG 346 FOUND FENCE POST AT CORNER SET BY JAMES SHIELDS. USED TO SUBDIVIDE SECTION 13
- 1885 RUGER VOL 2 PG 279 FOUND OLD DECAYED STAKE AND SET IN ITS PLACE NEW STAKE AND PUT ON EAST SIDE OF IT SMALL LIMESTONE. USED TO SUBDIVIDE SECTION 24
- 1890 BLEEDHORN VOL 2 PG 434 FOUND CORNER SET BY RUGER ABOUT 6' WEST OF N/S FENCE. USED IT TO SUBDIVIDE SECTION. FOUND RUGER'S CENTER OF SECTION AND PLACED A GAS PIPE AT THE EAST 1/16TH CORNER OF THE SW 1/4 OF SECTION 13.
- 1961 BATTERMAN PLAT OF SURVEY. SET CONCRETE MONUMENT. SHOWS A DISTANCE OF 1316.80 TO A 2" PIPE WHICH IS AT THE EAST 1/16TH CORNER OF THE SW 1/4 OF SECTION 13.
- 1973 COMBS PLAT OF SURVEY FOUND CONCRETE MONUMENT.
- 1976 BARNES VOL 5. PG 213 FOUND CONCRETE MONUMENT WITH BRASS CAP. TOP HALF BROKEN. REPLACED WITH ALUMINUM MONUMENT 1' DEEP.
- 1980 COMBS PLAT OF SURVEY. FOUND ALUMINUM MONUMENT

DUG AND FOUND 2.5 DEEP BOTTOM HALF OF ALUMINUM MONUMENT. PLACED ADDITIONAL MAGNETS BY THE MONUMENT.

Donald Barnes

March 3 1989