Paper weight-110# (minimum)

## Black nonfading ink required LAND SUI U.S. PUBLIC SURVEY MONUMENT RECORD


For Public Land Survey Corners In:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

USMONREC.DWG REV 10/23/2004

T. 4 N. R. 10 E. 4th P.M.

CORNER CODE INDEX



**UNION** TWP ROCK COUNTY WI

IF AVAILABLE ROCK COUNTY COORDINATES PERFERRED

Elev. North East Hor. Datum \_\_\_\_ Vert. Datum

ELLIPS. HT. **LATITUDE** 

LONGITUDE

NAD83(91) \_\_\_\_\_NETWORK ADJ. YR 2010

GPS (X) \_\_\_\_ TRAVERSE (X) X BASED ON THE FOLLOWING CONTROL:

**◆ CORNER MONUMENT** 

WITNESS MONUMENT

(a) ROCK COUNTY PROJECTION BEARINGS ARE BASED ON:

FIELD BOOK PAGE # OR OBSERVATION SHEET	SHEET		of 5
SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND S PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH. PLANNING & ZONING COMMITTEE ADOPTED THIS FORM ON 12/2/1982	URROUN	DING	<i>^</i> \
PLAINING & LONING COMMITTEE ABOUTED THIS TOTAL OF ALLESS		. /	1 — /

CORNER CODE  $\sqrt{-17(1)}$ 

## UN609 NECORSEC34

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1833 HARRISON (NOV 7) TOWN 4N RANGE 1DE NORTH BETWEEN 34 & 35

99.0 ENTER S.W {W CIRCLED & E PLACED ABOVE}
POINT OF TIMBER

330.0 LEAVE IT & ENTER MARSH

2640.00 QUARTER SEC COR. SET A POST & RAISED A MOUND OF TUSSOCK

3496.02 BROOK 6.6' CRS WEST

3847.8 CREEK 16.5' CRS S.W.

4950.0 PASS A SE POINT OF TIMBER

5280.00 SET COR TO SECS 26,27,34,35 NEAR WEST EDGE OF WET PRIAIRIE {RED | 10 S21E 211.2'; RED 0 10 S34W 10.56'; RED 0 10 N75W 66.00' LAND LEVEL & WET 3RD RATE GRASS &

WILLOWS

1833 HARRISON T4N R10E 4TH MER. EAST ON RANDOM BET 26 & 35

660.00 CREEK 13.2' CRS S.W.

2640.00 TEMPY 1/4 SEC COR 3300 LEAVE PRAIRIE & ENTER TI

3300 LEAVE PRAIRIE & ENTER TIMBER 5203.44 INT. E BDY N OF P IN W. EDGE OF PRAIRIE

5203.44 INT. E BDY N OF P IN W. EDGE OF PRAIRIE LAND 1ST 1/2 LEVEL & WET 3

RATE 2ND 1/2 LEVEL 2ND RATE WITH BURR D

WEST COR WEST BET SECS 26 & 35

1232.88 BURR 0 12 IN DIAM

2601.72 QUARTER SEC. COR. IN MARSH - POST &

RAISED MOUND

5203.44 INT SEC COR.

1833 HARRISON T4N R10E 4TH MER EAST BET. SECS 27 & 34

2640.00 TEMPY 1/4 SEC COR

5220.60 INT E BDY 7.92' N OF P LAND LEVEL 2ND RATE TIMBER BURR & RED O. MOSTLY SCRUB

GRASS & WEEDS

WEST COR WEST

1197.24 BURR 0 12

2610.30 QUARTER SEC COR {BURR 0 28 N69W 39.6';

BURR 0 24 S75W 12.54 BURR 0 28 & BURR

□ 24}MARKED

5220.60 SEC COR.

1833 HARRISON T4N R1DE 4TH MER NORTH BETWEEN SECS 26

& 27

739.2 CREEK 13.2' CRS S.E.

2046.0 LEFT WET PRAIRIE

2640.00 QUARTER SEC CORNER (BURR 0 20 N27E

13.86'; BURR O 10 S62E 67.32' BURR O 20

& BURR O 10 MARKED

5280 COR TO SECS 22,23,26,27 {BURR O 10 N4E

57.42'; BURR O 8 S80E 31.68'; BURR O. 10 S7E 44.88'; BURR O 10 N62W 55.44' LAND SOUTH 1/2 LEVEL OF MILE 3RD RATE NORTH 1/2 ROLLING 2ND RATE TIMBER ALL BURR O.

MOSTLY GRASS & WEEDS.

1855 CHURCH VOL 1 PG 45 STATES NOTHING ABOUT MON.

2666.40 TO E 1/4 COR SEC 34 & 2625.48 TO N1/4 COR SEC 34.

SHEET 1 OF 5

CORNER CODE V-17(1)

Banes 0 ct 20,2011 UN609 NECORSEC34

1865 LOCKE VOL 1 PG 231 & #5208 FD E 8 TREE WEST 8T GONE. BAR POST RIGHT. 2623.83 TO S 1/4 COR SEC 27

1870 RUGER AUG REMON-63 NORTH ON WEST LINE OF SW 1/4
SEC 35 ON A VAR 6-41 COULD FIND NO TRACE OF
QUARTER CORNER CONTINUED LINE ON SAME
VARIATION AS ABOVE GIVEN AT

5319.60 INTERSECTED NORTH BOUNDARY LINE 9.9'
EAST OF CORNER. FOUND OLD STAKE ON
CORNER AND STUMPS OF BEARING TREES.
COR VAR 6-47

ESTABLISHED WEST QUARTER CORNER OF SEC 35 AT A POINT IN A TRUE LINE BETWEEN AND EQUI-DISTANT FROM THE SW AND NW CORNERS OF SAID SECTION. IT BEING DISTANT FROM EACH 2659.8'

1870 RUGER AUG REMON-64 WEST ON NORTH LINE OF NE 1/4

SEC 35 ON A VAR 7-10 OFFSET SOUTH 15.51'

COULD FIND NO TRACE OF NORTH QUARTER

CORNER. CONTINUED WEST ON SAME

VARIATION AS ABOVE GIVEN AT

5239.74 INTERSECTED WEST BOUNDARY LINE 29.04'
SOUTH OF CORNER. COR VAR 7-01
ESTAHBLISHED NORTH QUARTER CORNER AT A
POINT IN A TRUE LINE BETWEEN AND EQUIDISTANT FROM THE NE & NW CORNERS OF SAID
SECTION IT BEING DISTANT FROM EACH 2619.87'

1870 RUGER AUG 18 REMON-69 WEST ON NORTH LINE OF NE 1/4 SEC 34 ON A VAR 7-20 OFFSET SOUTH 14.52' AT

2627.79 INTERSECTED QUARTER LINE 27.06' SOUTH OF QUARTER CORNER. FOUND OLD STAKE AT CORNER. ALSO FOUND STUMP OF NORTH BEARING TREE. COR VAR 7-04'

WEST ON NORTH LINE OF NW 1/4 SEC 34 ON A VAR 6-45 OFFSET NORTH 9.24' OFFSET SOUTH 28.71' OFFSET NORTH 1.32' OFFSET NORTH 3.63' AT

2620.53 INTERSECTED WEST BOUNDARY LINE 13.86'
SOUTH OF CORNER FOUND OLD STAKE AT
CORNER ALSO FOUND STUMP OF WEST BEARING
TREE COR. VAR 6-46'

1870 RUGER AUG REMON-68 SOUTH ON WEST LINE OF NW 1/4
SEC 26 ON A VAR 8-00 AT

2662.52 INTERSECTED QUARTER LINE 9.9' EAST OF QUARTER COR. COR VAR 7-47 AUGUST 19

SOUTH ON WEST LINE OF SW 1/4 SEC 26 ON A VAR 7-55 OFFSET EAST 12.71' AT

2654.52 INTERSECTED SOUTH BOUNDARY LINE 13.04' EAST OF CORNER.

- 1928 PARSONS BK 10 PG 46 ASSESSORS PLAT SHEET 2 OF 7.
- 1966 BATTERMAN VOL 4 PG 296 FD CUT STONE. 2633.50 TO N 1/4 COR SEC 34. WESTERLY 289.32 TO PIPE IN RR R/W LINE.
- 1971 COMBS SUB #3038
- 1977 COMBS SUM #2192 ASSESSORS PLAT SHEET 2. STATES NOTHING ABOUT MON. S89-58-30W 289.32 TO CENTER OF R/R.
- 1978 COMBS #5262 FD CUT STONE MON. S89-58-30W 1316.43
  TO SET 3/4 REROD @ 1/16TH COR & SO1-40W 726.26 TO
  SET 3/4 REROD ON WEST RAILROAD R/W. S89-58-30W
  385.60 TO SET 3/4 REROD ON WEST RAILROAD R/W

SHEET 2 OF 5

CORNER CODE V-17(1)

Bang

Oct 20,2011

## **UN609 NECORSEC34**

- 1979 SHEARMAN #5213 STATES NOTHING ABOUT MON. S89-32-49E 2623.53 TO S 1/4 COR SEC 26 & NO-13-57W 2659.23 TO W 1/4 COR SEC 26
- 1981 SCHROEDER CSM VOL 10 PG 329 STATES NOTHING ABOUT MON.
- 1985 BARNES V-17 FD CUT LIMESTONE IN SMALL MOUND. STONE IS 1' ABOVE GRADE. SET CARSONITE POST & REFERENCED SAME. 282,548.92; 2,190,919.81 ELEV 891 FB#2 PG 4
- 1985 BARNES VOL 6 PG 337 S89-29-08W 2633.05 TO 5 1/4 COR SEC 27 & N1-08-54W 2659.60 TO E 1/4 COR SEC 27
- 1985 BARNES VOL 6 PG 338 S89-29-08W 2633.05 TO N 1/4 COR SEC 34, S0-27-59E 2669.81 TO E 1/4 COR SEC 34, ANGLE 89-57-07 FROM E 1/4 TO N 1/4 COR SEC 34
- 1986 BARNES VOL 6 PG 340 N89-30-44E 2623.95 TO S 1/4 COR SEC 26, SD-27-59E 2669.81 TO W 1/4 COR SEC 35, ANLE @ SW COR SEC 26 FROM W 1/4 TO S 1/4 COR SEC 26 90-39-40 [SHEAMN 90-41-08]
- 1986 THOM CSM VOL 12 PG 402 FD LS. STATES NOTHING ABOUT MONUMENT AT E 1/4 COR SEC 27
- 1986 COMBS CSM VOL 12 PG 411 STATES NOTHING ABOUT MON.
- 1987 COMBS CSM VOL 12 PG 563 FD LS. STATES NOTHING ABOUT MONUMENT AT E 1/4 COR SEC 27
- 1995 COMBS CSM VOL 18 PG 126 LS USED E 1/4 COR SEC 27 FOR LINE & WENT 1368.79
- 1997 PLB #8625

Oct 20,2011

- 1997 COMBS CSM VOL 20 PG 236 CUT STONE 2659.56 TO E 1/4
- 1998 KNUDSON #8178 FD SQUARE MON. S89-59-32E 2623.70 TO SQUARE MON @ N 1/4 COR SEC 35.
- 1999 KNUDSON #7227 FD SQUARE MON. S89-59-32E 2623.70 TO SQUARE MON @ N 1/4 COR SEC 35.
- 1999 WAS SUB #13134 ASSESSORS PLAT SHEET 2 & SHEET 7.
  PAPER IN RDS
- 2003 COMBS CSM VOL 26 PG 259 STONE 2659.61 TO FD PK @ W 1/4 COR EC 26
- 2006 COMBS CSM VOL 30 PG 223 STATES NOTHING ABOUT MON. 2659.26 TO ALUM @ E 1/4 COR SEC 27
- 2007 COMBS SUB #14935 ASSESSORS PLAT SHEET #7 FD CUT LS. S89-34-06E 2623.56 TO CUT LS @ S 1/4 COR SEC 26 & NO-12-51W 938.83 TO FD PIN
- 2007 COMBS #15616 SIZE 2 SEC 27 MICRO 2/1 EVANS
- 2008 COMBS #16202 FD LIMESTONE. NO-13-28W 2669.26 TO ALUM SPIKE @ E 1/4 COR SEC 27.

ACCEPTED CUT LIMESTONE THAT I FOUND AND REFERENCE MONUMENTS.

SHEET 3 OF 5

CORNER CODE V-17(1)

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location? ACCEPTED GUT LIMESTONE.
D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least of the witness monuments shown on the drawing in (a), above.  NDNE
(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.
I, <b>Donald Barnes</b> , hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.
SHEET 4 OF 5  CORNER CODE V-17(1)
OCT 20,201/ CORNER CODE V-17(1)

CORNER CODE V-17(1) A.E. 7.08 REQUIREMENT

