
Paper weight-110# (minimum)

Black nonfading ink required

LAND U.S. SURVEY **PUBLIC** MONUMENT RECORD

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT For Public Land Survey Corners In: T. 4 N. R. 10 E. 4th P.M. REV 10/23/2004 USMONREC.DWG CORNER CODE INDEX



UNION TWP **ROCK COUNTY WI**

IF AVAILABLE ROCK COUNTY COORDINATES PERFERRED

North	Elev
East	
Hor. Datum	Vert. Datum
LATITUDE _	ELLIPS. HT
LONGITUDE	
NAD83(91)	NETWORK ADJ. YR 2010
GPS (X)	TRAVERSE (X) X
BASED ON TH	E FOLLOWING CONTROL:

◆ CORNER MONUMENT

WITNESS MONUMENT

(a) ROCK COUNTY PROJECTION BEARINGS ARE BASED ON:

FIELD BOOK PAGE #	1		3
OR OBSERVATION SHEET SHEET		_ OF	
SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROU	NDING		
PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.			(z)
PLANNING & ZONING COMMITTEE ADOPTED THIS FORM ON 12/2/1982	. 1	10.1	

UN610 N1/4CORSEC35

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1833 HARRISON TAN RIDE 4TH MER. EAST ON RANDOM BET

26 & 35

660.00 CREEK 13.2' CRS S.W.

2640.00 TEMPY 1/4 SEC COR

3300 LEAVE PRAIRIE & ENTER TIMBER

5203.44 INT. E BDY N OF P IN W. EDGE OF PRAIRIE LAND 1ST 1/2 LEVEL & WET 3 RATE 2ND 1/2 LEVEL 2ND RATE WITH BURR O

RATE 2ND 1/2 LEVEL 2ND RATE WITH BURR D

WEST COR WEST BET SECS 26 & 35

1232.88 BURR 0 12 IN DIAM

2601.72 QUARTER SEC. COR. IN MARSH - POST & RAISED MOUND

5203.44 INT SEC COR.

- 1856 CHURCH VOL 1 PG 63 STATES NOTHING ABOUT MON. USED TO SUBDIVIDE SEC 26. 2655.84 TO CENTER OF SEC 26 & 5311.68 TO N 1/4 COR SEC 26
- 1865 LOCKE VOL 1 PG 232 & #5199 FD OLD POST IN MOUND 2656.83 TO CENTER OF SEC 35 & 5313.66 TO N 1/4 COR SEC 26
- 1870 RUGER AUG REMON-64 WEST ON NORTH LINE OF NE 1/4 SEC
 35 ON A VAR 7-10 OFFSET SOUTH 15.51' COULD
 FIND NO TRACE OF NORTH QUARTER CORENR.
 CONTINUED WEST ON SAME VARIATION AS ABOVE
 GIVEN AT
 - 5239.74 INTERSECTED WEST BOUNDARY LINE 29.04'
 SOUTH OF CORNER. COR VAR 7-01
 ESTABLISHED NORTH QUARTER CORNER AT A
 POINT IN A TRUE LINE BETWEEN AND EQUIDISTANT FROM THE NE & NW CORNERS OF SAID
 SECTION IT BEING DISTANT FROM EACH 2619.87'
- 1902 UNKOWN VOL 3 PG 11 MONUMENT.
- 1962 BATTERMAN VOL 4 PG 146 FD MON.
- 1972 COMBS #5272 FD CUT STONE MON. 2623.20 TO FD CUT STONE @ NE COR SEC 35
- 1979 SHEARMAN #5213 STATES NOTHING ABOUT MON. N89-32-46W 2623.53 TO SW COR SEC 26 & NO-00-10E 2662.72 TO R/R SPIKE @ CENTER OF SEC 26.
- 1981 COMBS #5276 FD CUT STONE. SO-O1-40W 922.71 TO SET PIN ON SOUTH RAILROAD R/W
- 1985 BARNES V-19 FD CUT LIMESTONE 1.5' ABOVE GROUND. SET CARSONITE POST. REFERENCED SAME. 282,571.15; 2,193,543.56 ELEV 892. ON LINE N/S FENCE LINE. FB#2 PG 10. SOUTH REFERENCE PIPE IS STA 108.
- 1986 COMBS #13389 FD CUT STONE MON. EAST 477.60 TO PIN.
- 1988 COMBS CSM VOL 13 PG 240 STATES NOTHING ABOUT MON.
 NORTH 1863.89 TOWARDS CENTER OF SEC 26
- 1988 COMBS CSM VOL 13 PG 242 STATES NOTHING ABOUT MON. NORTH 1863.89 TOWARDS CENTER OF SEC 26
- 1990 COMBS CSM VOL 14 PG 487 FD STONE. USED R/R SPIKE @ CENTER OF SEC 26 FOR LINE
- 1993 BIRRENKOTT CSM VOL 16 PG 378 FD CUT STONE. N89-23-12E 2622.52 TO STONE @ SE COR SEC 26 & NO-56-20W 2662.11 TO FD ALUM @ CENTER OF SEC 26
- 1996 BARNES VOL 6 PG 340 S89-30-44W 2623.95 TO SW COR SEC 26, NO-56-14W 2662.41 TO CENTER OF SEC 26, & 5326.02 TO N 1/4 COR SEC 26

SHEET 1 OF 3

Oit 201/

CORNER CODE V-19(金)

_

UN610 N1/4CORSEC35

- 1998 KNUDSON #8178 SQUARE STONE MON. N89-59-32W
 2623.70 TO SQUARE MON @ NW COR SEC 35, N89-52-41E
 2622.82 TO SQUARE STONE @ SW COR SEC 25, SO-06-11E
 5317.51 TO SQUARE STONE MON @ S 1/4 COR SEC 35, NO26-16W 2662.31 TO ALUM @ CEN OF SEC 26.
- 1999 KNUDSON #7227 SQUARE STONE MON. N89-59-32W
 2623.70 TO SQUARE MON @ NW COR SEC 35, N89-52-41E
 2622.82 TO SQUARE STONE @ SW COR SEC 25, SO-06-11E
 5317.51 TO SQUARE STONE MON @ S 1/4 COR SEC 35, NO26-16W 2662.31 TO ALUM @ CEN OF SEC 26.
- 2003 WIDOT V-19(1) CUT LIMESTONE PROJ 5155-00-22 SHEET 4.4 DATE 4-10-2003 302,037.760; 424,395.950 NO-18-03W 2581.29 TO T.I.
- 2003 WIDOT #25087, 25290, & 25289 USH 14 CUT LIMESTONE PROJ 5155-00-22 SHEET 4.4 DATE 4-10-2003 302,037.760; 424,395.950 NO-18-03W 2581.29 TO T.I.
- 2004 WIDOT #25366 USH 14
- 2007 COMBS SUB #14935 ASSESSORS PLAT SHEET #7 FD CUT LS N89-34-06W 2623.56 TO CUT LS @ SW COR SEC 26

ACCEPTED MY 1985 TIES FOR THE CUT LIMESTONE & USED MY OBSERVATIONS IN THE TWP ADJUSTMENT.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FD PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

NONE

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

YES, IN 1870 RUGER DECLARED THE CORNER LOST & PLACED THE CORNER ON LINE WITH THE SW & SE CORNERS OF SEC 26 & MIDWAY BETWEEN THEM.

I, **Donald Barnes**, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

SHEET 2 OF 3

CORNER CODE V-19(

A.E. 7.08 REQUIREMENT

(2)

S 1/4 COR SEC 26 UNION TWP T4N R10E

DBSERVATION SHEET #891 1985 BARNES V-19 FB#2 PG 10

CUT LIMESTONE 1.5'

ABOVE GRADE / CARSONITE
POST

O 1985 SET O 1 5/8X24 PIPE

> EMBOSSED SEAL Danes Oct 20, 2011

