

U.S. PUBLIC LAND AND SURVEY MONUMENT RECORD

For Public Land Survey Corners in the

T. 1 N., R. 13 E

CORNER CODE INDEX

TURTLE TWP

ROCK COUNTY WI

A	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36		
B																																						
C																																						
D																																						
E																																						
F																																						
G																																						
H																																						
I																																						
J																																						
K																																						
L																																						
M																																						
N																																						
O																																						
P																																						
Q																																						
R																																						
S																																						
T																																						
U																																						
V																																						
W																																						
X																																						
Y																																						
Z																																						

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

GPS (x) _____ TRAVERSE (x) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL \blacklozenge AT PROPER LOCATION ON ABOVE INDEX

\blacklozenge CORNER MONUMENT

\bigcirc WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

FIELD BOOK _____ PAGE # _____

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH. THE CORNER MONUMENT SHALL HAVE THE FOLLOWING CHARACTERISTICS: 1) HAVE A LEAST TWO PREDETERMINED BREAK-OFF POINTS. 2) IF BROKEN LEAVE A PERMANENTLY MAGNETIZED REMNANT AT THE ORIGINAL POINT. 3) MUST BE EXTENDABLE. 4) THE CAP IS INSCRIBED "ROCK COUNTY SURVEY MONUMENT - PENALTY FOR DISTURBING MARKER". 5) OR AN EXISTING CUT LIMESTONE. AN IRON PIPE 1 1/2" X 4" MINIMUM MAY BE USED IN AREAS WHERE GROUND WATER IS WITHIN ONE FOOT OF THE SURFACE. IF THE CORNER IS OCCUPIED BY AN IMPROVEMENT (MANHOLE, BURIED CABLE, ETC) AND DURABLE, DISTINCT MONUMENT MAY BE USED. CORNERS SHALL BE REFERENCED WITH AT LEAST 4 DURABLE WITNESS MONUMENTS. WITNESS MONUMENTS SHALL BE MADE OF CONCRETE, NATURAL STONE, IRON OR OTHER EQUALLY DURABLE MATERIAL EXCEPT WOOD. DESCRIBE THE CORNER AND THE WITNESS MONUMENTS.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/21/1982
WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

SHEET 1 OF 2

CORNER CODE

P25

TU580

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1867 LOCKE VOL 1 PG 283 5308.25 TO W 1/4 COR SEC 24 & 2644.12 VAR 7-08 TO NE & SE CORNERS OF SEC 24. CORNER LOST. SET STAKE FROM CORNERS OF SECTION & SURROUNDED IT BY 3 HH & AFTER WARDS FOUND REMAINS OF BTS AGREEING WITH CORNER AS SO SET.

1868 LOCKE VOL 1 PG 324 CALLS FOR THE COR. TO BE 1.82' SOUTH OF THE W 1/4 COR SEC 19.

1971 LEE VOL 4 PG 516 DUG & FOUND HH 10X12X15. SET CI WITH STONE ON WEST SIDE. SHOWS 3.0' SOUTH OF E/W FENCE & ON LINE WITH N/S FENCE.

1976 BARNES VOL 5 PG 221 FOUND CI AT W 1/4 COR SEC 19. SHOWS REC 1.82 TO EAST 1/4 COR SEC 24. 2648.44 FROM CI TO SE COR SEC 24.

1980 BARNES VOL 6 PG 81 CALLS FOR 2640.11 TO NE COR SEC 24.

FOUND CI MON. 2640.14 TO NE COR SEC 24 & 2650.62 TO SE COR SEC 24. THE CI MON IS .16' WEST OF A LINE BETWEEN THE SE & NE CORNERS OF SEC 24.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FOUND PERPETUATED LOCATION

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

LOCKE'S CALL FOR TWO DISTINCT CORNERS AT THE E 1/4 COR SEC 24 & THE W 1/4 COR SEC 19 IS BASED ON HIS DETERMINATION THAT THERE ARE TWO DISTINCT CORNERS AT THE NE COR OF SEC 24 AND THE NW COR OF SEC 19. THE ORIGINAL GOVERNMENT SURVEY FOR THE TOWNSHIP LINE, CLINTON TOWNSHIP, & TURTLE TOWNSHIP CALLS FOR A COMMON CORNER. THEREFORE THE 1/4 CORNER BETWEEN SEC 24 & 19 IS THE SAME AND THERE ARE NOT TWO AS LOCKE CALLS FOR.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

NO

I, Donald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on, 1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.

COUNTY SURVEYOR FILING DATA

seal

Date of computer entry _____

Donald Barnes
OCT 6, 1995

Date microfilmed _____

Number of included sheets _____

CORNER CODE

EMBOSS LAND SURVEYOR SEAL

A-E 7.08 REQUIREMENT

N 1/4 COR
SEC 24

NE COR
SEC 24

S87-55-01E 2644.73

S0-05-25W 2650.63

S0-05-49W 2640.14

S44-09-59E 3815.60

E 1/4 COR
SEC 24

FD CI


N46-11-34E 3687.09

N0-01-32E 5289.34

S87-52-52E 2658.51

SE COR
SEC 24

S 1/4 COR
SEC 24



Donald Barnes
Oct 6, 1995

P25