

PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in the


T. 1 N., R. 13 E.

CORNER CODE INDEX

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
A																									
B																									
C																									
D																									
E																									
F																									
G																									
H																									
I																									
J																									
K																									
L																									
M																									
N																									
O																									
P																									
Q																									
R																									
S																									
T																									
U																									
V																									
W																									
X																									
Y																									
Z																									

PLACE MONUMENT SYMBOL (●) AT PROPER LOCATION ON ABOVE INDEX

EXAMPLE



TURTLE TWP
ROCK COUNTY WI

IF AVAILABLE
STATE PLANE COORDINATES

North (Y) 21,545.52 Elev. (Z) _____
 East (X) 506,639.56 Zone _____
 Hor. Datum COUNTY Vert. Datum _____

◆ CORNER MONUMENT

○ WITNESS MONUMENT

BEARINGS ARE BASED ON:

TU585

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1836 LYON SET POST CORNER TO SECTIONS 20,21,28,&29 & MADE MOUND OF EARTH & SOD. CALLS FOR 2658.15 TO S 1/4 COR SEC 21,2640 TO S 1/4 COR SEC 20,& 2640 TO W 1/4 COR SEC 28 & W 1/4 COR SEC 21.

1911 KERCH VOL 3 PG 64 FOUND REMAINS OF CHARRED STAKE. SET 2" GAS PIPE FILLED WITH CEMENT. CALLS FOR 2666.4 TO E 1/4 COR SEC 29,2647.8 TO S 1/4 COR SEC 20,2651.0 TO E 1/4 COR SEC 20,& AN ANGLE OF 89-53-30 FROM THE S 1/4 COR SEC 20 TO THE E 1/4 COR SEC 20.

1994 BARNES VOL 6 PG 442 CALLS FOR 2647.76 (REC 2647.8) TO S 1/4 COR SEC 20,2651.88 (REC 2651.0) TO E 1/4 COR SEC 20,& AN ANGLE OF 89-53-38 (REC 89-53-30) FROM S 1/4 COR SEC 20 TO E 1/4 COR SEC 20.

FOUND PK & REFERENCED SAME.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FOUND PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

NO

I, Donald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on,1994, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.

COUNTY SURVEYOR FILING DATA

Date of computer entry _____

Date microfilmed _____

Number of included sheets _____
CORNER CODE

seal
Donald Barnes
6/13/95

EMBOSS LAND SURVEYOR SEAL

A-E 7.08 REQUIREMENT

R9

