

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 2 N., R. 11 E

CORNER CODE INDEX

A	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
B																									
C	6					5					A				3						2			1	
D																									
E																									
F																									
G	7					8					9				10						11			12	
H																									
I																									
J																									
K	13					11				15				15							14			13	
L																									
M																									
N																									
O																									
P	18					20				21				22							23			24	
Q																									
R																									
S																									
T	30					29				28				27							26			25	
U																									
V																									
W																									
X	31					32				33				34							35			36	
Y																									
Z																									

PLYMOUTH TWP

ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 2

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE T-5

PL595

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1833 HARRISON NORTH BET SECS 29 & 30

1326.6 LEFT TIMBER & ENTER PRAIRIE
2640 QUARTER SEC COR ON GROUND ASCENDING N. SET
POST & RAISED MOUND.
5280 SEC COR TO SECS 19,20,29,30 SET POST & RAISED
MOUND. LAND HIGH ROLLING 1ST RATE PRAIRIE
GROWTH GRASS & WEEDS.

1868 LOCKE PG 62 NORTH BETWEEN SECS 29 AND 30 VAR 7-10
OFF 19.14'

1327.92 FENCE RUNNING EAST
2652.54 INTERSECTED 1/4 LINE 13.53' WEST OF COR. FOUND
LARGE LIMESTONE SET FOR COR. 4 INCHES WEST
OF FENCE POST AT ANGLE OF ROAD AND ON SOUTH
SIDE THERE OF. VAR CORRECTED 7-17

CONTINUED NORTH FROM 1/4 COR WITH VAR 7-10

5304.75 INTERSECTED NORTH BOUNDARY 3.63' EAST OF
COR. FOUND STAKE SET BY SELF. (SEE CO.
SURVEYOR RECORD) SEC 20) VAR CORRECTED 7-15
SEPT 9 1868

1869 LEE VOL 2 PG 5 FD MON 2655.18 VAR 7-20 TO SE COR SEC
30 & 2647.26 VAR 30 TO CENTER SEC 30

1976 COMBS CSM VOL 6 PG 113 FD CUT STONE

1978 BARNES VOL 5 PG 425 FD CUT L.S. 0.5' ABOVE GROUND.
REFERENCED SAME. SOUTH OF STH 213

1992 BARNES VOL 6 PG 430 FD CUT L.S. SO-00-26E 2653.76 TO
E 1/4 COR SEC 30 & S89-31-1W 2655.52 TO N 1/4 OF SEC 30

FD CUT L.S. TOP 15" IS BROKEN OFF. REMAINING PART IS 3"
DEEP. PLACED 2 MAGNETS 15' DEEP ON NORTH SIDE OF L.S.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FD CUT L.S. AS THE PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, Donald Barnes, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Seal

Donald Barnes

Emboss

1-03-03



SHEET 1 OF 2

CORNER CODE T-5

A.E. 7.08 REQUIREMENT

N

ROCK COUNTY
PROJECTION



OBSERVATION SHEETS
254 & 32

3/4X24" REROD/
PLASTIC CAP

CARSONITE BOUNDARY POST
PLACED TOP OF CUT
L.S. BY CARSONITE

FD TOP 15" OF STONE
BROKE OFF. FD BOTTOM 1/2
OF CUT L.S. SET 2
MAGNETS ON NORTH SIDE
15" DEEP. STONE IS
3" DEEP.



STH 213

N23-01E 48.51

S70-50-38E 86.35

N11-15-26E 116.51

S66-18-34E 82.61
EDGE OF BANK

N23-37-21E 71.79

S25-20-52E 109.50

S33-53-54E 172.19

S62-27-58E 71.68

WPL N
2-11-30
51/28

ANT
N1-20-12W 43,932'

N60-43-14W 9,198'
ORFORDVILLE WATER TANK

ANT.
N80-14-38W 19,560'

N19-45-29E 47,357' ANT
N20-50-16E 24,873' CELL TOWER
N36-07-05E 35,413' RED/WHITE ANT.

FARM FIELD

SHEET 2 OF 2

T-5

EMBOSSED SEAL

Donald Barnes

1-03-03