

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners In:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 2 N. R. 11 E.

CORNER CODE INDEX

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
A																									A
B																									B
C																									C
D																									D
E																									E
F																									F
G																									G
H																									H
I																									I
J																									J
K																									K
L																									L
M																									M
N																									N
O																									O
P																									P
Q																									Q
R																									R
S																									S
T																									T
U																									U
V																									V
W																									W
X																									X
Y																									Y
Z																									Z

PLYMOUTH TWP

ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25
PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON: _____

OBSERVATION SHEETS 1799 7705

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 3

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE V-15

PL608

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1833 HARRISON EAST ON RAND. BET 27 & 34

2640 TEMPY 1/4 P

5246.34 INT E. BDY 31.68' N OF P LAND ROLLING 1ST RATE WITH GOOD TIMBER W.O. & BLK O. ASPEN, LYNN, HICKY, WALNUT ASH CHERRY & ? OF P. ASH VINES ??

DDR. WEST

2623.17 QUARTER SEC COR {W.O. 24 N5W 13.86' W.O. 16 S88E 73.92' W.O 24 W.O. 16}

5246.34 INT. W BDY AT P.

1837 TWP ROAD RECORDS BK 1 PG 29 COMMENCING 726' WEST OF THE N 1/4 COR SEC 34 T2 R11; THENCE RUNNING S48E 3531' TO A POST THENCE S65E 4620' TO A POST; THENCE S78 1/2 E 775.5' TO A POST 825' EAST OF THE S 1/4 COR OF SEC 35 ON THE TOWN LINE BETWEEN PLY. AND NEWARK AND THE ABOVE RD IS HEREBY ORDERED TO BE OPENED AND WE THE SUPERVISORS HAVE ALSO TAKE UP AND ALTERED THE TERRITORIAL RD LEADING FROM THE NE COR OF SEC 32 RUNNING EAST ON THE SEC LINE OF 33 AJND 34 TO A PT 726' WEST OF THE N 1/4 COR SEC 34 TO THE COMMENCEMENT OF THE ABOVE DESCRIBED RD; THENCE FOLLOWING SAID RD TO THE TOWN LINE OF NEWARK TO A PT WHERE THE ABOVE DESCRIBED RD ENDS AND THE SAID RD IS HEREBY ORDERED TO BE OPENED, 66' IN WIDTH

1844 PEASE TWP RD RECORDS BK 1 PG 4 COMMENCING AT THE CORNERS OF SEC 26,27,34 AND 35, IN T2N R11E AND RUNNING WEST ON THE LINE BETWEEN SECTIONS 27 & 34, 2622.84'. SET POST WHERE OLD 1/4 POST ON SAID LINE STOOD BURNT STUMP OF WHITE OAK BEARS N5W 13.86' AND S88E 73.92'; THENCE WEST ON SAID LINE 2622.84' TO THE CORNER OF SEC 27,28,33, & 34, SET POST WHITE OAK 24 INCHES IN DIA BEARS S35E 114.18', BURNT STUMP OF BASS WOOD 24" N78E 86.46'; THENCE WEST ON LINE BETWEEN SECS 28 AND 33 TO CORNER OF SEC 28,29,32 & 33 5224.5' SETTING POST IN OLD MOUND; THENCE WEST ON LINE BETWEEN SECTIONS 29 & 32, 2652.8' SET POST BY BLACK OAK 24 INCH BEARS N26E 27.06'; THENCE WEST ON THE LINE BEFORE SAID 2642.64' TO THE COR OF SEC 29,30,31 & 32, BLACK OAK BEARS N41E 78? AND N22W 97.02'; THENCE WEST OF LINE BETWEEN SEC 30 & 31, 5297.16' TO THE LINE BETWEEN RANGES 10 & 11 EAST 4 MILES AND 5.94'. SAID RD EXTENDS 33' ON EACH SIDE OF THE ABOVE LINE.

1868 LOCKE PG 13 EAST BETWEEN SECS 27 AND 34 VAR 6-18

2638.68 INTERSECTED 1/4 LINE 21.12' NORTH OF COR. FOUND WHERE BTS WERE DUG OUT AND STAKE COR IN CENTER OF HIGHWAY AND IN LINE OF FENCE FUNNING NORTH VAR CORRECTED 5-50

CONTINUED EAST WITH VAR 5-20

5288.25 INTERSECTED EAST BOUNDARY 23.43' SOUTH OF COR. VAR CORRECTED 5-50

1873 RUGER VOL 2 PG 114 STONE MON

1874 RUGER VOL 2 P G122 STONE MON. VAR 5-30 726 TO HH IN CENTER OF RD TO THE WEST.

1876 RUGER VOL 2 PG 206 STONE MON. VAR 5-44 2659.14 TO GEN SEC 27, VAR 5-44 5323.23 TO N 1/4 COR SEC 27, & 2634.06 TO SW COR SEC 27

1965 BATTERMAN VOL 4 PG 222 FD CUT STONE MON & REF SAME. NOTE: TIES REMOVED SEE PG 261 VOL 4.

1965 WIDOT PROJECT 811-01(1) STATES NOTHING ABOUT MON. *

1966 BATTERMAN VOL 4 PG 261 FD PK O.13 N. REF. COR

1966 BATTERMAN VOL 4 PG 283 REF. COR. 889-47E TO SE COR SEC 27 & N89-32W TO SW COR SEC 27

SHEET 1 OF 3 CORNER CODE V-15

Donald Barnes

6-17-03

PL608

1978 BARNES VOL 5 PG 473 1318.97 TO N/S FENCE TO THE WEST
& 2637.95 TO NW COR SEC 34.
1981 COMBS GSM 10-285 PIPE IN MON BOX
1983 LEUENBERGER MAP #04348 MON. BOX
1984 COMBS MAP #13829 FD PIPE IN MON. BOX.
1989 COMBS MAP #12293 FD PIPE USED TO SUBDIVIDE SEC 34.
1990 COMBS GSM VOL 14 PG 289 ALUM. 2655.08 TO SW COR
SEC 27
1995 SCHROEDER GSM VOL 18 PG 453 STATES NOTHING ABOUT
MON.

FOUND 1" PIPE IN MON. BOX

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED 1" PIPE IN MON. BOX, WHICH PERPETUATED FD CUT
L.S.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, Donald Barnes, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Seal

Donald Barnes
Emboss


6-17-03

SHEET 2 OF 3

CORNER CODE

V-15

A.E. 7.08 REQUIREMENT



U.S. FED. DISK IN
CONCR. STAMPED
PLYMOUTH #2 1935

1" IP IN
MON. BOX
@ CENTER PVMT

N 1/4 COR
SEC 34
PLYMOUTH TWP
T2N R11E

PLYMOUTH/CHURCH RD

N32-38-54E 43.332
FAR ANT.

CELL TOWER
N9-02-07W 26,544
ANT.
N16-40-17W 48,946
ANT.

MICRO TOWER
S40-44-18E 4,622

ORFORDVILLE TANK
N70-27-42W 22,325
3/4X24 REROD/
PLASTIC CAP
ON LINE WITH SOUTH
PVMT EDGE PROJ. FROM
WEST; ON LINE WITH SOUTH
PVMT EDGE PROJECTED FROM EAST

6-17-03
EMBOSSED SEAL
Donald
Barnes

SHEET 3 OF 3
V-15

NOT TO SCALE
OBSERVATION SHEET 179