

Paper weight-110# (minimum)

Black nonfading ink required

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners In:
T. 4 N. R. 11 E. 4th P.M.

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT
REV 10/23/2004 USMONREC.DWG

CORNER CODE INDEX

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
A																									
B																									
C		6																							
D																									
E																									
F																									
G																									
H																									
J																									
K																									
L																									
M																									
N																									
O																									
P																									
Q																									
R																									
S																									
T																									
U																									
V																									
W																									
X																									
Y																									
Z																									

PORTER TWP
ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

NAD83(91) _____ NETWORK ADJ. YR _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

BEARINGS ARE BASED ON: _____

FIELD BOOK _____ PAGE # _____

SHEET 15 OF 2

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THIS FORM ON 12/2/1982

CORNER CODE C-24

PD2519 S1/16TH NE1/4SEC1

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

- 1874 RUGER VOL 1 PG 128 SUBDIVIDED SEC 1. @ GEN OF SEC 1
DROVE STAKE & PUT ON TOP OF IT HH 23X9X9
SURROUNDED BY 4 HH.
- 1886 RUGER VOL 2 PG 284 SET HH 12X8X5 SURROUNDED BY 4
HH @ S 1/16 TH COR OF NE 1/4 SEC 1.
- 1971 LEE VOL 4 PG 508 DUG & FD HH 12X8X5 SURROUNDED BY
4 HH. REFERENCED SAME

FD NW & NE REF. PIPE. N/S FENCE LINE IS GONE. E/W FENCE &
REF. PIPES ON SOUTH SIDE ARE GONE.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FD PIPES.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

NONE

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, **Donald Barnes**, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Donald Barnes

Seal

Barnes


Emboss

May 6, 2009

SHEET 1 OF 2

CORNER CODE C-24

A.E. 7.08 REQUIREMENT



S 1/16TH
 CDR
 SEC 1
 PORTER TWP
 T4N R11E

OBSERVATION SHEET #953

STEBBINSVILLE RD

N89-21-08E 1277.40
 1874 RUGER 1278.09

S81-30-59E 98.36

SET 3/4X24 REROD

FD 1" PIPE

1971 28.37
 N1-45-36W 28.37

N13-31-20W 18,146'
 CELL

1971 49.84
 S89-54-20E 49.85

1971 58.15
 S60-43-16E 58.15

S89-23-26W 3977.87
 1874 RUGER 3976.17

S64-40-06E 523.32

N86-52-57E 144.79

FD 1" PIPE
 PUSHED TO GRADE
 66.05' E75-15-33

SHEET 2 OF 2

SET 3/4X24 REROD

Donald
 EMBOSSED
 SEAL
James
 May 6 2009

C-24

NOT TO SCALE