
U.S.

PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in: T. \(\Lambda \), R. \(\Lambda \)E

CORNER CODE INDEX



WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

BELUIT TWP

ROCK COUNTY WI

IF AVAILABLE ROCK COUNTY COORDINATES PERFERRED

North 201,092,92 Elev.

Hor. Datum OONTY Vert. Datum

East 702,377,70

LATITUDE _____ELLIPS. HT.

LONGITUTE

GPS (X) ___

TRAVERSE (X)

BASED ON THE FOLLOWING CONTROL:

♦ CORNER MONUMENT

O WITNESS MONUMENT

BEARINGS ARE BASED ON:

(a)

					1	
FIELD	воок	PAGE #			SHEET	OF _/
SHOW	A PLAN VIEW	DRAWING DEPI	CTING THE C	ORNER MONUMEN	T AND SURROUNDING	3
PHYSIC	CAL FEATURES	, INCLUDING THE	EXCAVATION	N AREA AND DEP	TH.	
PLANNIN	IG & ZONING CO	MMITTEE ADOPTED	THE ABOVE FO	RM ON 12/2/1982		1
						111

CORNER CODE 2 15/16

NW 6 4015 ILL4015

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

183? ORIGINAL PLAT 4214.76 TO SW COR SEC 6.

1907 THISSANDIER SET CONCRETE MONUMENT WITH BRASS PLUG. 5409.44 TO NE COR SEC 6, 5300.00 TO NW COR SEC 1, CLOCKWISE ANGLE OF 180-22-31 (THOM'S COPY) (180-22-26 OTHER COPY) FROM NE COR SEC 6 TO NW COR SEC 1, ANGLE 90-05-32 FROM NE COR SEC 6 TO SW COR SEC 6 & 90-16-34 FROM SE COR SEC 1 TO NW COR SEC 1. LAT 42-30-20.42 LONG 89-04-50.37.

1939 SHIMEALL CITY OF BELOIT NOTES FOUND STONE WITH PLUG IN CENTER. CALLS FOR S 1/4 COR SEC 34 397.28 TO THE WEST. REFERENCED TO LIGHT POLES & TREE.

1940 SHIMEALL VOL 6 PG 306 397.30 TO S 1/4 COR SEC 34.

1940 SHIMEALL MAP #11937 337.02 TO S 1/4 COR SEC 34 & 2650.71 TO N 1/4 COR SEC 1.

FOUND 1" PIN. MEASURED THE FOLLOWING: ANGLE FROM NE COR SEC 6 TO NW COR SEC 1 180-23-10 (REC 180-22-26) 5408.22 (5409.44 REC) TO NE COR SEC 6, 5301.52 (REC 5303.40 & 5300.00) TO NW COR SEC 1, & 396.96 (REC 397.02,397.28,397.30) TO S 1/4 COR SEC 34.

- C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location? DID NOT ACCEPT NOR REJECT FOUND LOCATION.
- D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.
- (E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location. NO

I, Donald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on, established, reestablished, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.

Date of computer entry__

Date microfilmed __

Number of included sheets CORNER CODE

EMBOSS LAND SURVEYOR SEAL

A-E 7.08 REQUIREMENT