

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 1N., R. 11E

CORNER CODE INDEX

A	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
B	6				5					A			3			2					1			
C																								
D																								
E																								
F																								
G	1					8				9			10			11					12			
H																								
I																								
J																								
K																								
L	18					11				16			15			14					13			
M																								
N																								
O																								
P																								
Q	19					20				21			22			23					24			
R																								
S																								
T	30					29				28			27			26					25			
U																								
V																								
W																								
X	31					32				33			34			35					36			
Y																								
Z																								

NEWARK TWP

ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

Fd TIES VOL 4 PG 193

OBSERVATION sheet 546

FIELD BOOK _____ PAGE # _____

SHEET _____ OF _____

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE 911(1)

ne546

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1834 MILLER PG 28 RANDOM BETWEEN 9 & 16
264 ENTER PRAIRIE
5246.34 INTERSECT 1.32' NORTH OF POST
LAND GENTLY ROLLING 2ND RATE TIMBER OAK & HICKORY
OAK & HAZEL U.G.

WEST CORRECTED BETWEEN SEC 9 & 16

2065.14 BUR OAK 12 DIA
2621.52 SET 1/4 SEC POST BUR OAK 12 IN S13W 26.4'; BUR OAK 12 IN
N32W 31.68'
4210.14 BUR OAK 12 IN
5246.34 SEC COR

1871 COLLINS REMONUMENTATION NOTES

PG 182 EAST BETWEEN 9 & 16 VARIATION 5

2640 SET 1/4 STONE BY STUMP OF WITNESS TREE.

CONTINUED EAST VARIATION 4-50

5274.06 SECTION CORNER

1882 HOLMES VOL 2 PG 348 CALLS FOR MON BUT STATE NOTHING. VAR 6-30 2665.08
TO CENTER OF SEC 9 & VAR 6-30 5309.7 TO N 1/4 COR SEC 9

1964 BATTERMAN VOL 4 PG 193 FD CUT STONE. SET MON BOX OVER 1" PIPE &
REFERENCED SAME.

1995 KREBS CSM 18 PG 419 1332.13 TO W 1/16TH COR OF NE 1/4 SEC 16.

1989 BARNES VOL 6 PG 401 FD PIPE IN MON. BOX. S0-08-03W 2664.18 TO FD PIN @
CENTER OF SEC 16, 5309.38' TO S 1/4 COR SEC 16, N89-13-26W 2639.40 (N89-26-36W
2637.82 ERRONEOUS) NW COR SEC 16.

1989 BARNES J-11 FD 1" PIPE IN MON. BOX & 4 REFERENCE TIES.

FD 1" PIPE IN MON. BOX. 2' SOUTH OF CENTER OF PVMT & ON LINE N/S CENTER OF
PVMT. FD REFERENCE PIPES.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found
perpetuated location?


ACCEPTED FD PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the
location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy
on the plan view drawing under (a), above. Show the distances between the corner as previously restored or
reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments
shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including
the directions and distances to other public land survey corners used as evidence or used for proportioning the
corner location.

I, Donald Barnes, hereby certify that the corner location as identified by the corner code index was
determined by me under my direction and control and that this U.S. Public Land Survey Monument Record
is correct and complete to the best of my knowledge and belief.

seal


emboss

Number of included sheets 1

6-29-01

CORNER CODE J-11(1)

A-E 7.08 REQUIREMENT