

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 1 N., R. 11 E

CORNER CODE INDEX

A	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
B	6																							
C		5																						
D																								
E																								
F																								
G	1																							
H		8																						
I																								
J																								
K																								
L	18																							
M		17																						
N																								
O																								
P																								
Q	19																							
R		20																						
S																								
T																								
U	30																							
V		29																						
W																								
X																								
Y	31																							
Z		32																						

NEWARK TWP
ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

OBSERVATION SHEET ~~586~~ 864

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 2

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE P-1 (1)

NE574

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

- 1833 MULLETT PG 10 NORTH ON EAST SIDE SECTION 24
1150.38 BUR OAK 10 IN DIA
2640 SET QUARTER SECTION POST BUR OAK 8 S68W 7.92'; BUR OAK 10 N29W 82.5'
5280 SET POST CORNER SECTIONS 13 & 24 BUR OAK 14 S33W 64.02'; BUR OAK 16 N12W 34.98'
LAND ROLLING SECOND RATE THICKLY TIMBERED WITH BUR WHITE AND BLACK OAK RED ROOT ROSE WILLOW
- 1870 RUGER VOL 2 PG 42 FD OLD STAKE & WHERE STUMPS OF BEARING TREES HAD BEEN DUG UP. SET HH STONE 20X15X9 & SURROUNDED WITH 4 HH. VAR 6-45 2665.41 TO NW COR SEC 19, VAR 6-50 2680.92 TO SW COR SEC 19, & VAR 5-38 2676.3 TO CENTER SEC 19, & 5319.6 TO E 1/4 COR SEC 19.
- 1870 RUGER VOL 2 PG 48 SEE PLAT SEC 29 NEWARK PG 42. VAR 6-39 2670.36 TO CENTER OF SEC 24 7 VAR 6-39 5332.14 TO W 1/4 COR SEC 24.
- 1871 COLLIN'S REMONUMENTATION NOTES
PG 203 NORTH ON WEST LINE OF 19 VARIATION 6
2674.32 SET 1/4 STONE IN PLACE OF STONE SET BY RUGER AGREEING WITH ROOTS OF WITNESS TREES. NOV 3rd 1871
CONTINUED NORTH VARIATION 6-30
- 5346 INTERSECT SECTION LINE 6.6' WEST OF CORNER. SET STONE FOR CORNER OF 18 & 19 IN PLACE OF STONE SET BY RUGER CORRECTED VARIATION 6-39
- 1974 LEE VOL 5 PG 47 FD CUT STONE AT INT. OF N/S FENCE & E/W FENCE GO INT. WEST.
- 1996 HASSE P-1 FD 3X6" CUT LIMESTONE LOCATED 1' EAST OF N/S/W FENCE CORNER. THIS CORNER HAD BEEN PREVIOUSLY SHOWN ON A SECTION SUMMARY SHEET DATED. OCT 1974 BY HUGH LEE. REFERENCED SAME.

FD CUT L.S. & CARSONITE. L.S. IS BROKEN LENGTH WISE. FD HASSE'S TIES.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

THE ORIGINAL GOV. SURVEYOR, MILLER SET A CLOSING CORNER (A POST) AT THE NW & SW CORNERS OF SEC 19. SINCE COLLIN ACCEPTED THE ROOTS OF THE WITNESS TREES, HE MUST OF ACCEPTED THE STANDARD CORNER MULLETT SET AS THE W 1/4 COR OF SEC 19. ACCEPTED FD CUT L.S. AS THE W 1/4 COR SEC 19.

DURING MARCH OF 1833, HARRISON SURVEYED AVON TWP SOUTH OF SUGAR RIVER & IN JANUARY OF 1834, HE SURVEYED THE TWP NORTH OF SUGAR RIVER. HE ALSO HAD A SPECIAL CONTRACT TO SURVEY THE SOUTH LINE OF SEC 36 AVON TWP, WHICH HE DID IN 1834. IN THE 1834 SURVEY HE NOTES WHILE SURVEYING THE NORTH LINE OF SEC 36 HE "INT. THE EAST BOUNDARY IN MARSH 924' ". IS THE "924'" THE DISTANCE TO THE RANDOM STATE LINE? LATER THAT SPRING, MILLER SURVEYED NEWARK TWP. IN THE TOWNSHIPS TO THE NORTH, STANDARD AND CLOSING CORNERS ON THIS LINE ARE DOCUMENTED AND PERPETUATED. MILLER'S FIELD NOTES STATE HE SET POSTS & BEARING TREES WHERE HE CLOSED ON THE AVON/NEWARK TOWN LINE FROM THE STATE LINE TO THE NW CORNER OF SEC 19. SINCE COLLIN ACCEPTED BEARING TREE EVIDENCE AT THE 1/4 CORNERS ALONG THE TOWN LINE FROM THE SW COR SEC 31 TO THE NW COR SEC 19, HE MUST OF CONSIDERED THE AVON AND NEWARK CORNERS TO BE COMMON. SINCE THE ORIGINAL GOV. SURVEYORS SET

SHEET 1 OF 2 CORNER CODE P-1(1)

Paul Bures
7-09-01


NE574

STANDARD AND CLOSING CORNERS ON THIS LINE, DID COLLIN USE THE BEARING TREES AT THE CLOSING CORNERS FOR NEWARK OR AVON TOWNSHIP? HIS MEASUREMENTS SUPPORTS THE NOTION THAT HE USED MULLETT'S CORNERS.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, Donald Barnes, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

seal


emboss

7-09-01

sheet 1 of 2

CORNER CODE **P-1(1)**

A-E 7.08 REQUIREMENT