



(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1874 RUGER VOL 2 PG 129 SET HH 24X9X8. CALLS FOR 1302.84 TO THE NE AND N 1/4 CORNERS OF SECTION 4.  
1973 LEE VOL 5 PG 45 DUB AND FOUND HH 24X9X8 SET BY RUGER. REFERENCED SAME.

FOUND 1" PIPE 0.3' DEEP AND REFERENCE PIPES.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?  
ACCEPTED FOUND PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, Donald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on, SEPTEMBER 8, 1993 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.

seal  
*Donald Barnes*  
*SEP 14, 1993*

COUNTY SURVEYOR FILING DATA

Date of computer entry \_\_\_\_\_

Date microfilmed \_\_\_\_\_

Number of included sheets \_\_\_\_\_  
CORNER CODE

AFFIX YOUR LAND SURVEYOR SEAL

*1 OF 2*

*A12*



*Donald Barnes*  
 Sep 14, 1993

FOUND PIPE LAYING  
 HORIZONTALLY



FOUND PIPE LAYING  
 HORIZONTALLY




3/4 X 24 REROD  
 WITH PLASTIC CAP

BRUSH ROW

STEBBINS VILLE RD

FD PIPE 0.3 DEEP



S37-15-03E 46.51  
 REC 46.44

N4-04-07E 37.06  
 REC 36.81

S16-34-27E 70.63

MAPLE TREE  
 STUMP




N89-59-55E 30.74  
 REC 30.87

FOUND 1" PIPE

FD BENT PIPE  
 RESET

XXXXXXXXXXXXXXXXXXXX



FB # 3 PG 42

2 of 2

A 12