

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners In:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 4 N. R. 12 E. 4th P.M.

REV 10/23/2004

USMONREC.DWG

CORNER CODE INDEX

FULTON

TWP

ROCK COUNTY WI

IF AVAILABLE

ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

NAD83(91) _____ NETWORK ADJ. YR _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

A	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	A
B		6																								B
C			5																							C
D				4																						D
E					3																					E
F						2																				F
G							1																			G
H								7																		H
I									8																	I
J										9																J
K											10															K
L												11														L
M													12													M
N														13												N
O															14											O
P																15										P
Q																	16									Q
R																		17								R
S																			18							S
T																				19						T
U																					20					U
V																						21				V
W																						22				W
X																							23			X
Y																								24		Y
Z																									25	Z

PLACE MONUMENT SYMBOL AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

BEARINGS ARE BASED ON: _____

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 3

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THIS FORM ON 12/2/1982

CORNER CODE J-15(1)

FU548 ^

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1834 (MAR/APR) HARRISON EAST BETWEEN SECS 10 & 15 ON
RANDOM

2112 BROOK 13.2' CRS SOUTH

2640 TEMPY 1/4 SEC COR

5273.4 INT E BDY AT P LAND ROLLING 2ND RATE TIMBER &
SAME AS BEFORE

COR WEST

2636.7 QUARTER SEC COR. {RED O 12 S38W 56.1' RED O
12 N1E 67.98' RED O 12 RED O 12}

5273.4 INT SEC COR.

1848 PIERCE TWP RD BK 1 PG 11 THIS DAY SURVEYED A RD BY
DIRECTION OF THE COMMISSIONERS OF HIGHWAYS,
BEGINNING AT A STAKE ON THE SEC. LINE OF 9 & 16 IN
T4 OF RANGE 12 AND IN THE RD RUNNING NORTH &
SOUTH BEING W. OF THE 1/4 SECTION POST IN 1/4 COR SEC
16) 1361.58 NOW FROM SAID STAKE RUN ON SECTION
LINE N81-15E 2079'; THENCE S58E 528'; THENCE N60E
462'; THENCE N86-15E 660'; N58E 613.8' TO SECTION
LINE OF 15 & 10 THEN ON SECTION LINE N81-15E
1564.2; THENCE S62E 297'; THENCE N73-15E 1036.2'
TO THE SEC LINE; THENCE N81-15E SECTION LINE
2329.8' TO SEC CORNER; THENCE N49E 2277'; N18W
825'; THENCE N38W 363'; THENCE N7E 1395.9', N65-
15E R, 2310'? THEN N73E 660'; THENCE N42-30E 759';
THENCE N63E 775.5'; THENCE S73E 1155' N83E 645.38;
THENCE N56E 301.62'; THENCE N73E 601.26' TO THE 1/4
LINE OF SEC 12 & HIGHWAY ON NORTH BANK OF ROCK
RIVER. MAKING 21,077.76'

1859 RUGER VOL 1 PG 123 & 1232 STATES NOTHING ABOUT
MON. VAR 8-35 TO NW COR SEC 15, VAR 5-38 2698.08 TO
CEN SEC 15, & N1-30E FROM S 1/4 COR SEC 15 TO CEN
SEC 15

1871 RUGER VOL 2 PG 53 & 1234 FD NORTH BEARING TREE &
STUMP OF SW BARING TREE. SET LIMESTONE 19X12X4
POINT UP. VAR 7-14 2638.68 TO NE COR SEC 15, VAR 7-
31 2627.62 TO NW COR SEC 15.

1872 LEE #1231 & VOL 2 PG 88 FD COR SET BY RUGER. VAR 7-
10 1319.09 EAST OF N 1/16TH COR OF NW 1/4 SEC 15

1944 SUNNY #1130 FD IRON RAIL

1946 SUNNY #1132 & 6542 FD STONE MON 2672 TO IRON
RAIL @ CEN SEC 10

1969 NORTHROP #12694 EXISTING HARRISON C.I. MON. FND
2634.85 TO SE COR SEC 10

1974 KIENBAUM #6544 CI. 2668.35 TO CEN SEC 10, ANGLE
90-36-30 @ S 1/4 COR SEC 10 FROM CEN SEC 10 TO SE
COR SEC 10.

1978 SANDSNES VOL 5 PG 447299,659.05; 2,251,724.55

1978 SANDSNES #6576, #1117, #1239, & #6573 EDGERTON
PHOTO CONTROL

1980 SANDSNES #1126 & 7159 ROCK COUNTY MON. N1-33-
33W 2668.23 TO CEN SEC 10. BEARING IS NAD27

1980 BARNES VOL 6 PG 19 SANDSNES CALLED & REPORTED
THE FOLLOWING CORRECTIONS; 299,665.035;
2,251,727.377 SHOULD BE 299,659.46; 2,251,724.550

1980 BARNES VOL 6 PG 104 239,659.05; 2,251,724.55
SANDSNES N89-03-04E 2634.77 TO NE COR SEC 15,
SANDSNES S89-32-03W 2632.55 TO NW COR SEC 15..

1980 WEIR CSM VOL 9 PG 206 ALUM. MON. SET PIPE 339.31
EAST OF COR.

1981 SANDSNES #7158 & 1125 N1-33-33W 2668.66 TO CEN
SEC 10, ANGLE 89-04-46 @ CEN SEC 10 FROM E 1/4 COR
SEC 10 TO S 1/4 COR SEC 10, & ANGLE 91-01-34 @ CEN
SEC 10 FROM S 1/4 COR SEC 10 TO W 1/4 COR SEC 10

PAGE 1 OF 3

CORNER CODE J-15(1)

Donald Barnes

12/11/06

FU548

1982 COMBS #1144 FD CAST IRON MON 2632.24 TO SW COR
SEC 10

1987 NORTHROP #12694 CI 2634.85 TO SE COR SEC 10.

1988 BARNES J-15 FD C.I. LEANING TO THE SOUTH. PLACED
MON. DEEPER AND AT THE LOCATION OF THE OLD BASE.
DID NOT USE GCM VOL 9 PG 206 TO DETERMINE
LOCATION BECAUSE OF DISCREPANCIES IN RECORD AND
FIELD MEASUREMENTS AS SHOWN. 7.5' SOUTH OF UP
WHICH IS ON E/W UP LINE. REFERENCED SAME.

1995 KREBS GCM VOL 19 PG 13 C.I. 5306.28 TO N ¼ COR SEC
10

1997 NORTHROP #8604 CI 2634.82 TO NE COR SEC 15, &
ANGLE 90-33-03 @ N ¼ COR SEC 15 FROM NE COR SEC
15 TO N/S ¼ LINE SEC 15

2004 COMBS #14904 FD PIN 2631.44 TO FD PIPE @ SW COR SEC
10, & ANGLE 90-39-57 @ SW COR SEC 10 FROM W ¼ COR SEC
10 TO S ¼ COR SEC 10

FD CI MON. WITH WHITE PLASTIC POST AND REFERENCE PINS. MON
IS ON SOUTH FACE OF AN EXTREME SLOPE.

B) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FD CI.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, **Donald Barnes**, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Seal

Emboss
Donald Barnes
17/11/06

SHEET 2 OF 3

CORNER CODE **J-15(1)**

A.E. 7.08 REQUIREMENT

WOODS

ELEV 100.0
NAIL

N51-02-11E 40.31
REC 21.41

S89-11-11E 17.79
REC 17.98

ELEV 88.6'
ELEV 89.6'

S20-00-27E
REC 7.60
REC 7.45

S70-03-19E 21.60
REC 21.68

REC 20.70

N88-22-08E 22.61
REC 22.25

ELEV 87.9



REC 21.36
REC 21.17
N68-43-35E

ELEV 85.9'
FD CI
/WHITE PLASTIC
POST

S 1/4 COR
SEC 10

E/W RIDGE

ASSUMED VERTICAL DATUM



NOT TO SCALE
OBSERVATION SHEET 993
FB #3 PG 17
FD 3/8" REROD

EMBOSSSED SEAL
Ronald Bourne
12-11-06

ELEV 88.6'

SHEET 3 OF 3

J-15(1)