

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 1N., R. 12E 4th P.M.

BELoit TWP

CORNER CODE INDEX

TWP

ROCK COUNTY, WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

A	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25
B	6					5																			
C																									
D																									
E																									
F																									
G	7					8																			
H																									
I																									
J																									
K																									
L	18					17																			
M																									
N																									
O																									
P	19					20																			
Q																									
R																									
S																									
T	30					29																			
U																									
V																									
W																									
X																									
Y																									
Z	31					32																			

North 217,159.49 Elev. _____

East 472,365.29

Hor. Datum COUNTY Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

ELLIPS. DATUM
NAD83(91) _____ COUNTY _____ LIST _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL  AT PROPER LOCATION ON ABOVE INDEX

 CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 2

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE N-7

BE564

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

1834 HARRISON EAST ON RAND BET. 17 & 20
2640 TEMPY 1/4 SEC COR
5288.58 INT. E. BOUNDARY 35.64' NORTH OF POST.
COR WEST BET 17 & 20
2644.29 QUARTER SEC COR ON SUMMIT OF RIDGE N & S. POST & RAISED
MOUND.
5288.58 SEC COR.
1859 RUGER VOL 1 PG 95 SURROUNDED 1/4 POST 3 HH
1962 BATTERMAN VOL 4 PG 176 FD 2" PIPE ON THE N/S CENTER SEC 17. A
PIPE IS 33 NORTH OF S 1/4 COR SEC 17.
1984 WISDOT PROJ 5571-01-21 REV 8-2-84 FD 1" PIN 198,231.16; E/W
2,242,451.24

FOUND PIN

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?
ACCEPTED FOUND LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.
NO

I, Donald Barnes, hereby certify that the corner points as identified by the corner code index were, in a field survey on, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with the regulations and rules as required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management.

seal
Donald Barnes
OCT 9, 1998

COUNTY SURVEYOR FILING DATA

Date of computer entry _____

Date microfilmed _____

Number of included sheets _____

CORNER CODE N-7


EMBOSS LAND SURVEYOR SEAL.

A-E 7.08 REQUIREMENT

Donald Barnes
Oct 9, 1998

BEARINGS @ S 1/4 COR
 TO TANK S19-52-36E 27,276'
 TO TANK S15-53-28E 29,255'
 TO LARGE WHITE TANK S46-59-59E 22,918
 TO MAST N45-45-39W 25,809'

STA #9428 FD DOT
 CAPPED REROD; 24 +/- S79-48-39E STA #12 FD LARGE SPIKE;
 NORTH CENTER OF PVMT, 80.32 10 +/- NORTH OF CENTER
 OF PVMT.



STA #11 FD T-BAR
 15' +/- WEST CENTER
 PVMT; 52 +/-
 CENTER OF RD. INT.

STA #13 T-BAR
 16 +/- SOUTH CENTER
 PVMT; 25 +/- EAST
 OF CENTER DR.

S 1/4 COR
 SEC 17

