

# U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners in:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. 1 N., R. 11 E

### CORNER CODE INDEX

A	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
B	6																									
C		5																								
D			4																							
E				3																						
F					2																					
G						1																				
H	1	8	9	10	11	12																				
I																										
J																										
K																										
L	18	17	16	15	14	13																				
M																										
N																										
O																										
P	19	20	21	22	23	24																				
Q																										
R																										
S																										
T	30	29	28	27	26	25																				
U																										
V																										
W																										
X	31	32	33	34	35	36																				
Y																										
Z																										

NEWARK TWP

ROCK COUNTY WI

IF AVAILABLE  
ROCK COUNTY COORDINATES PREFERRED

North \_\_\_\_\_ Elev. \_\_\_\_\_

East \_\_\_\_\_

Hor. Datum \_\_\_\_\_ Vert. Datum \_\_\_\_\_

LATITUDE \_\_\_\_\_ ELLIPS. HT. \_\_\_\_\_

LONGITUDE \_\_\_\_\_

GPS (X) \_\_\_\_\_ TRAVERSE (X) \_\_\_\_\_

BASED ON THE FOLLOWING CONTROL:

PLACE MONUMENT SYMBOL  AT PROPER LOCATION ON ABOVE INDEX

CORNER MONUMENT

WITNESS MONUMENT

(a)

BEARINGS ARE BASED ON:

OBSERVATION SHEET 603

FIELD BOOK \_\_\_\_\_ PAGE # \_\_\_\_\_

SHEET 1 OF 1

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THE ABOVE FORM ON 12/2/1982

CORNER CODE V-3

NE602

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

- 1834 MILLER MARCH PG 31 WEST RANDOM BETWEEN SECS 30 & 31  
5016 ENTER MARSH S.E. 396' WIDE  
5364.48 INTERSECT RANGE LINE 12.54' SOUTH POST LAND LEVEL 2ND  
RATE TIMBER OAK & HICKORY  
\*WEST CORRECTED BETWEEN SECS 30 & 31  
SET POST TO COR OF 30 & 31 BUR OAK 14 SSE 168.3; BUR OAK 18  
N88-30E {5.33' OR 532.62'}  
652.74 BUR OAK 14 DIA  
2724.48 SET 1/4 SEC POST BUR OAK 10 S58E 50.82; YELLOW OAK 22 IN  
N52W 87.78'  
5364.48 SEC COR  
\* RANDOM & CORRECTION BOTH WEST? {NOTE IN FIELD NOTES}
- 1871 COLLIN'S REMONUMENTATION NOTES  
EAST BETWEEN 30 & 31 VARIATION 5-45  
2766.72 SET 1/4 STONE BY ROOTS OF WITNESS TREES.  
CONTINUED EAST SAME VARIATION  
5405.4 SECTION CORNER
- 1959 SHIMEALL #3236 1319.50 EAST TO 1/16 TH COR  
1960 SHIMEALL #3250 1319.50 FROM NE COR SEC 31 WEST TO 1/16 TH COR  
1962 BATTERMAN VOL 4 PG 65 FOUND REMAINS OF CUT STONE MON.  
REFERENCED SAME.  
1962 BATTERMAN VOL 4 PG 209 FD CUT STONE MON. REFERENCED SAME  
1972 SHIMEALL #3243 1339.44 WEST TO 1/16TH COR  
1977 LEUNBERGER #3253 2764.48 TO NW COR SEC 31  
1995 KREBS #9253 2764.89 TO NW COR SEC 31  
1995 KREBS CSM 18 PG 333 2666.88 TO CENTER OF SEC 31

FD R/R SPIKE. DRILLED HOLE IN CENTER. FD TIES FROM VOL 4 PG 209.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?


ACCEPTED FD R/R AS PERPETUATED LOCATION.

D) Describe any material discrepancy between the location of the corner as restored or reestablished and the location of that corner as previously restored or reestablished by distance and direction. Show the discrepancy on the plan view drawing under (a), above. Show the distances between the corner as previously restored or reestablished and (1) the corner as restored or reestablished, and (2) to at least 4 of the witness monuments shown on the drawing in (a), above.

(E) Was the corner reestablished through lost corner proportionate methods? If so, show the method, including the directions and distances to other public land survey corners used as evidence or used for proportioning the corner location.

I, Donald Barnes, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

seal



emboss

7-07-01

sheet 1 of 1

CORNER CODE V-3