

Paper weight-110# (minimum)

Black nonfading ink required

U.S. PUBLIC LAND SURVEY MONUMENT RECORD

For Public Land Survey Corners In:

WI ADMINISTRATIVE CODE A-E 7.08 REQUIREMENT

T. N. R. E. 4th P.M.

REV 10/23/2004

USMONREC.DWG

CORNER CODE INDEX

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	
A																									A
B	6					5					4				3					2				1	B
C																									C
D																									D
E																									E
F																									F
G	7					8					9				10					11				12	G
H																									H
J																									J
K																									K
L	18					17					16				15					14				13	L
M																									M
N																									N
O																									O
P	19					20					21				22					23				24	P
Q																									Q
R																									R
S																									S
T	30					29					28				27					26				25	T
U																									U
V																									V
W																									W
X	31					32					33				34					35				36	X
Y																									Y
Z																									Z

TWP
ROCK COUNTY WI

IF AVAILABLE
ROCK COUNTY COORDINATES PREFERRED

North _____ Elev. _____

East _____

Hor. Datum _____ Vert. Datum _____

LATITUDE _____ ELLIPS. HT. _____

LONGITUDE _____

NAD83(91) _____ NETWORK ADJ. YR _____

GPS (X) _____ TRAVERSE (X) _____

BASED ON THE FOLLOWING CONTROL:

◆ CORNER MONUMENT

○ WITNESS MONUMENT

BEARINGS ARE BASED ON: (a) _____

FIELD BOOK _____ PAGE # _____

SHEET 1 OF 3

SHOW A PLAN VIEW DRAWING DEPICTING THE CORNER MONUMENT AND SURROUNDING PHYSICAL FEATURES, INCLUDING THE EXCAVATION AREA AND DEPTH.

PLANNING & ZONING COMMITTEE ADOPTED THIS FORM ON 12/2/1982

CORNER CODE E-1

FU521 ^

(B) Describe any record evidence, monument evidence, occupational evidence, testimonial evidence or any other material evidence you considered, and whether the monument was found or placed.

- 1833 (SEP 20) MULLETT & BRINK NORTH ON EAST SIDE SECTION 1
1372.14 BUR OAK 12 IN DIAMETER
2640 SET QUARTER SECTION POST BUR OAK 14 S19W
22.44' BUR OAK 12 N4N 48.18'
5280 SET POST CORNER TO TOWNSHIPS 4 & 5 N
RANGES 11 & 12E BEARINGS {BUR OAK 12 N33E
24.42' BUR OAK 16 N77W 3.3'} MARKED {BUR
OAK 18 S26E BUR OAK 18 S62W LAND LEVEL
FIRST
- 1833 (SEP 20) MULLETT & BRINK NORTH ON EAST SIDE SEC 12 T4N
R11E
957 ENTER PRAIRIE
1538.46 INDIAN PATH @ NW & SE
2131.8? LEAVE PRAIRIE
2180.64 BURR OAK 10 IN DIAMETER
2640 SET QUARTER SECTION POST BUR OAK 18 S23W
9.9' BUR OAK 10 N4 1/4W 165'
3993.66 BUR OAK 10 IN DIAMETER
5280 SET POST CORNER SECTIONS 1 & 12 BLACK OAK 8 S
1 1/2 W 55.44' BUR OAK 8 N57W 9.9' LAND ROLLING
SECOND RATE FIRST 1/2 SOME PRAIRIE LAST 1/2
TIMBERED WITH WHITE BLACK AND BUR OAK
- 1833 (OCT 30) HARRISON EAST ON RANDOM BET SECS 1 & 12 T4N
R11E 4TH MER.
2640 TEMPY QUARTER SEC COR.
5332.8 INT. E BDY 39.6' N OF P LAND ROLLING 2ND RATE
THINLY AND BADLY TIMBERED WITH SMALL RED &
BURR O ? ? GRASS & WEEDS
COR WEST BET SECS 1 & 12
2666.4 QUARTER SEC COR. {BURR O 8 S58E 91.08' BURR
O 10 N38E 105.6' BURR O 8 BURR O 10} MARKED
5332.8 INT SEC COR.
- 1834 (APR 4) HARRISON WEST ON RAND. BET SECS 6 & 7
2640 TEMPY 1/4 SEC COR.
5316.3 INT. W. BDY 29.7' N OF P LAND ROLLING 2ND RATE
TIMBER ALL BURR O. UNDERGROWTH ? GRASS &
WEEDS
COR. EAST
2676.3 QUARTER SEC COR. {BURR O 12 S80W 26.4' RED O.
10 N54E 76.56' BURR O 12, RED O 20} MARKED
4579.74 BURR O 12 IN DIAMETER
5316.3 SEC COR.
- 1847 TWP RD REC BK 1 PG 10 ALSO A RD, THE CENTER LINE
OF WHICH IS DESCRIBED AS FOLLOWS TO WIT: PLACE OF
BEGINNING IS THE QUARTER SECTION POST BETWEEN
SECTION 5 & 8 IN T4N R12E FROM SAID POST RUN ON
SECTION LINE S81-15W 957' THENCE S54W 858', THENCE
N83-45W 1130.58' TO SEC COR [NW COR SEC 8] THEN ON
SECTION LINE BETWEEN 6 & 7 S81-15W 5315.64' TO THE
TOWN LINE, MAKING 8261.22'. IN WITNESS WHEREOF WE
HAVE HEREUNTO SET OUR HANDS AT FULTON ON THE 12 DAY
OF OCT. 1847 GOODRICH, PHILIP & DAVOLT MARK
COMMISSIONER OF HIGHWAYS.
- 1847 PIERCE TWP RD BK 1 PG 10 SURVEYED JUNE 2ND 1847 A
RD THE CENTER LINE OF WHICH IS DESCRIBED AS FOLLOWS
TO WIT; PLACE OF BEGINNING IS THE 1/4 SEC POST BETWEEN
SEC 5 & 8 IN T4 OF R12 FROM SAID POST, RUN ON SEC. LINE
S81-15W 957.00' THEN S54W? 858' THEN N83-45W 1130.58'
TO SEC COR [NW COR SEC 8], THE ON SEC LINE BETWEEN 6 &
7 S81-15W 5315.64 TO THE TOWN LINE MAKING 8,261.22'.

SHEET 1 OF 3
CORNER CODE E-1

Dodd
Banes
11/03/07

FU521 ^

- 1871 RUGER VOL 2 PG 63 FD OLD STAKE & STUMP OF SW BT (SHOULD READ S10 1/2W INSTEAD OF S 1 1/2W) & WHERE STUMP OF N.W. BT HAD BEEN DUG UP DROVE STAKE DEEP & PUT ON TOP OF IT LIMESTONE 14X6X5 SURROUNDED IT WITH 4 HH STONES. CORNER IS ABOUT 3.96' SOUTH OF E/W FENCE & 26.4' EAST OF FENCE ON WEST SIDE OF RD. W 1/4 COR SEC 7 DECLARED LOST, VAR 7-27 FROM W 1/4 COR TO NW & SW CORNERS SEC 7.
- 1871 RUGER VOL 2 PG 79 & 1069 SEE SEC 12 PG 39 VAR 7-25 2672.34 TO N 1/4 COR SEC 7. SEE SEC 12 PORTER TWP PG 39
- 1876 RUGER #1069 VAR 7-27 2672.34 TO N 1/4 COR SEC 7
- 1886 RUGER VOL 2 PG 284 FD LIMESTONE SURROUNDED BY 4 HH STONES. VAR 5-45 2537.7 TO S 1/4 COR SEC 6 & VAR 5-30 2659.30 TO W 1/4 COR SEC 1
- 1934 DOT #3901, 13300, 13302, 13301 STATES NOTHING ABOUT MON. SHOWS ANGLE OF 90-10 @ SW COR SEC 6 FROM SOUTH LINE OF SEC 6 TO WEST LINE OF SEC 7
- 1965 BATTERMAN VOL 4 PG 223 PK NAIL BY WP&L. WP&L 2642.9X TO E 1/4 COR SEC 12 PORTER TWP, WP&L 1270.20 TO HH SURROUNDED BY 4 HH @ N 1/16TH COR OF NE 1/4 OF SEC 12 PORTER TWP. WPL 2540.4X TO FD LS. 18X6X5 @ N 1/4 SEC 12 PORTER TWP
- 1966 BATTERMAN VOL 4 PG 256 DUG 6/1/66 FD LS SURROUNDED HHS 2.1' DEEP. PLACED BOLT @ COR & REF SAME.
- 1967 BATTERMAN VOL 4 PG 355 DUG & FOUND STONES AS DESCRIBED IN RECORDS. REF. SAME. @ INT. OF STH 59 & HARTZE RD.
- 1981 BARNES VOL 6 PG 211 FD 1" IP & REPLACED WITH ALUM. MON. FD REC SPIKE 44.18 NW IN UP & REC NAIL 11.50 TO THE SOUTH.
- 1992 NORTHROP CSM VOL 15 PG 475 2679.03 TO N 1/4 COR SEC 7 & ANGLE 89-50-36 @ N 1/4 COR SEC 7 FROM S 1/4 COR SEC 7 TO NW COR SEC 7
- 1994 NORTHROP #9491 2679.03 SW COR SEC 6 TO S 1/4 COR SEC 6, ANGLE OF 91-10-35 @ S 1/4 COR SEC 6 FROM SW TO N 1/4 COR SEC 6. ALUM MON.
- 2000 NORTHROP CSM VOL 24 PG 45 & 87 ALUM. 2679.02 TO N 1/4 COR SEC 7 & ANGLE 90-22-23 @ NW COR SEC 7 FROM N 1/4 COR SEC 7 TO W 1/4 COR SEC 7

FD ALUM. MON.

C) Was the corner restored through acceptance of (1) an obliterated evidence location, or, (2) a found perpetuated location?

ACCEPTED FD ALUM. MON. IT PERPUTATES THE ORIGINAL GOV. MON.

I, **Donald Barnes**, hereby certify that the corner location as identified by the corner code index was determined by me under my direction and control and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Seal


Donald Barnes
Emboss

11/03/07

SHEET 2 OF 3

CORNER CODE **E-1**

A.E. 7.08 REQUIREMENT



OBSERVATION SHEET #394, #409, & 2521
 NOT TO SCALE

W 1/16TH COR
 OF SW 1/4
 SEC 6
 R/R SPIKE
 REFERENCED WITH 4
 REFERENCE MONUMENTS

RED/WHITE ANT
 N80-46-26W 324X

HARTZELL RD

N1-05-38W 1329.11

SW COR
 SEC 6

S00-54-13E 1490.43

STH 59

RED/WHITE ANT
 N44-10-36W 465X

STA #409
 3/4X24 REROD/CAP
 7.1 WEST OF WEST PVMT
 EDGE, NORTH SIDE OF DR.

N33-12-17E 4843.04

N62-08-33W 2757.97

N26-01-11E 5988.06

N72-12-30W 591X'
 RED/WHITE ANT

N88-16-11E 2678.97

N89-02-49E 2413.32

STH 59

N57-21-42E 2837.55

N 1/4 COR
 SEC 6

FD CI

N02-17-34E 5345.27

FD ALUM MON
 S 1/4 COR SEC 6

N81-15-01E
 267.88

DISK '1V50'
 PID DF9893
 STA 9893
 NAVD 88 876.81

3 OF 3

E-1

*Donald
 Barnes
 11/03/07*