

Board of Supervisors 51 S. Main Street Janesville, WI 53545 Phone: 608/757-5510 FAX: 608/757-5511

www.co.rock.wi.us

ROCK COUNTY BOARD OF SUPERVISORS' MEETING THURSDAY, APRIL 10, 2014 – 6:00 P. M.

COUNTY BOARD ROOM/COURTROOM H FOURTH FLOOR/COURTHOUSE EAST

Agenda

- 1. CALL TO ORDER
- 2. INVOCATION & PLEDGE OF ALLEGIANCE
- 3. ROLL CALL
- 4. ADOPTION OF AGENDA
- 5. APPROVAL OF MINUTES March 27, 2014
- 6. PUBLIC HEARING
 - A. Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (Chapter 4 Part 11) (First Reading)
 - B. Amending Various Sections of the Rock County Storm Water Management Ordinance (Chapter 4 Part 8) (First Reading)
- 7. CITIZEN PARTICIPATION, COMMUNICATIONS AND ANNOUNCEMENTS
- 8. NOMINATIONS, APPOINTMENTS AND CONFIRMATION
 - A. Appointment as Alternate to the Transportation Coordinating Committee
 - B. Appointments to the Transportation Coordinating Committee Marketing and Outreach Sub-Committee
 - C. Appointments to the Transportation Coordinating Committee Personal Mobility Sub-Committee
 - D. Appointments to the Transportation Coordinating Committee Bicycle and Pedestrian Sub-Committee
 - E. Appointments to the Transportation Coordinating Committee Transportation Advocacy Sub-Committee
 - F. Appointment to the City of Janesville TIF District No. 32, Amendment #1 and TIF District No. 35, Amendment #2
- 9. INTRODUCTION OF NEW RESOLUTIONS OR ORDINANCES BY SUPERVISORS FOR REFERRAL TO APPROPRIATE COMMITTEE
- 10. REPORTS
- 11. UNFINISHED BUSINESS
- 12. NEW BUSINESS

ROCK COUNTY BOARD OF SUPERVISORS April 10, 2014 Page 2

12. NEW BUSINESS

A. Supplementary Appropriations and Budget Changes - Roll Call

1) Amending the 2014 Rock County Health Department Budget to Increase the Environmental Health Technician Position from 0.4 FTE to 0.6 FTE

NOTE: Item 12.A.1. will be considered by the County Board Staff Committee on April 8, 2014

- 2) Amending the 2014 Land Conservation Department Budget Gypsy Moth Suppression
- 3) Amending the Human Services Department Budget to Accept Funding for Post Reunification Support Program
- 4) Amending the 2014 Human Services Department Budget to Accept In-Home Safety Services Initiative Grant Funds
- 5) Authorizing Acceptance of Cops and Kids Foundation Grant

NOTE: Item 12.A.5. will be considered by the Public Safety and Justice Committee on April 7, 2014

- B. Bills Over \$10,000 No Roll Call
- C. Encumbrances Over \$10,000 Roll Call
- D. Contracts Roll Call
 - 1) Establishing the Salary for the Rock County Clerk of Courts for the 2015-2018
 Term
 - 2) Establishing the Salary for Rock County Sheriff for the 2015-2018 Term

NOTE: Items 12.D.1. and 12.D.2. will be considered by the County Board Staff Committee on April 8, 2014

E. Authorizing Application with Wisconsin Department of Natural Resources for Snowmobile Grant Funds

NOTE: Item 12.E. will be considered by the Public Works Committee on April 10, 2014

- F. Proclaiming Correctional Employees Week
- G. Proclaiming Police Officer Week

NOTE: Items 12.F. and 12.G. will be considered by the Public Safety and Justice Committee on April 7, 2014

- H. Recognizing Deferred Prosecution Director Kristin Koeffler
- I. To Recognize Charles Holznecht

NOTE: Items 12.H. and 12.I. will be considered by the Public Safety and Justice Committee on April 7, 2014 and County Board Staff Committee on April 8, 2014

ROCK COUNTY BOARD OF SUPERVISORS April 10, 2014 Page 3

12. NEW BUSINESS

- J. Rock County Rabies Awareness Week
- K. Recognizing Ivan Collins
- L. Recognizing Steve Howland
- M. Recognizing Marilynn Jensen
- N. Recognizing Phillip Owens, Jr.
- O. Recognizing Mike Rundle
- P. Recognizing Mary Wopat
- Q. Recognizing Fred Yoss

NOTE: Items 12.K., 12.L., 12.M., 12.N., 12.O., 12.P. and 12.Q. will be considered by the County Board Staff Committee on April 8, 2014

R. To Recognize Economic Support Staff

NOTE: Items 12.R. will be considered by the County Board Staff Committee on April 8, 2014 and Human Services Board on April 9, 2014

13. ADJOURNMENT

ORDINANCE ROCK COUNTY BOARD OF SUPERVISORS

LAND CONSERVATION	
COMMITTEE	
INITIATED BY	



ANDREW BAKER DRAFTED BY

MARCH 26, 2014 DATE DRAFTED

LAND CONSERVATION COMMITTEE SUBMITTED BY

1

2 3

4 5

> 6 7

> 8

9

10

11

12

13

14 15 16

17 18

19

20 21

22 23

24 25

26

27

28 29

30

31 32

33 34

35

36 37

38 39 40

41 42 AMENDING VARIOUS SECTIONS OF THE ROCK COUNTY CONSTRUCTION SITE EROSION CONTROL ORDINANCE (CHAPTER 4 PART 11)

The County Board of Supervisors of the County of Rock does ordain as follows:

I. Chapter 4, Part 11, of the Rock County Ordinances shall be amended to read as follows (new language underscored, deleted language crossed out):


4.1105 Jurisdiction, Applicability and Waivers

- Applicability (2)
 - This ordinance applies to the following land disturbing activities:
 - 9. Land disturbing activities, on a site of any size, that have been observed to cause, or have been determined likely to result in, undue channel erosion, increased water pollution by scouring or the transportation of particulate matter, or endangerment of property or public safety. The <u>LCC LCD</u> shall make this determination after review and recommendation by the Technical Review Committee LCD.
- Waivers (3)
 - The Technical Review Committee LCD shall be responsible for making (B) recommendations to the LCC concerning all waiver applications.

4.1107 Performance Standards

- Erosion and Other Pollutant Control Requirements (1)
 - (B) BMPs shall, by design, reduce pollutants from the construction site to the maximum extent practicable by use of methods including, but not limited to, the following:
 - Prevent gully and bank erosion.
 - Achieve a reduction of 80% of the sediment load carried in runoff, on an average annual basis, as compared with no sediment or erosion controls until the construction site has undergone final stabilization. The LCD may, upon written approval by the DNR, use a standard that is equivalent to an 80% reduction in sediment load. Discharge no more than 5 tons per acre per year, or to the maximum extent practicable, of the sediment load carried in runoff from initial grading to final stabilization. If BMPs cannot be designed to meet the standard in this paragraph, (B)2., the plan shall include a written and site-specific explanation as to why the standard is not attainable and a statement that the sediment load shall be reduced to the maximum extent practicable.
 - (E) Sediment controls shall be implemented to do all of the following:

	4. Prevent the discharge of sediment from soil stockpiles existing for more than 7
	days.
	5. Prevent the transport by runoff into waters of the state of untreated wash water
	from vehicle and wheel washing.
	 Prevent the transport by runoff into waters of the state of chemicals, cement, and other building compounds and materials on the construction site during the
	construction period.
	constitution period.
	lementation. The BMPs used to comply with the performance standards must be implemented
as	follows:
	(A) Erosion and sediment control practices shall be constructed or installed before land disturbing construction activities begin in accordance with the approved plan
	(B) Final stabilization activity shall commence when land disturbing activities cease and final grade has been reached on any portion of the site.
	(C) Temporary stabilization activity shall commence when land disturbing construction
	activities have temporarily ceased and will not resume for a period exceeding 14
	calendar days.
	(D) BMPs that are no longer necessary for erosion and sediment control shall be removed
	by the responsible party.
	aintenance. The permit holder shall maintain all BMPs once a week and within 24 hours of
	ch rain of 0.5 inches or more to meet the requirements of this ordinance until the site has
	hieved final site stabilization and a written BMP removal authorization has been received from e LCD.
ш	ELCD.
(<u>5</u> 4)	Alternate Requirements.
·- /	
(A) The LCD may establish erosion and sediment control requirements more stringent than those
(set forth in this section if the LCD determines that an added level of protection is needed to
	protect sensitive resources.
(B	
	any erosion and sediment control requirements more stringent than those set forth in this
	section.
1.11081	Permits and Waivers
	•
((4) Erosion and Sediment Control Plans
	(A) Plan Requirements for Class One Land Disturbing Activities.
	3. Each plan shall include a description of interim and permanent BMPs that will be
	implemented at the site to prevent pollutants from reaching waters of the state of
	adjacent property. The plan shall clearly describe the appropriate control
	measure(s) for each major activity and the timing during the land disturbing
	activity. The BMPs shall meet, when appropriate, the following minimum requirements:
	a. Preservation of existing vegetation where possible, minimize soil
	compaction and preservation of topsoil;
	(5) Evaluation Of Applications. Within 10 working days of receipt, the LCD shall review
	applications to insure they are complete. Any application found to be incomplete shall be
	returned to the applicant for completion. Upon receiving a complete application, the LCD
	shall use the following procedure:



II. This ordinance shall be effective upon publication.

161

162 163

Respectfully submitted:

LAND CONSERVATION COMMITTEE

Richard Bostwick, Chair

Jarry Wiedenfeld, Vice-Chair

Eva Arnold

Edwin Nash

Nauam A- Pleasant V.

David Rebout, USDA-FSA Representative

Alan Sweeney

Fred Yoss

FISCAL NOTE:

No fiscal impact.

Sherry Oja

Finance Director

LEGAL NOTE:

The County Board is authorized to take this action by Wisconsin Statutes sections 59.02, 59.692 and 59.693.

Eugene R. Dumas

Deputy Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

Amending Section 4.11 032614.res

Executive Summary

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8)

and

Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Please note that complete annotated and non-annotated versions of each ordinance, which incorporate each of the proposed amendments, are available at the County Clerk's office.

The County of Rock was authorized by the DNR on November 13, 2006 to discharge stormwater from the County owned Municipal Separate Storm Sewer Systems (MS4) in the Urbanized Area under a general Wisconsin Pollutant Discharge Elimination System (WPDES) MS4 permit. The Urbanized Area is determined by population density based on the most recent census. Under the permit language, MS4 means a conveyance or system of conveyances including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, constructed channels or storm drains, which meets all of the following criteria: Owned or operated by a municipality, designed or used for collecting or conveying storm water, and which is not a combined sewer conveying both sanitary and storm water.

The County's WPDES MS4 General Permit outlines certain minimum programs and documentation that must be developed and submitted by dates certain. Among the requirements is to adopt and enforce construction site erosion control and post-construction storm water management regulations, which the County has had in place since March 2004. These ordinances have been approved by the DNR in the past, but changes to State Administrative Code NR 151 in January of 2011 are required to be incorporated into local ordinances. The recommended action for each ordinance approves those required changes (including various definitions) along with less substantive changes which are recommended by the LCD based on administrative experiences.

The substantive changes are summarized below with reference to the ordinance section(s):

Removal of Technical Review Committee (recommended by the LCD for both ordinances): All references to the Technical Review Committee have been deleted from each Ordinance and changed, where necessary, to LCD and/or LCC. Staff has determined that this additional level of review, requiring input from other departments or local unit of government, is a step in the review process that is not necessary to effectively administer the ordinances. Appeals and/or alternative requirements formerly requiring input from the Technical Review Committee will be processed with a LCD recommendation and LCC decision. The LCD recommendation will still be based on consultation with other entities with jurisdiction over the project.

Post-Construction Storm Water Management (4.8)

Changes to required standards for redevelopment projects:

1. **(4.805(2)(B)1.e.)** Redevelopment projects are no longer entirely exempt from storm water ordinance requirements under NR 151. Redevelopment projects must meet total suspended solid (TSS) reduction standards (40% reduction, compared to 80%

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8) and Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Page 1 of 2

- reduction for new development), however exemptions remain for infiltration and peak discharge standards.
- 2. **(4.807(1)(B))** Maintenance of effort. This section is added, based on NR 151, to address redevelopment sites that were previously approved under the storm water ordinance requirements for new development. This section prevents a redevelopment project from being required to meet lesser standards than what were required when originally permitted.

Changes to the peak discharge rate and volume standards:

- 1. (4.807(2)). The one year, twenty-four hour storm event was added to the design requirements in NR 151.
- 2. (4.807(2)(B)4). The maximum pre-development runoff curve numbers were revised.

Changes to the storm water runoff discharge quality standards (total suspended solids):

1. (4.807(3)). Infill development is no longer exempt from TSS reduction standards under NR 151.

Changes to infiltration standards (4.807(4)):

This section was entirely reorganized based on the changes to NR 151. The level of infiltration that is required is now based on the level of planned impervious surface, rather than land use type. Also, sections formerly titled "Exclusions" and "Exemptions" have been reorganized to clarify the intent of the standards. Generally, the ordinance now includes criteria for Source Area Restrictions (i.e. the area that drains to an infiltration practice(s)) and the Location of Practices.

Changes to certain definitions (4.813): For the most part, the changes to the definitions are directly from NR 151 and are primarily for clarification purposes.

Construction Site Erosion Control (4.11)

Changes to performance standards under NR 151:

- 1. (4.1107(1)(B)2.): The method used to estimate the sediment discharged from a project and, subsequently, design a plan to reduce it has been revised. The 80% reduction standard was changed to a standard which allows a maximum of 5 tons per acre per year from a construction site. This level of allowed discharge is consistent with agricultural standards for most of the soils in Rock County. In terms of actual tolerable soil loss, 80% reduction and 5 tons per acre per year are very similar thresholds. However, the acceptable software tools to estimate soil loss and plan the practices to reduce erosion and sedimentation are simpler to use and not cost prohibitive.
- 2. (4.1107(1)(E)): The addition of other sources of pollutants that must be consideration considered when developing a plan.
- 3. (4.1107(2)): Implementation techniques are specified to avoid any question of what is required. These points were typically included in the permit conditions of approval, but now are added directly to the performance standards section to be consistent with NR 151.

ORDINANCE ROCK COUNTY BOARD OF SUPERVISORS

LAND CONSERVATION COMMITTEE INITIATED BY



ANDREW BAKER DRAFTED BY

March 26, 2014 DATE DRAFTED

LAND CONSERVATION COMMITTEE SUBMITTED BY

44 45 AMENDING VARIOUS SECTIONS OF THE ROCK COUNTY STORM WATER MANAGEMENT

ORDINANCE (CHAPTER 4 PART 8) The County Board of Supervisors of the County of Rock does ordain as follows: 1 2 I. Chapter 4, Part 8, of the Rock County Ordinances shall be amended to read as follows (new 3 language underscored, deleted language crossed out): 4 5 4.805 Jurisdiction, Applicability and Waivers 6 7 8 (2) Applicability 9 (A) This ordinance applies to the following land disturbing activities: 10 11 (3) Land disturbing activities, on a site of any size, that have been observed to cause, 12 or have been determined likely to result in, runoff in excess of the safe capacity of the 13 existing drainage facilities or receiving body of water, undue channel erosion, increased 14 water pollution by scouring or the transportation of particulate matter, or endangerment of property or public safety. The LCD LCC shall make this determination after review 15 by the Technical Review Committee LCD. 16 17 (B) Exemptions. 18 19 1. This ordinance does not apply to the following: 2.0 21 e. Redevelopment post construction sites with no increase in exposed parking lots or roads 22 23 fe. Post-construction sites with less than 10 percent connected 24 imperviousness, based on complete development of the post-construction 25 26 site, provided the cumulative area of all parking lots and rooftops 27 impervious surfaces is less than one acre; 28 29 g f. Underground utility construction such as water, sewer, and fiber optic lines. This exemption does not apply to the construction of any above 30 31 ground structures associated with utility construction: 32 (3) Waivers 33 34 (B) The Technical Review Committee LCD shall be responsible for making 35 36 recommendations to the LCC concerning all waiver applications. 37 38 4.807 Performance Standards 39 (1) General Considerations 40 41 42 (B) Maintenance of Effort. For redevelopment sites where the redevelopment will be 43 replacing older development that was subject to post-construction performance standards of

this ordinance in effect on or after March 2004, the storm water management plan must

meet the TSS reduction, peak flow control, infiltration, and protective area standards

applicable to the older development or meet the redevelopment standards of the revised ordinance, whichever is more stringent.

- (C) Off-Site Drainage. When designing BMPs, runoff draining to the BMP from off-site shall be taken into account in determining the treatment efficiency of the practice. Any impact on the efficiency shall be compensated for by increasing the size of the BMP accordingly.
- (2) Storm Water Runoff Peak Discharge Rate and Volume. Unless otherwise provided for in this ordinance, all land development activities subject to this ordinance shall establish onsite management practices to control the peak flow rates of storm water discharged from the site as described in this ordinance. Infiltration of storm water runoff from driveways, rooftops, parking lots, and landscaped areas shall be incorporated to the maximum extent practical to provide volume control in addition to control of peak flows
 - (A) The proposed land development shall, by design, not increase peak flow rates of storm water runoff from that which would have resulted from the same storm occurring over the site with the land in its pre-developed conditions for the one (1), two (2), ten (10), and one-hundred (100) year, twenty-four (24) hour storms.
 - (B) All runoff and flow calculations required for peak flow design shall use a hydrograph-producing method such as described in the most recent version of TR-55. The LCD retains approval of the methods used to determine runoff volume. Calculations for determining peak runoffs and volumes must incorporate the following assumptions.
 - 1. The design rainfall storm accumulation for different storm intensities in Rock County shall be based on the following data.
 - a. Rainfall Accumulation for 24 hour Rainfall:

i) <u>1-Year Storm</u>	2.25 Inches
i <u>ii</u>) 2-Year Storm	2.9 Inches
ii iii)10-Year Storm	4.1 Inches
iii iv)100-Year Storm	6.0 Inches

4. Runoff Curve Numbers for on-site areas shall be based on pre-developed and proposed developed land use conditions. The maximum pre-development runoff curve numbers are shown in Table 1. Runoff Curve Number for off-site areas shall be based on the pre-developed or proposed land use, which ever results in the highest peak flows. Runoff Curve numbers are described in TR-55.

(NEW TABLE)

Maximum Pre-development Runoff Curve Numbers						
Land	Hydrologic Soil Group					
Cover		-	_			
	A	В	C	D		
Woodland	30	55	70	77		
Grassland	39	61	71	78		
Cropland	55	69	78	83		

Table 1

(TABLE TO BE DELETED)			
	 	L	 L

- (E) The storm water runoff peak discharge rate and volume requirements of this section of this ordinance do not apply to any of the following:
 - 1. A post-construction site where the discharge is directly into a lake over 5,000 acres or a stream or river segment draining more than 500 square miles. A post-construction site where the change in hydrology due to development does not increase the existing downstream surface water elevation of rivers, streams, or lakes by more than 0.01 foot for the 100 year, 24 hour storm.
 - 2. Except as provided in 4.807(1)(B), a redevelopment post-construction site.
 - 3. An in-fill development of less than 5 acres.
- (F) A determination as to whether the exceptions listed in (E) above apply to a particular post construction site must be made as part of the waiver process described in sec. 4.808(3) of this ordinance.
- (3) Storm Water Runoff Discharge Quality Total Suspended Solids. BMPs shall be designed, installed or applied, and maintained to control total suspended solids carried in runoff from the post-construction site as follows:
 - (A) For new development and in-fill development, by design, reduce to the maximum extent practicable, the total suspended solids load by 80%, based on the average annual rainfall, as compared to no runoff management controls. No person shall be required to exceed an 80% total suspended solids reduction to meet the requirements of this section.
 - (B) For redevelopment, by design, reduce to the maximum extent practicable, the total suspended solids load generated on parking areas and roads by 40%, based on the average annual rainfall, as compared to no runoff management controls. No person shall be required to exceed a 40% total suspended solids reduction to meet the requirements of this section.
 - (C)—For in-fill development under 5 acres that occurs within 10 years after October 1, 2002, by design, reduce to the maximum extent practicable, the total suspended solids load by 40%, based on an average annual rainfall, as compared to no runoff management controls. No person shall be required to exceed a 40% total suspended solids reduction to meet the requirements of this section.
 - (D) For in fill development that occurs 10 or more years after October 1, 2002, by design, reduce to the maximum extent practicable, the total suspended solids load by 80%, based on an average annual rainfall, as compared to no runoff management controls. No person shall be required to exceed an 80% total suspended solids reduction to meet the requirements of this section.
 - (CE) Notwithstanding paragraphs (A) and to (BD), if the design cannot achieve the applicable total suspended solids reduction specified, the storm water management plan shall include a written and site-specific explanation why that level of reduction is not attained and the total suspended solids load shall be reduced to the maximum extent practicable.

155	(4) Infiltration. BMPs shall
156	maximum extent practicable in
157	(\underline{FE}) through (\underline{IH}) .
158	
159	(A) For residential of
160	
161	1. Infiltrate suf
162	volume shall be
163	on an average a
164	systems to meet
165	as an effective i
166	
167	2. Infiltrate 25
168	design storm wi
169	impervious surf
170	curve numbers
171	infiltration syste
172	is required as ar
173	is required as an
174	(B) For non-residen
175	institutional developme
176	mstitutional developme
177	1. Infiltrate su
178	volume shall be
179	on an average a
180	systems to mee t as an effective i
181	us an enective i
182	2 Infilmata 10
183	2. Infiltrate 10
184	type II distribut
185	surfaces shall b
186	numbers as defi
187	systems to mee
188	as an effective i
189	
190	(A) Low imperviousnes
191	such as parks, cemeteri
192	runoff volume so that t
193	percent of the pre-deve
194	However, when design
195	more than one percent
196	infiltration area.
197	
198	(B) Moderate impervio
199	percent connected impe
200	multi-family developn
201	infiltrate sufficient run
202	shall be at least 75 percentage
203	average annual rainfall
204	meet this requirement,
205	as an effective infiltrat
206	
207	(C) High imperviousne
208	imperviousness, such a
209	downtowns, infiltrate s
210	volume shall be at leas
211	on an average annual r
212	to meet this requirement
213	required as an effective
-13	roganou ao an oriceny

be designed, installed, and maintained to infiltrate runoff to the accordance with the following, except as provided in paragraphs

developments one of the following shall be met:

- fficient runoff volume so that the post-development infiltration at least 90% of the pre-development infiltration volume, based nnual rainfall. However, when designing appropriate infiltration this requirement, no more than 1% of the project site is required nfiltration area.
- % of the post-development runoff from the 2-year, 24-hour ith a type II distribution. Separate curve numbers for pervious and faces shall be used to calculate runoff volumes and not composite as defined in TR-55. However, when designing appropriate ems to meet this requirement, no more than 1% of the project site n effective infiltration area.
- atial development, including commercial, industrial and ent, one of the following shall be met:
 - fficient runoff volume so that the post-development infiltration eat least 60% of the pre-development infiltration volume, based unual rainfall. However, when designing appropriate infiltration t this requirement, no more than 2% of the project site is required infiltration area.
 - % of the runoff from the 2-year, 24-hour design storm with a ion. Separate curve numbers for pervious and impervious e used to calculate runoff-volumes, and not composite curve ined in TR-55. However, when designing appropriate infiltration t this requirement, no more than 2% of the project site is required infiltration area.
- ss. For development up to 40 percent connected imperviousness, ies, and low density residential development, infiltrate sufficient the post-development infiltration volume shall be at least 90 elopment infiltration volume, based on an average annual rainfall. ing appropriate infiltration systems to meet this requirement, no of the post-construction site is required as an effective
- pusness. For development with more than 40 percent and up to 80 erviousness, such as medium and high density residential, nent, industrial and institutional development, and office parks, off volume so that the post-development infiltration volume cent of the pre-development infiltration volume, based on an . However, when designing appropriate infiltration systems to no more than 2 percent of the post-construction site is required
- ess. For development with more than 80 percent connected as commercial strip malls, shopping centers, and commercial sufficient runoff volume so that the post-development infiltration st 60 percent of the pre-development infiltration volume, based ainfall. However, when designing appropriate infiltration systems nt, no more than 2 percent of the post-construction site is e infiltration area.

- (DC) Pre-development conditions shall be the same as in paragraph (2).
- (ED) Before infiltrating runoff, pretreatment shall be required for parking lot runoff and for runoff from new road construction in commercial, industrial and institutional areas that will enter an infiltration system. The pretreatment shall be designed to protect the infiltration system from clogging prior to scheduled maintenance and to protect groundwater quality in accordance with paragraph (<u>I H</u>). Pretreatment options may include, but are not limited to, oil/grease separation, sedimentation, biofiltration, filtration, swales or filter strips.

(FE) Exclusions Source Area Restrictions

- 1. Prohibitions. The runoff from the following areas may not be infiltrated and shall may not be credited toward meeting the requirements of sec. 4.807(4) unless demonstrated to meet the conditions of 4.807(4)(I). A determination as to whether these exclusions apply to a particular post-construction site must be made as part of the waiver process described in sec. 4.808(3) of this ordinance.
- <u>a</u>¹. Areas associated with tier 1 industrial facilities identified in NR 216.21 (2) (a), Wis. Adm. Code, including storage, loading, rooftop and parking.
- <u>b2</u>. Storage and loading areas of tier 2 industrial facilities identified in NR 216.21 (2) (b), Wis. Adm. Code.
- <u>c3</u>. Fueling and vehicle maintenance areas. <u>Rooftops of fueling and vehicle</u> maintenance areas may be infiltrated with the concurrence of the LCD.
- 2. Exemptions. The runoff from the following areas may be credited toward meeting the requirement when infiltrated, but the decision to infiltrate runoff from these source areas is optional:
 - a. Parking areas and access roads less than 5,000 square feet for commercial and industrial development not subject to the prohibitions in par 1.
 - b.Except as provided under 4.807(1)(B), redevelopment post-construction sites.
 - c.In-fill development areas less than 5 acres.
 - d.Stand alone roads in commercial, industrial and institutional land uses, and arterial residential roads. Roads that are part of a common plan of development are subject to the standard in this section.

(G) Location of Practices

- 1. Prohibitions. Infiltration practices may not be located in the following areas:
- <u>4a</u>.Areas within 1000 feet up gradient or within 100 feet down gradient of <u>direct</u> conduits to groundwater <u>karst features</u>.

b.Areas within 400 feet of a community water system well as specified in NR 811.16 (4) Wis. Adm. Code, or within the separation distances as specified in NR 812.08, Wis. Adm. Code, for any private well or non-community well for runoff infiltrated from commercial, including multi-family residential, industrial and institutional land uses or regional devices for one- and two- family residential development.

- c.Areas where contaminants of concern, as defined in NR 720.03 (2), Wis. Adm. Code are present in the soil through which infiltration will occur.
- 2.Separation Distances. Infiltration practices shall be located so that the characteristics of the soil and the separation distance between the bottom of the infiltration system and the elevation of seasonal high groundwater or the top of

 bedrock area in accordance with Table 2. Applicable requirements for injection wells classified under NR 815 shall be followed.

(NEW TABLE)

Separation Distances and Soil Characteristics					
Source Area	Separation Distances	Soil Characteristic			
Industrial, Commercial,	5 feet or more	Filtering Layer			
Institutional Parking Lots and					
Roads					
Residential Arterial Roads	5 feet or more	Filtering Layer			
Roofs Draining to Subsurface	1 foot or more	Native or Engineered Soil with			
Infiltration Practices	1	Particles Finer than Coarse Sand			
Roofs Draining to Surface	Not Applicable				
Infiltration Practices					
All Other Impervious Source	3 feet or more	Filtering Layer			
Areas					

Table 2

- 3. <u>Infiltration rate exemptions.</u> <u>Infiltration practices located in the following areas may be credited toward meeting the requirements under the following conditions, but the decision to infiltrate under these conditions is optional:</u>
 - a. Where the infiltration rate of the soil measured at the bottom of the proposed infiltration system is less than 0.6 inches/hour using a scientifically credible field test method.
 - b. Where the least permeable soil horizon to 5 feet below the proposed bottom of the infiltration system using the U.S. Department of Agriculture method of soils analysis is one of the following: sandy clay loam, clay loam, silty clay loam, sandy clay, silty clay, or clay.
- 5. Areas with less than 3 feet separation distance from the bottom of the infiltration system to the elevation of seasonal high groundwater or the top of bedrock, except this paragraph does not apply to infiltration of roof runoff.
- 6. Areas with runoff from industrial, commercial and institutional parking lots and roads and residential arterial roads with less than 5 feet separation distance from the bottom of the infiltration system to the elevation of seasonal high groundwater or the top of bedrock.
- 7. Areas within 400 feet of a community water system well as specified in NR 811.16 (4) (d) 3., Wis. Adm. Code, or within 100 feet of a private well as specified in NR 812.08 (4), Wis. Adm. Code, for runoff infiltrated from commercial, industrial and institutional land uses or regional devices for residential development.
- 8. Areas where contaminants of concern, as defined in NR 720.03 (2), Wis. Adm. Code are present in the soil through which infiltration will occur.
- 9. Any area where the soil does not exhibit one of the following soil characteristics between the bottom of the infiltration system and the seasonal high groundwater and top of bedrock: at least a 3-foot soil layer with 20% fines or greater; or at least a 5-foot soil layer with 10 percent fines or greater. This does not apply where the soil medium within the infiltration system provides an equivalent level of protection. This paragraph does not apply to infiltration of roof runoff.

322	(F) Exemptions. The following are not required to meet the requirements of
323	this paragraph. A determination as to whether these exceptions apply to a
324	particular post-construction site must be made as part of the waiver process
325	described in sec. 4.808(3) of this ordinance.
326	described in section (content of the content of the
327	1. Areas where the infiltration rate of the soil is less than 0.6 inches/hour
328	measured at the bottom of the infiltration system.
	measured at the bottom of the minutation system.
329	2. Parking areas and access roads less than 5,000 square feet for
330	
331 332	commercial and industrial development.
	2 Padayalanment pagt construction sites
333	3. Redevelopment post-construction sites.
334	4 In 511 development areas loss than 5 series
335	4. In fill development areas less than 5 acres.
336	
337	5. Infiltration areas during periods when the soil on the site is frozen.
338	
339	6. Roads in commercial, industrial and institutional land uses, and arterial
340	residential roads.
341	
342	(\underline{HG}) Where alternate uses of runoff are employed, such as for toilet flushing, laundry or
343	irrigation or storage on green roofs where an equivalent portion of the runoff is captured
344	permanently by rooftop vegetation, such alternate use shall be given equal credit toward
345	the infiltration volume required by this paragraph.
346	
347	(<u>I</u> H) Infiltration systems designed in accordance with this paragraph shall, to the extent
348	technically and economically feasible, minimize the level of pollutants infiltrating to
349	groundwater and shall maintain compliance with the preventive action limit at a point of
350	standards application in accordance with NR 140, Wis. Adm. Code. However, if site-
351	specific information indicates that compliance with a preventive action limit is not
352	achievable, the infiltration BMP may not be installed or shall be modified to prevent
353	infiltration to the maximum extent practicable.
354	• -
355	(<u>II</u>) Notwithstanding paragraph (<u>II</u>), the discharge from BMPs shall remain below the
356	enforcement standard at the point of standards application.
357	
358	(5) Protective Areas.
359	
360	(A) "Protective area" means an area of land that commences at the top of the channel of
361	lakes, streams and rivers, or at the delineated boundary of wetlands, and that is the
362	greatest of the following widths, as measured horizontally from the top of the channel
363	or delineated wetland boundary to the closest impervious surface. However, in this
364	paragraph, "protective area" does not include any area of land adjacent to any stream
365	enclosed within a pipe or culvert, such that runoff cannot enter the enclosure at this
	location.
366 367	iocanon.
368	4. For highly susceptible wetlands, 50 75 feet. Highly susceptible wetlands include
369	the following types: <u>calcareous</u> fens, sedge meadows, <u>open and coniferous bogs</u> , low
370	prairies, conifer <u>ous</u> swamps, <u>lowland hardwood swamps</u> , and <u>ephemeral ponds</u> .
371	shrub swamps, other forested wetlands, fresh wet meadows, shallow marshes, deep
	marshes and seasonally flooded basins. Wetland boundary delineations shall be made
372	
373	in accordance with NR 103.08 (1m) Wis. Adm. Code. This paragraph does not apply
374	to wetlands that have been completely filled in accordance with all applicable state
375	and federal regulations. The protective area for wetlands that have been partially
376	filled in accordance with all applicable state and federal regulations shall be
377	measured from the wetland boundary delineation after fill has been placed.
378	
379	5. For less susceptible wetlands, 10 percent of the average wetland width, but no
380	less than 10 feet nor more than 30 feet. Less susceptible wetlands include degraded
381	wetlands dominated by invasive species such as reed canary grass, cultivated hydric
382	soils, gravel pits or dredged material or fill material disposal sites that take on the
383	attributes of a wetland.
384	

		(D) This paragraph does not apply to:
		(D) This paragraph does not appry to.
		1. Except as provided under 4.807(1)(B), rRedevelopment post-construction sites.
	(9)	Alternate Requirements.
		··· ··· ·
		(B) The Technical Review Committee LCD shall make recommendations to the LCC LCI concerning any storm water requirements more stringent than those set forth in this section The LCC shall approve or deny alternative requirements.
.808	Per	mits and Waivers
• • • • • • •	(6)	Evaluation and Americal of Amelications Within 10 washing days of societ the LCD sho
	retu	Evaluation and Approval of Applications. Within 10 working days of receipt, the LCD sha ew applications to insure they are complete. Any application found to be incomplete shall be rned to the applicant for completion. Upon receiving a complete application, the LCD shall the following approval/disapproval procedure:
		··············
		(D) Completed and locations will be explored for compliance with the manifest of the
		(B) Completed applications will be evaluated for compliance with the requirements of this ordinance. Other governmental departments or the Technical Review Committee may be consulted during application evaluation.
		(E) Within 20 working days from the receipt of a complete waiver application on 10
		(E) Within 20 working days from the receipt of a complete waiver application, or 10 working days from the receipt of additional information requested in accordance with paragraph C, whichever is later, the applicant shall be informed whether the application habeen approved or disapproved. The LCD shall base the decision in consideration of the recommendations of the Technical Review Committee other governmental departments at the requirements of this ordinance.
		· · · · · · · · · · · · · · · · · · ·
		(J) If the application is disapproved, or if the applicant does not agree with the permit conditions, the applicant may request a review by the Technical Review Committee LCC . This request must be made in writing within 30 calendar days from the date of the applicant was notified of the LCD decision. The schedule and procedure for a waiver described in paragraph (E) above will be followed for this review.
1.813	Defi	nitions
	usei	erage Annual Rainfall: a typical calendar year of precipitation as determined by the DNR for as of models such as SLAMM, P8, or equivalent methodology. The average annual rainfall is sen from a DNR publication for the location closest to the municipality -a calendar year of
		sipitation, excluding snow, which is considered typical.
	 Cor	are acted. The mounting are as a sum are story a grade on the click directly and the story of th
		nected Imperviousness : an impervious surface that is directly connected to a separate m sewer or water of the state via an impervious flow path or minimally pervious flow path
	min	ect conduits to groundwater: wells, sinkholes, swallets, fractured bedrock at the surface, e shafts, non-metallic mines, tile inlets discharging to groundwater, quarries, or ressional groundwater recharge areas over shallow fractured bedrock.
		sting development: development in existence on March 1, 2004, or development for which orm water management permit application was submitted to the LCD by March 1, 2004
		ering layer: soil that has at least a 3-foot deep layer with at least 20 percent fines; or at t a 5-foot deep layer with at least 10 percent fines; or an engineered soil with an

448 equivalent level of protection as determined by the regulatory authority for the site. 449 450 **Impaired water:** a waterbody impaired in whole or in part and listed by the department 451 pursuant to 33 USC 1313 (d) (1) (A) and 40 CFR 130.7, for not meeting a water quality 452 standard, including a water quality standard for a specific substance or the waterbody's 453 designated use. 454 455 Impervious Surface: an area that releases as runoff all or a large portion of the precipitation that falls on it, except for frozen soil. Rooftops, sidewalks, gravel or paved driveways, gravel or 456 457 paved parking lots, and gravel or paved streets are examples of surfaces that typically are 458 impervious. 459 460 In-fill Area: an undeveloped area of land located within existing development. "In-fil area" 461 does not include any undeveloped area that was part of a larger new development plan for 462 which a storm water permit has previously been approved by the LCD 463 464 Maximum Extent Practicable: the highest level of performance that is achievable but is not 465 equivalent to a performance standard in this chapter. Maximum extent practicable applies when a person who is subject to a performance standard of this ordinance demonstrates to the 466 467 LCD's satisfaction that a performance standard is not achievable and that a lower level of 468 performance is appropriate. In making the assertion that a performance standard is not 469 achievable and that a level of performance different from the performance standard is the 470 maximum extent practicable, an applicant shall take into account the best available technology, 471 cost effectiveness, geographic features, and other competing interests such as protection of 472 public safety and welfare, protection of endangered and threatened resources, and preservation 473 of historic properties, a level of implementing BMPs in order to achieve a performance standard 474 specified in this chapter which takes into account the best available technology, cost 475 effectiveness and other competing issues such as human safety and welfare, endangered and 476 threatened resources, historic properties and geographic features. "Maximum extent 477 practicable" allows flexibility in the way to meet the performance standards and may vary based 478 on the performance standard and site conditions. 479 480 Technical Review Committee: a committee comprised of the Director of the Land 481 Conservation Department, a representative of the Planning and Development Agency, a 482 representative of the Land Conservation Department, and a representative of the Public Works. 483 Highway and Parks Department, and a representative of the town where the site of a permit or 484 waiver application is located. If the application site is located within the extraterritorial area of 485 a city or village a representative of that city or village will be invited to participate as a member 486 of the committee for that application. If groundwater concerns are among issues the committee 487 must address, the Public Health Department will be invited to participate as a member of the 488 committee for that application. 489 490 Total maximum daily load or TMDL: the amount of pollutants specified as a function of one 491 or more water quality parameters, that can be discharged per day into a water quality limited 492 segment and still ensure attainment of the applicable water quality standard. 493

II. This ordinance shall be effective upon publication.

494

Respectfully submitted:

LAND CONSERVATION COMMITTEE

Jarry Wiedenfeld
Larry Wiedenfeld, Vice-Chair

Eva Arnold

David Rebout, USDA-FSA Representative

Alan Sweeney

FISCAL NOTE:

No fiscal impact.

Sherry Oja

Finance Director

LEGAL NOTE:

The County Board is authorized to take this action by Wisconsin Statutes sections, 59.02, 59.692 and 59.693.

Eugene R. Dumas

Deputy Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

Amending Section 4.8 020314.res

Executive Summary

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8)

and

Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Please note that complete annotated and non-annotated versions of each ordinance, which incorporate each of the proposed amendments, are available at the County Clerk's office.

The County of Rock was authorized by the DNR on November 13, 2006 to discharge stormwater from the County owned Municipal Separate Storm Sewer Systems (MS4) in the Urbanized Area under a general Wisconsin Pollutant Discharge Elimination System (WPDES) MS4 permit. The Urbanized Area is determined by population density based on the most recent census. Under the permit language, MS4 means a conveyance or system of conveyances including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, constructed channels or storm drains, which meets all of the following criteria: Owned or operated by a municipality, designed or used for collecting or conveying storm water, and which is not a combined sewer conveying both sanitary and storm water.

The County's WPDES MS4 General Permit outlines certain minimum programs and documentation that must be developed and submitted by dates certain. Among the requirements is to adopt and enforce construction site erosion control and post-construction storm water management regulations, which the County has had in place since March 2004. These ordinances have been approved by the DNR in the past, but changes to State Administrative Code NR 151 in January of 2011 are required to be incorporated into local ordinances. The recommended action for each ordinance approves those required changes (including various definitions) along with less substantive changes which are recommended by the LCD based on administrative experiences.

The substantive changes are summarized below with reference to the ordinance section(s):

Removal of Technical Review Committee (recommended by the LCD for both ordinances): All references to the Technical Review Committee have been deleted from each Ordinance and changed, where necessary, to LCD and/or LCC. Staff has determined that this additional level of review, requiring input from other departments or local unit of government, is a step in the review process that is not necessary to effectively administer the ordinances. Appeals and/or alternative requirements formerly requiring input from the Technical Review Committee will be processed with a LCD recommendation and LCC decision. The LCD recommendation will still be based on consultation with other entities with jurisdiction over the project.

Post-Construction Storm Water Management (4.8)

Changes to required standards for redevelopment projects:

1. **(4.805(2)(B)1.e.)** Redevelopment projects are no longer entirely exempt from storm water ordinance requirements under NR 151. Redevelopment projects must meet total suspended solid (TSS) reduction standards (40% reduction, compared to 80%

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8) and Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Page 1 of 2

- reduction for new development), however exemptions remain for infiltration and peak discharge standards.
- 2. **(4.807(1)(B))** Maintenance of effort. This section is added, based on NR 151, to address redevelopment sites that were previously approved under the storm water ordinance requirements for new development. This section prevents a redevelopment project from being required to meet lesser standards than what were required when originally permitted.

Changes to the peak discharge rate and volume standards:

- 1. (4.807(2)). The one year, twenty-four hour storm event was added to the design requirements in NR 151.
- 2. (4.807(2)(B)4). The maximum pre-development runoff curve numbers were revised.

Changes to the storm water runoff discharge quality standards (total suspended solids):

1. (4.807(3)). Infill development is no longer exempt from TSS reduction standards under NR 151.

Changes to infiltration standards (4.807(4)):

This section was entirely reorganized based on the changes to NR 151. The level of infiltration that is required is now based on the level of planned impervious surface, rather than land use type. Also, sections formerly titled "Exclusions" and "Exemptions" have been reorganized to clarify the intent of the standards. Generally, the ordinance now includes criteria for Source Area Restrictions (i.e. the area that drains to an infiltration practice(s)) and the Location of Practices.

Changes to certain definitions (4.813): For the most part, the changes to the definitions are directly from NR 151 and are primarily for clarification purposes.

Construction Site Erosion Control (4.11)

Changes to performance standards under NR 151:

- 1. (4.1107(1)(B)2.): The method used to estimate the sediment discharged from a project and, subsequently, design a plan to reduce it has been revised. The 80% reduction standard was changed to a standard which allows a maximum of 5 tons per acre per year from a construction site. This level of allowed discharge is consistent with agricultural standards for most of the soils in Rock County. In terms of actual tolerable soil loss, 80% reduction and 5 tons per acre per year are very similar thresholds. However, the acceptable software tools to estimate soil loss and plan the practices to reduce erosion and sedimentation are simpler to use and not cost prohibitive.
- 2. (4.1107(1)(E)): The addition of other sources of pollutants that must be consideration considered when developing a plan.
- 3. (4.1107(2)): Implementation techniques are specified to avoid any question of what is required. These points were typically included in the permit conditions of approval, but now are added directly to the performance standards section to be consistent with NR 151.

APPOINTMENT AS ALTERNATE TO THE TRANSPORTATION COORDINATING COMMITTEE

POSITION:

Alternate Member of the Transportation Coordinating

Committee

AUTHORITY:

County Board Resolution 13-4B-315

TERM:

Unexpired Term Ending December 31, 2015

PER DIEM:

For County Board Supervisors Only

(Per Board Rule IV.J.)

PRESENT MEMBER:

Dave Kipp

CONFIRMATION:

Yes, by County Board of Supervisors

APPOINTMENT:

Rebecca Smith

(for Dave Mumma) 900 North Parker Drive Janesville, WI 53545

EFFECTIVE DATE:

APPOINTMENT TO THE TRANSPORTATION COORDINATING COMMITTEE MARKETING AND OUTREACH SUB-COMMITTEE

POSITION:

Member of the Transportation Coordinating Committee

Marketing and Outreach Sub-Committee

AUTHORITY:

County Board Resolution 14-3B-563

TERM:

Coinciding with their Terms on the Transportation

Coordinating Committee

PER DIEM:

For County Board Supervisors Only

(Per Board Rule IV.J.)

CONFIRMATION:

Yes, by County Board of Supervisors

APPOINTMENT:

Justin Svingen

(term expiring 12/31/15)

Rock County Mobility Manager

51 South Main Street Janesville, WI 53545

Dave Mumma

(term expiring 12/31/15) Janesville Transit System 900 North Parker Drive Janesville, WI 53545

Ryan Schomber

(term expiring 12/31/15) Rock County Job Center 1900 Center Avenue Janesville, WI 53546

EFFECTIVE DATE:

APPOINTMENT TO THE TRANSPORTATION COORDINATING COMMITTEE PERSONAL MOBILITY SUB-COMMITTEE

POSITION:

Member of the Transportation Coordinating Committee

Personal Mobility Sub-Committee

AUTHORITY:

County Board Resolution 14-3B-563

TERM:

Coinciding with their Terms on the Transportation

Coordinating Committee

PER DIEM:

For County Board Supervisors Only

(Per Board Rule IV.J.)

CONFIRMATION:

Yes, by County Board of Supervisors

APPOINTMENT:

Steve Skelly

(term expiring 12/31/14) Rock County Transit 51 South Main Street Janesville, WI 53545

Lynn Jones

(term expiring 12/31/14) Community Action 20 Eclipse Center Beloit, WI 53511

Patty Hansberry

(term expiring 12/31/16)

RSVP

2433 S. Riverside Drive, Suite B

Beloit, WI 53511

EFFECTIVE DATE:

APPOINTMENT TO THE TRANSPORTATION COORDINATING COMMITTEE BICYCLE AND PEDESTRIAN SUB-COMMITTEE

POSITION:

Member of the Transportation Coordinating Committee

Bicycle and Pedestrian Sub-Committee

AUTHORITY:

County Board Resolution 14-3B-563

TERM:

Coinciding with their Terms on the Transportation

Coordinating Committee

PER DIEM:

For County Board Supervisors Only

(Per Board Rule IV.J.)

CONFIRMATION:

Yes, by County Board of Supervisors

APPOINTMENT:

John Hanewall

(term expiring 12/31/15)
Developmental Disabilities
51 South Main Street

Janesville, WI 53545

Terry Nolan

(term expiring 12/31/14)

Janesville MPO 18 N. Jackson Street Janesville, WI 53545

Karl Schulte

(term expiring 12/31/16) Brown Cab Services Inc.

PO Box 66

Fort Atkinson, WI 53538

EFFECTIVE DATE:

APPOINTMENT TO THE TRANSPORTATION COORDINATING COMMITTEE TRANSPORTATION ADVOCACY SUB-COMMITTEE

POSITION:

Member of the Transportation Coordinating Committee

Transportation Advocacy Sub-Committee

AUTHORITY:

County Board Resolution 14-3B-563

TERM:

Coinciding with their Terms on the Transportation

Coordinating Committee

PER DIEM:

For County Board Supervisors Only

(Per Board Rule IV.J.)

CONFIRMATION:

Yes, by County Board of Supervisors

APPOINTMENT:

Michelle Gavin

(term expiring 12/31/14) Beloit Transit System 1225 Willowbrook Beloit, WI 53511

Dave Mumma

(term expiring 12/31/15) Janesville Transit System 900 North Parker Drive Janesville, WI 53545

Rob Wilkinson

(term expiring 12/31/16)

AARP/GWAAR 633 Milton Avenue Janesville, WI 53545

EFFECTIVE DATE:

APPOINTMENT TO THE CITY OF JANESVILLE JOINT REVIEW BOARD FOR TAX INCREMENTAL FINANCING DISTRICT NO. 32 AMENDMENT NO. 1 AND

TAX INCREMENTAL FINANCING DISTRICT NO. 35 AMENDMENT NO. 2

POSITION:

Member of TIF District No. 32, Amendment #1

And

Member of TIF District No. 35, Amendment #2

AUTHORITY:

Wis. Stats. 66.1105(4)

TERM:

Indefinite

PER DIEM:

Yes, Per Board Rule IV.J.

CONFIRMATION:

Yes, by County Board of Supervisors

NEW APPOINTMENT:

Jason Heidenreich

4437 Rockingham Drive Janesville, WI 53546

EFFECTIVE DATE:

<u>Use of Funds</u> 31-3000-0000-61100

Regular Wages

RESOLUTION

ROCK COUNTY BOARD OF SUPERVISORS

Board of Health INITIATED BY		Karen Cain, Health O DRAFTED BY	Officer
Board of Health SUBMITTED BY	Na Para	March 21, 2014 DATE DRAFTED	
Amending the 2014 Rotthe Environmental Hea			
WHEREAS, the Rock County H Economic & Community Develo Clearances; and			
WHEREAS, the Rock County P reimburse the Rock County Heal lead clearances at \$125 per clearances.	th Department for lead r		
WHEREAS, the amount of time the Health Department's 2014 Bu		assessments and cleara	ances was not included in
WHEREAS, an increase in work completion of work not currently		nental Health Technici	an would allow for
NOW, THEREFORE BE IT Roon this day of Department to increase the Envir from April 14, 2014 through Octoberartment Budget as follows:	, 2014 does he onmental Health Techni	eby authorize the Rocl	k County Health 1 0.4 FTE to 0.6 FTE
Source of Funds 31-3000-0000-68010	Budget <u>3/21/14</u>	Increase (Decrease)	Amended <u>Budget</u>
Cross Charges	-0-	(\$3,250)	(\$3,250)

\$2,133,955

\$3,250 \$2,137,205

12.A.1.(2)

Amending the 2014 Rock County Health Department Budget to Increase the Environmental Health Technician Position from 0.4 FTE to 0.6 FTE Page 2

Respectfully submitted,

BOARD OF HEALTH

Sandra Kraft, Chair

Richard Bostwick

Kutl Konhol M

Dr. Keith Konkol, M.D.

Dr. Connie Winter, DDS

Eric Gresens, RPH

Low Pen

Louis Peer, Vice Chair

Mike Rundle

Dr. Dean Peterson, DVM

udith Wade

FINANCE COMMITTEE ENDORSEMENT

Reviewed and approved on a vote of

1 how Maulenn

Mary Mawhinney, Chair

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson

County Administrator

FISCAL NOTE:

This resolution temporarily increases an Environmental Health Technician's work hours from 0.4 FTE to 0.6 FTE. The increased salary and fringe costs will be mostly offset by cross-charges to the Planning Department. Any additional costs will be covered by savings from Health Department personnel vacancies.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to take this action pursuant to § 59.22(2), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65.90(5)(a), W#s. Stats.

Jeffrey S. Kuglitsch Corporation Counsel

Page 3			
County Board Staff Committee	<u>ee</u> :		
J.Russell Podzilni, Chair			
Sandra Kraft, Vice Chair			
Eva Arnold			
Henry Brill			
Betty Jo Bussie			
Marilynn Jensen		·	
Mary Mawhinney			
Louis Peer			
Kurtis Yankee			

AMENDING THE 2014 ROCK COUNTY HEALTH DEPARTMENT BUDGET TO INCREASE THE ENVIRONMENTAL HEALTH TECHNICIAN POSITION FROM 0.4 FTE TO 0.6 FTE

EXECUTIVE SUMMARY

The Rock County Health Department's Environmental Health staff has the technical expertise to conduct Lead Risk Assessments and Lead Clearance Tests. Lead Risk Assessments are conducted to determine if there is a lead hazard in an environment, and Lead Clearances are conducted to determine if the lead hazard has been eliminated after rehabilitation of the environment. At the request of the Rock County Planning, Economic & Community Development Agency, the Health Department has agreed to assist with conducting Lead Risk Assessments and Lead Clearances for the HUD and CDBG grants.

The additional work of these assessments and clearances was not included in the Health Department's 2014 Budget. Currently, Health Department staff is not able to conduct the work without additional staff time. Increasing the Environmental Health Technician's position from 0.4 FTE to 0.6 FTE during the busiest time period of April 14, 2014 through October 31, 2014 would provide sufficient additional time for Environmental Health staff to complete the Lead Assessments and Clearances, and other work assignments.

The Rock County Planning, Economic & Community Development Agency will reimburse the Health Department for Lead Risk Assessments at \$250 per assessment, and Lead Clearances at \$125 per clearance. The projected revenue from Rock County Planning, Economic & Community Development Agency is \$3,250. Reimbursement from the Rock County Planning, Economic & Community Development Agency should cover most of the cost of the increased hours. If the cost is higher than expected, there are currently 2 open positions in the department, and sufficient funds in the Health Department's salary and fringe benefit accounts to cover an unexpected increase.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

<u>Land Conservation Committee</u> INITIATED BY

<u>Land Conservation Committee</u> SUBMITTED BY



Thomas Sweeney DRAFTED BY

February 27, 2014 DATE DRAFTED

AMENDING THE 2014 LAND CONSERVATION DEPARTMENT BUDGET GYPSY MOTH SUPPRESSION

WHEREAS, the Land Conservation Committee has elected to participate in the 2014 State
 Cooperative Gypsy Moth Suppression Program; and,

 WHEREAS, Wisconsin Administrative Code NR 47, requires an agency of the county to coordinate the program and act as the grant recipient; and,

WHEREAS, the Land Conservation Department has taken the appropriate action and has been designated by the WDNR as the Coordinating Agency for Rock County; and,

WHEREAS, the landowners in the unincorporated area of Afton have requested the Land Conservation Department investigate the outbreak of Gypsy Moth and determine if the area is eligible for treatment under the State Cooperative Gypsy Moth Suppression Program; and,

WHEREAS, the Land Conservation Department conducted the appropriate field work and determined that the impacted area met all program guidelines; and,

WHEREAS, the Land Conservation Department has submitted a grant application to the DNR for treatment of 29 plus acres in the Town of Rock and unincorporated area of Afton; and,

WHEREAS, the WDNR has agreed that the mapped area submitted as part of the grant application meets the program criteria and is eligible for grant funding, if federal cost sharing becomes available; and,

WHEREAS, all grants received for this program are based on a 50/50% match; and,

WHEREAS, if grant funding does not become available, the Land Conservation Department will use the gypsy moth suppression program fund balance to cover all appropriate costs associated with the treatment of the infested area.

NOW, THEREFORE, BE IT RESOLVED, that the Rock County Board of Supervisors duly assembled this _____ day of _____, 2014 does hereby approve the Gypsy Moth Suppression Grant and amends the 2014 Land Conservation budget as follows:

	BUDGET AT	INCREASE	AMENDED
A/C DESCRIPTION	<u>01/01/2014</u>	(DECREASE)	BUDGET
Source of Funds:			
62-6340-0000-41000	\$0	\$2,000	\$2,000
Federal Aid		•	
Use of Funds:			
62-6340-0000-62119			
Other Contracted Services	\$0	\$2,000	\$2,000

BE IT FURTHER RESOLVED, that the Rock County Board of Supervisors approves the Land Conservation Committee to enter into an agreement with the DNR for the aforementioned project and approves all expenditures associated with the projects implementation.

AMENDING THE 2014 LAND CONSERVATION DEPARTMENT BUDGET GYPSY MOTH SUPPRESSION

Page 2

Respectfully submitted,

Land Conservation Committee

Richard Bostwick, Cha

Harry Wiedenfeld

Larry Wiedenfeld, Vice Chair

Finance Committee Endorsement

Reviewed and approved on a vote of

<u>4-0</u>

Mary Mawhinney, Chair

Eva Arnold

Edwin Nash

Jorvain Pleasant Ir

David R. Rebout, USDA-FSA

Alan Sweeney

Fred Yoss

FISCAL NOTE:

This resolution authorizes the acceptance and expenditure of \$2,000 in Federal Aid for the Gypsy Moth Suppression program. If the grant funding does not become available, a transfer in from the Gypsy Moth Suppression program fund balance, which has a current balance of \$16,845, will be used as the funding source.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pulsuant to sec. 65.90(5)(a), Wis. Stats.

Jeffrey . Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended

Craig Knutson County Administrator

EXECUTIVE SUMMARY

This resolution requests the Land Conservation Department's budget be amended to include the Gypsy Moth Suppression Program. The Wisconsin Department of Natural Resources and landowners in the Town of Rock approached the Land Conservation Department in September of 2013, to coordinate this program. The Land Conservation Department identified a high population of this very destructive moth in Afton, along Bass Creek. The Land Conservation Committee agreed to coordinate the program for Rock County and submit all necessary grant application materials for the suppression of the Gypsy Moth population identified in Rock County.

A grant request was submitted to the DNR in December 2013 to support suppression activities and aerial spraying. The County LCD received notification of a grant approval notice, contingent on Federal Cost Sharing availability, on February 26, 2014. The grant received from the US Forest Service, through DNR is based on a 50% local match and 50% Federal match. The local match, or full funding will come from the Gypsy Moth Suppression program fund balance.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Human Services Board
INITIATED BY

Sara Mooren DRAFTED BY

<u>Human Services Board</u> SUBMITTED BY

27

28 29

30

31

32

33

34

Federal Aid

Use of Funds

36-3642-0000-64604

36-3642-0000-68204

Program Expense

Allocated CPS

March 13, 2014 DATE DRAFTED

Amending the 2014 Human Services Department Budget To Accept Funding for Post Reunification Support Program

WHEREAS, the Wisconsin Department of Children and Families has awarded the Department \$79,200 1 in Post Reunification Support Program funds; and, 2 3 WHEREAS, grant funds will be used to provide post reunification support services to children and their 4 families who are being reunified after an out of home care placement to promote family stability and 5 6 adjustment; and, 7 8 WHEREAS, other goals of the program include empowering parents to strengthen care-giving, problem-9 solving, and coping skills, reducing the likelihood of child maltreatment recurrence and re-entry of a child to out of home care after reunification, and improving the short and long term well-being of the child and 10 11 their family; and, 12 13 WHEREAS, these funds will provide flexible post reunification support services to approximately six children and their families at a time. 14 15 NOW, THEREFORE, BE IT RESOLVED by the Rock County Board of Supervisors duly assembled 16 17 , 2014, does hereby authorize the acceptance of Post Reunification Support Program funds. 18 19 20 BE IT FURTHER RESOLVED, that the Human Services Department budget for 2014 be amended as follows: 21 22 23 Budget Increase Amended 24 Account/Description 3/13/14 **Budget** (Decrease) Source of Funds 25 36-3642-0000-42100 26 \$0 \$79,200 \$79,200

\$0

\$0

\$74,200

\$5,000

\$74,200

\$5,000

14-4A-569

Amending the 2014 Human Services Department Budget To Accept Funding for Post Reunification Support Program Page 2

Human Services Board

Brian Knudson

Brian Knudson, Chair

Ally Jun Mauratan Survey and Mary Mawhinney, Chair

Terry Fell

Billy Bob Crahn

Ashley Kleven

Phillip Owens

Town Thomas

FINANCE COMMITTEE ENDORSEMENT

Reviewed and approved on a vote of 4-0

Mary Mawhinney, Chair

Mary Mawhinney, Chair

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

FISCAL NOTE:

Absent

Absent Marvin Wopat

Shirley Williams

Respectfully submitted,

This resolution authorizes the acceptance and expenditure of \$79,200 in Federal Aid for the post reunification support program. No additional County funds are required.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65.90(5)(a), Wis. Stats.

Jeffrey S. Kuglitsch Corporation Counsel

Executive Summary

Amending the 2014 Human Services Department Budget To Accept Funding for Post Reunification Support Program

The Wisconsin Department of Children and Families has awarded the Department \$79,200 in Post Reunification Support Program funds. These funds are part of a state IV-E waiver demonstration project. Funds will be used in Rock County to provide post reunification support services to children and their families who are being reunified after an out of home care placement.

The goals of the program are: 1) Promote family stability and adjustment after reunification; 2) Empower parents to strengthen care-giving, problem-solving, and coping skills; 3) Reduce the likelihood of child maltreatment recurrence and re-entry of a child to out of home care after reunification, and; 4) Improve the short and long term well-being of the child and their family.

These funds will provide flexible post reunification support services to approximately six children and their families at a time.

Human Services Board INITIATED BY

Human Services Board SUBMITTED BY



Sara Mooren DRAFTED BY

March 13, 2014 DATE DRAFTED

Amending the 2014 Human Services Department Budget to Accept In-Home Safety Services Initiative Grant Funds

WHEREAS, the Wisconsin Department of Children and Families awarded a third year of grant 1 funding for \$254,129 through the In-Home Safety Services Initiative; and, 2 3

4 5

WHEREAS, the Human Services Department, as part of a consortium with Jefferson and Green Counties, is continuing to develop and manage a comprehensive, family centered safety services and 6 monitoring program; and,

7

WHEREAS, the program is designed to monitor and support safety plans, train and support Child 8 Protective Services (CPS) staff in safety management, develop informal supports within family systems, 9 enhance protective factors, and provide 24/7 coverage for safety management, monitoring and crisis 10 11 response and support to families; and,

12 13

WHEREAS, the target population served by this project are families involved with CPS who have been determined to be unsafe based on a standardized safety assessment; and,

14 15 16

17

WHEREAS, the long term goals of the initiative are to improve child safety outcomes, increase the availability of safety service resources, enhance family protective factors, decrease the need for CPS involvement, and increase the ability of CPS workers to assess safety and develop effective safety plans.

18 19 20

NOW, T	HEREFORE, BE	IT RESOLVED by the Rock County Board of Supervisors duly assembled
this	day of	, 2014, does hereby authorize the acceptance of the In-Home
Safety Se	rvices Initiative gran	nt; and,

22 23 24

21

BE IT FURTHER RESOLVED, that the Human Services Department budget for 2014 be amended as follows:

25 26

27		Budget	Increase	Amended
28	Account/Description	<u>3/13/14</u>	(Decrease)	Budget
29	Source of Funds			
30	36-3639-0000-42100	\$0	\$254,129	\$254,129
31	Federal Aid			·
32				
33	Use of Funds			
34	36-3639-0000-62119	\$0	\$242,028	\$242,028
35	Other Contracted Services			ŕ
36	36-3639-0000-68204	\$0	\$12,101	\$12,101
37	Allocated CPS		•	,

Amending the 2014 Human Services Department Budget to Accept In-Home Safety Services Initiative Grant Funds Page 2

Respectfully submitted,

Human Services Board					
Brian Knydson					
Brian Knudson, Chair			_		
1 . 1		1	_		

Weaver-Landers, Vice Chair

Phillip Owens

Absent Shirley Williams

Absent Marvin Wopat FINANCE COMMITTEE ENDORSEMENT

Reviewed and approved on a vote of 4/-0

Mary Mawhinney, Chair

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

FISCAL NOTE:

This resolution authorizes the acceptance and expenditure of \$254,129 in Federal Aid for In-Home Safety Services. No additional County funds are required.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65,90(5)(a) / Wis Stats

effrey S. Kuglitsch Corporation Counsel

Executive Summary

Amending the 2014 Human Services Department Budget to Accept In-Home Safety Services Initiative Grant Funds

This resolution authorizes acceptance of \$254,129 through the In-Home Safety Services Initiative grant administered by the Wisconsin Department of Children and Families. The resolution also amends the 2014 HSD Budget. This is the third year of funding.

The Human Services Department, as part of a consortium with Jefferson and Green Counties, will continue to develop and manage a comprehensive, family centered safety services and monitoring program. Programming is designed to monitor and support safety plans, train and support Child Protective Services (CPS) staff in safety management, develop informal supports within family systems, enhance protective factors, and provide 24/7 coverage for safety management, monitoring and crisis response and support to families.

The target population served by this project are families involved with CPS who have been determined to be unsafe based on a standardized safety assessment. The long term goals of the initiative are to improve child safety outcomes, increase the availability of safety service resources, enhance family protective factors, decrease the need for CPS involvement, and increase the ability of CPS workers to assess safety and develop effective safety plans.

Rock County will be the fiscal agent for the project. Orion Family Services will provide 24/7 safety services to identified Rock, Green and Jefferson Counties' families.

No additional county funds are required.

ROCK COUNTY BOARD OF SUPERVISORS

Sheriff Robert D. Spoden	
INITIATED BY	
Public Safety and Justice	
Committee	
SUBMITTED BY	



Deputy Christopher Krahn DRAFTED BY

March 13, 2014
DATE DRAFTED

AUTHORIZING ACCEPTANCE OF COPS AND KIDS FOUNDATION GRANT

1 WHEREAS, the Cops and Bobbers fund is a component of the Cops and Kids Foundation, Inc.; and,

WHEREAS, the Cops and Kids Foundation is a nonprofit organization whose programs and services provide law enforcement with the tools and funding necessary to implement award winning community service; and,

WHEREAS, the Rock County Sheriff's Office is eligible to receive a grant of \$1,000 from the Cops and Kids Foundation; and,

WHEREAS, the grant funds will be used to support the Rock County Cops and Bobbers fishing program.

NOW, THEREFORE BE IT RESOLVED by the Rock County Board of Supervisors assembled this ____ day of ____ 2014, that the Rock County Sheriff is authorized to accept funds from the Cops and Kids Foundation; and,

BE IT FURTHER RESOLVED, that the 2014 budget be amended as follows:

Account Description <u>Account Number</u>	Budget at <u>01/01/14</u>	Amount <u>Incr (Decr)</u>	Amended <u>Budget</u>
Source of Funds Other Grants and Contracts 21-2144-2014-46002	\$0	\$1,000	\$1,000
Use of Funds Sundry Expense 21-2144-2014-64904	\$0	\$1,000	\$1,000
Respectfully submitted,			
Public Safety and Justice Co	ommittee		Finance Committee Endorsement
Ivan Collins, Chair		·	Reviewed and approved on a vote of
Mary Beaver		-	Mary Mawhinney, Chair
Henry Brill			
Brian Knudson			
Larry Wiedenfeld			

AUTHORIZING ACCEPTANCE OF COPS AND KIDS FOUNDATION GRANT 12.A.5.(2) Page 2 Page 2

FISCAL NOTE:

This resolution authorizes the acceptance and expenditure of \$1,000 in grant funds for the Cops and Bobbers fishing program. No County funds are required.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to 5.90(5)(a), Wis, Stats.

poration Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson

County Administrator

Executive Summary Authorizing Acceptance of Cops and Kids Foundation Grant

The Rock County Sheriff's Office has received a grant from the Cops and Bobbers fund, a component of the Cops and Kids Foundation, Inc. The Cops and Kids foundation is an area nonprofit organization whose programs and services provide law enforcement with the tools and funding necessary to implement their award winning community service.

The grant is for \$1,000 and will be used to support the Rock County Cops and Bobbers fishing program. Various fishing supplies, boat rental, and other related materials will be purchased with the funds. Additionally, Cops and Bobbers will be providing fishing poles, life jackets, and T-shirts.

The primary goal of the Cops and Bobbers program is to teach kids how to fish. The cops are the hosts and volunteers from the community can also assist. The goal of Cops and Bobbers is to get kids hooked on fishing rather than drugs and crime. Kids will get to interact with local cops and form a positive and friendly relationship.

The Cops and Kids grant is renewable for up to three years, but we must show clear evidence we are on route to be self-sufficient. The Rock County Sheriff's Office will receive funding, training in implementing the program, and training in fund raising to help sustain the program.

A total of two Cops and Bobbers events will be held the first year at different locations throughout Rock County. A maximum of 20 kids in the community for each event will get the chance to take part in the program.

No additional County funds are needed.

RESOLUTION NO. 14-4A-572 AGENDA NO. 12.B.

INITIATED: FINANCE DIRECTOR

SUBMITTED BY: FINANCE COMMITTEE

DATE: APR 0 3 2014

WHEREAS. THE FINANCE COMMITTEE HAS EXAMINED THE FOLLOWING BILLS OVER \$10,000 AS REQUIRED BY COUNTY BD. RULE H.(3), AND FOUND THEM TO BE PROPER AND WITHIN BUDGET.

NOW THEREFORE BE IT RESOLVED. THE ROCK COUNTY BOARD OF SUPERVISORS AT ITS REGULAR MEETING ON APR 1 0 2014 . APPROVES PAYMENT AND ALITHOPIZES AND DIRECTS THE COUNTY SEEDING. COUNTY TREASURER TO PAY THE SAME.

Vendor Name	Fund Name	Department N	ame Program N	ame	Amount	Claim Amount
NETECH CORP	ISF-CS	INFORMATION	T IT CAPITAL P	R 87513	71,413.70	
						71,413.70
SECURED LIVING	SRF-DD BOARD	DD BOARD	D.D.BOARD	0214POC	10,500.00	
			•			10,500.00
TURNING POINT SYSTEMS GROUP	ISF-CS	INFORMATION	T INFORMATION	T 14101	10,137.00	10,137.00
CLAIMS IN THE AMOUNT OF	92,050.70			RESPECTFULLY SUBMITTED,		

HAVE BEEN APPROVED AND CHECKED BY THE GOVERNING COMMITTEES.

FINANCE COMMITTEE

LEGAL NOTE:

THE COUNTY BOARD RULE CITED REQUIRES THE COUNTY BOARD TO EXAMINE AND SETTLE ALL CLAIMS OVER \$10,000.00

CORPORATION COUNSEL

FISCAL NOTE

ABOVE LISTED CLAIMS ARE FULLY FUNDED.

SHERRY OJA FINANCE DIRECTOR ADMINISTRATIVE NOTE

RECOMMENDED

CRAIG KNUTSON COUNTY ADMINISTRATOR APPROVAL OF ENCUMBRANCES OVER \$10,000.00

Page 1

RESOLUTION NO. 14-4A-573

12.C. AGENDA NO.

INITIATED: FINANCE DIRECTOR

SUBMITTED BY: FINANCE COMMITTEE

APR 0 3 2014

WHEREAS, THE FINANCE COMMITTEE HAS EXAMINED THE FOLLOWING ENCUMBRANCES OVER \$10,000 AS REQUIRED BY COUNTY BD. RULE H.(3), AND FOUND THEM TO BE PROPER AND WITHIN BUDGET.

NOW THEREFORE BE IT RESOLVED, THE ROCK COUNTY BOARD OF SUPERVISORS AT ITS REGULAR MEETING ON APR 1 0 2014 , APPROVES PAYMENT AND AUTHORIZES AND DIRECTS THE COUNTY CLERK AND COUNTY TREASURER TO PAY THE SAME, UPON ACCEPTANCE BY THE DEPARTMENT HEAD.

Vendor Name

Fund Name

Department Name Program Name

PR Number

Claim Amount

ORION FAMILY SERVICES

SANOFI PASTEUR

SRF-HUMAN SERVIC HUMAN SERVICES HEALTH DEPT. HEALTH DEPT

IN-HM SFTY SRVCS HEALTH DEPT.

R1401636 R1401764 216,294.33 42,682.09

CLAIMS IN THE AMOUNT OF

258,976.42

HAVE BEEN APPROVED AND

CHECKED BY THE GOVERNING COMMITTEES.

FINANCE COMMITTEE

LEGAL NOTE:

THE COUNTY BOARD RULE CITED REQUIRES THE COUNTY BOARD

TO EXAMINE AND SETTLE ALL CLAIMS OVER \$10.000.00

COMPORATION COUNSEL

FISCAL NOTE

ABOVE LISTED CLAIMS ARE FULLY FUNDED.

SHERRY OJA

FINANCE DIRECTOR

ADMINISTRATIVE NOTE

RECOMMENDED

CRAIG KNUTSON

COUNTY ADMINISTRATOR

RESOLUTION NO.	1 / / / 57 /
RESOLUTION NO.	14-4A-574

A CIENTO A NIC	10 D 1 (1)	
AGENDA NO.	12.D.1.(1)	

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Dave O'Connell, HR Director DRAFTED BY

March 26, 2014
DATE DRAFTED

ESTABLISHING THE SALARY FOR THE ROCK COUNTY CLERK OF COURTS FOR THE 2015-2018 TERM

	-		FOR THE 2015	5-2018 TERM		
2	WHEREAS, the Rock Courts for the 2015-20			s the compensation	on for the Rock County	Clerk Of
	WHEREAS, the Coun Clerk of Courts.	ity Board Staff C	ommittee has con	nsidered the issue	of compensation for t	he Rock County
7 8 9	below schedule: 4.07% 2017, and 2%, effective	, 2014, set the b, effective Janua e January 1, 201	e increase in salar ary 1, 2015, 2.009	ry for the Rock C %, effective Janua	ounty Clerk of Courts ary 1, 2016, 2.0%, effe	as per the ective January 1,
13 14 15		01/01/2015 \$72,069.16	01/01/2016 \$73,510.54	01/01/2017 \$74,980.00	01/01/2018 \$76,480.00	
18	BE IT FURTHER RE the Wisconsin Retirem contributions required	ent System in ac	the aforemention cordance with law	ed County elected wand the County	d official is entitled to shall pay only its shar	participate in e of
21 22 23 24	BE IT FURTHER RE County's health insura from time to time, und- represented manageria represented manageria	nce program sub er the same term l County employ	ject to the terms as and conditions as sees who are not la	and conditions of as the health insur aw enforcement r	the program, which m rance coverage offered nanagerial employees	ay be modified to non-
	Respectfully Submitted	d,				
	COUNTY BOARD ST	TAFF COMMIT	ГЕЕ			
	J. Russell Podzilni, Ch	air	Survey August Annual Annua	Marilyn	n Jensen	
	Sandra Kraft, Vice Ch	air		Mary M	awhinney	
	Eva Arnold		and the second s	Louis Pe	eer	
	Henry Brill			Kurtis Y	ankee	
	Betty Jo Bussie		***************************************			
		•				

ESTABLISHING THE SALARY FOR THE ROCK COUNTY CLERK OF COURT FOR THE 2015-2018 TERM

Page 2

FISCAL NOTE:

Sufficient funds will need to be included in the 2015 - 2018 budgets for the cost of this position.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to take this action pursuant to sec. 59.22(1), Wis. Stats.

Jeffrey S Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Matter of policy.

Craig Knutson County Administrator

Executive Summary:

Under State law every four years the County Board must set the salary for the elected officials. In 2012 the County Board set the salaries for the County Clerk, County Treasurer and Register of Deeds for 2013, 2014, 2015, and 2016.

This year the Board must set the salaries for the Sheriff and Clerk of Courts for 2015, 2016, 2017 and 2018.

The County Board Staff Committee asked the Rock County Human Resource Department for comparable information. The HR Director provided salary data from all of the other counties in the State for their Clerk of Courts' salaries in 2011-2014. He also provided the Committee with the best 2015 data available for the traditional counties Rock County uses for comparables: Brown, Kenosha, Marathon, Outagamie, Racine, Sheybogan, and Winnebago. He also provided information on the salaries for the Rock County Clerk, County Treasurer and Register of Deeds. The current Clerk of Courts asked that his job be compared to that of the Rock County Child Support Director and that comparable information was also presented

After discussion at the County Board Staff Committee meetings on March 11 and 25, the Committee directed the HR Director to prepare this resolution. Under the resolution adopted by the Committee, the salary of the Rock County Clerk of Courts would be increased so that it is equal to the Rock County Clerk, County Treasurer and Register of Deeds. This would be accomplished by increasing the salary by 4.07% in 2015 and 2% in 2016. The increase for the 3rd and 4th years would also be 2% each year.

The Clerk of Courts would also begin paying the employee portion of the WRS contribution (currently 7%) just like the County Clerk, County Treasurer and Register of Deeds.

This increase to the Rock County Clerk of Court's salary will keep that salary in line with the Rock County Clerk, County Treasurer and Register of Deeds.

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Dave O'Connell, HR Director DRAFTED BY

March 27, 2014 DATE DRAFTED

$\frac{\text{ESTABLISHING THE SALARY FOR ROCK COUNTY SHERIFF}}{\text{FOR THE 2015-2018 TERM}}$

	WHEREAS, the Rock County Board of	Supervisors set	s the compensati	ion for the Rock County Sheriff for the		
2 3	2015-2018 term of office; and,					
4	WHEREAS , the County Board Staff Committee has considered the issue of compensation for the Rock County Sheriff.					
	NOW, THEREFORE, BE IT RESOLV	ED, that the R	lock County Boa	rd of Supervisors duly assembled this		
8	day of, 2014, set the	increase in sala	ry for the Rock	County Sheriff as per the below		
	schedule: 2.5% effective January 1, 2015 2%, effective January 1, 2018 to be paid					
	year.	equality over a	period of 20 of 2	r regular pay periods unoughout each		
12	•					
13	01/01/2015	<u>1/01/2016</u>	01/01/2017	01/01/2018		
14 15	\$105,389.00	\$112,597.00	\$114,849.00	\$117,146.00		
16 17 18	BE IT FURTHER RESOLVED , that the Wisconsin Retirement System (WRS) elected official's contribution of the elect which the elected official shall begin pay) in accordance ed official's ear	with law and the mings as require	e County shall contribute the full		
21 22	BE IT FURTHER RESOLVED, that in protective status position prior to July 1, WRS contribution, currently seven perce	2011, by law tl				
25 26	BE IT FURTHER RESOLVED , that the available to appointed department heads, plans, as may be modified from time to time.	under the same	Sheriff shall be terms and cond	eligible to participate in all the benefits litions, including the health and dental		
	Respectfully Submitted,					
	COUNTY BOARD STAFF COMMITTE	BE				
: *	J. Russell Podzilni, Chair	· · · · · · · · · · · · · · · · · · ·	Marily	nn Jensen		
	ŕ		•			
4	Sandra Kraft, Vice Chair Mary Mawhinney					
	Eva Arnold		Louis F	Peer		
*.***	Henry Brill	e-manusco-construint	Kurtis	Yankee		
	Betty Jo Bussie					

ESTABLISHING THE SALARY FOR THE ROCK COUNTY SHERIFF FOR 2015 $-\,2018$ TERM Page 2

FISCAL NOTE:

Sufficient funds will need to be included in the 2015-2018 budgets for the cost of this position.

Sherry Oja Finance Director

LEGAL NOTE:

The County Board is authorized to take this action pursuant to sec. 59.22(1), Wis. Stats.

Jeffrey S Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Matter of policy.

Craig Knutson County Administrator

Executive Summary:

Under State law every four years the County Board must set the salary for the elected officials. In 2012 the County Board set the salaries for the County Clerk, County Treasurer and Register of Deeds for 2013, 2014, 2015, and 2016.

This year the Board must set the salaries for the Sheriff and Clerk of Courts for 2015, 2016, 2017 and 2018.

The County Board Staff Committee asked the Rock County Human Resource Department for comparable information. The HR Director provided salary data from all of the other counties in the State for their Sheriff's and Chief Deputies' salaries in 2011-2014. He also provided the Committee with the best 2015 data available for the traditional counties Rock County uses for comparables: Brown, Kenosha, Marathon, Outagamie, Racine, Sheybogan, and Winnebago. In addition the Sheriff's Office provided information for three additional counties: Dane, LaCrosse and Walworth; and for the Chiefs of Police in the Cities of Beloit and Janesville.

After discussion at the County Board Staff Committee meetings on March 11 and 25, the Committee directed the HR Director to prepare this resolution. Under the resolution adopted by the Committee, the salary of the Rock County Sheriff would be increased by 1.5% in 2015 (the same as the County Clerk, County Treasurer and Register of Deeds) and then increased by adding a lump sum of \$5,000 in 2016 plus 2% of that number, and then increased by 2% in each of the next two years of the four-year term.

The Sheriff's salary would also be increased by an additional 1% in 2015 with a corresponding 1% WRS contribution to be paid by the Sheriff. This one percent contribution is the same as all of the other law enforcement employees in Rock County who have protective status. [Note. This provision applies to anyone who is elected Sheriff in 2014 and is a current member of the Wisconsin Retirement System and has protective status. In the event a newly elected Sheriff was not enrolled in WRS in a protective status position prior to July 1, 2011 that person would have to pay the employee share of their WRS contribution like the County Clerk, County Treasurer, Register of Deeds and Clerk of Courts. The employee share for all of those elected positions is currently seven percent in 2014.]

This increase to the Rock County Sheriff's salary will keep that salary in line with other comparables and also create separation between the Sheriff's salary and that of the Chief Deputy.

RESOLUTION NO.	14-4A-576	
RESOLUTION NO.	14-4A-3/0	

AGENDA NO. 12.E.(1)

RESOLUTION

ROCK COUNTY BOARD OF SUPERVISORS

Public Works Committee
Initiated by
·
Public Works Committee
& Parks Advisory Committee
Submitted by

Brent Fox

Rick Richard



Lori Williams, Parks Director Drafted by

March 24, 2014 Date Drafted

	IENT OF NATURAL RESOURCES IOBILE GRANT FUNDS			
WHEREAS, the Rock County Board of June, 1981, adopted the Rock County Sr	Supervisors Resolution #81-6A-038, on the 11th day of nowmobile Plan; and,			
WHEREAS, Rock County desires to participate in snowmobile grant funded projects pursuant to provisions of s.23.09(11) of the Wisconsin Statutes; and,				
WHEREAS, grant funds are available from the State of Wisconsin Department of Natural Resources (DNR) and a resolution of application for Snowmobile Grant Funds is required; and,				
WHEREAS, Rock County is interested in operating the snowmobile trail for public outdoor recreation purposes as described in the application; and,				
WHEREAS, financial aid is required to	o carry out the project.			
Division-Public Works Department, to	ereby authorizes Lori Williams, Parks Director, Parks act on behalf of Rock County to submit an application to			
Division-Public Works Department, to	ereby authorizes Lori Williams, Parks Director, Parks act on behalf of Rock County to submit an application to			
Division-Public Works Department, to the State of Wisconsin Department of N Funds that may be available.	ereby authorizes Lori Williams, Parks Director, Parks act on behalf of Rock County to submit an application to			
Division-Public Works Department, to the State of Wisconsin Department of N Funds that may be available. Respectfully submitted,	act on behalf of Rock County to submit an application to Natural Resources for financial aid for Snowmobile Grant			
Division-Public Works Department, to the State of Wisconsin Department of N Funds that may be available. Respectfully submitted, PUBLIC WORKS COMMITTEE	ereby authorizes Lori Williams, Parks Director, Parks act on behalf of Rock County to submit an application to Natural Resources for financial aid for Snowmobile Grant PARKS ADVISORY COMMITTEE			

Authorizing Application with Wisconsin Department of Natural Resources for Snowmobile Grant Funds

Page 2

FISCAL NOTE:

This resolution only authorizes an application for a grant and, therefore, has no fiscal impact at this time. If a grant is awarded, a subsequent resolution would be required to accept the grant.

Sherry Oja
Finance Director

LEGAL NOTE:

The authority to accept grant funds pursuant to sec. 59.52(19), Wis. Stats., necessarily implies the authority to make application for such funds.

Jeffrey S. Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

- EXECUTIVE SUMMARY -

AUTHORIZING APPLICATION WITH WISCONSIN DEPARTMENT OF NATURAL RESOURCES FOR SNOWMOBILE GRANT FUNDS

This resolution provides authorization to apply for funding for the 2014-2015 Rock County Snowmobile Trail Program.

The DNR Snowmobile Grant of \$56,600 would cover 226.4 miles of trail. The snowmobile trail project is 100% grant funded. Any field work (includes labor, materials, and machinery) by DPW Parks Division or Highway Division is 100% billed back to the grant. The area Snowmobile Alliance provides trail signage and grooming and is reimbursed for those services after the county costs are covered.

These funds are 100% provided by the payments snowmobilers have made through license and prorated fuel tax payments. Rock County receives a 50% advance payment check after the completed contract is signed, the balance due upon final close out of the grant.

ROCK COUNTY BOARD OF SUPERVISORS

SHERIFF ROBERT SPODEN INITIATED BY

Larry Wiedenfeld

PUBLIC SAFETY & JUSTICE
SUBMITTED BY



CMDR ERIK CHELLEVOLD

DRAFTED BY

MARCH 18, 2014 DATE DRAFTED

PROCLAIMING CORRECTIONAL EMPLOYEES WEEK

WHEREAS, the State of Wisconsin has proclaimed May 4-10, 2014 as Correctional Employees Week, to recognize the significant work and unique contributions of correctional employees; and, 3 WHEREAS, Rock County Correctional employees demonstrate a selfless commitment to ensuring 5 public safety by the diligent supervision of sentenced and pretrial offenders and adjudicated juveniles; 6 7 8 WHEREAS, the quality of life in Rock County is enhanced by the commitment of correctional 9 employees to restoring a portion of the County's citizenry to a more positive position in society by 10 providing offenders fair and impartial custody, treatment, nutrition, education and healthcare; and, 11 12 WHEREAS, as public servants, correctional employees dutifully perform their work with courage, 13 pride and true professionalism; 14 15 NOW THEREFORE BE IT RESOLVED, that the Rock County Board of Supervisors assembled this 16 2014, proclaim May 4-10, 2014 to be Correctional Employees Week and 17 call upon all our citizens to especially honor and show our appreciation for correctional employees 18 serving Rock County. Respectfully Submitted, PUBLIC SAFETY & JUSTICE COMMITTEE Ivan Collins, Chair Henry Brill, Vice Chair Mary Beaver Brian Knudson

ROCK COUNTY BOARD OF SUPERVISORS

INITIATED BY

4

5

6 7

8

9

10

11 12

13

14 15

16

17 18 PUBLIC SAFETY & JUSTICE
SUBMITTED BY



GRACE BECKER

DRAFTED BY

MARCH 18, 2014 DATE DRAFTED

PROCLAIMING POLICE OFFICER WEEK

WHEREAS, the State of Wisconsin has proclaimed May 11-17, 2014, as Police Officer Week, to recognize the significant work and unique contributions of Law Enforcement Officers; and,

WHEREAS, Rock County Law Enforcement Officers demonstrate a selfless commitment to safeguarding the rights and freedoms of Rock County; and,

WHEREAS, the quality of life in Rock County is enhanced by the commitment of Law Enforcement Officers to ensure the safety of the County's citizenry by safeguarding life and property, by protecting them against violence, and disorder, by protecting the innocent against deception, and the weak against oppression; and,

WHEREAS, as public servants, Rock County Law Enforcement Officers dutifully perform their work with courage, pride and true professionalism;

NOW THEREFORE BE IT RESOLVED, that the Rock County Board of Supervisors assembled this day of ______ 2014, proclaim May 11-17, 2014, to be Rock County Law Enforcement Officers Week and call upon all our citizens to especially honor and show our appreciation for Law Enforcement Officers serving Rock County.

Respectfully Submitted,

PUBLIC SAFETY & JUSTICE COMMITTEE

Ivan Collins, Chair

Mary Beaver

Henry Brill

Brian Knudson

Larry Wiedenfeld

14-4A-578

ROCK COUNTY BOARD OF SUPERVISORS

District Attorney David J. O'Leary
INITIATED BY
Public Safety & Justice

SUBMITTED BY

6

7

8

10

11

20

21

22 23

24

25

26 27

28



Renee Grover
DRAFTED BY

February 19, 2014
DATE DRAFTED

RECOGNIZING DEFERRED PROSECUTION DIRECTOR KRISTIN KOEFFLER

WHEREAS, Kristin Koeffler began her employment with Rock County on April 11, 1977 as an Administrative
Assistant in the Rock County District Attorney's Deferred Prosecution Program (DPP), and began serving as the
Acting Director on September 26, 1977, and was promoted to the Deferred Prosecution Director on March 9, 1978;
and,

WHEREAS, during her tenure with the Deferred Prosecution Program, Kristin Koeffler was instrumental in the implementation and development of the Domestic Violence Intervention Program (DVIP); and,

WHEREAS, Kristin Koeffler has dedicated her career toward helping both first time and domestic violence offenders learn to modify their thinking or behavior to become better citizens; and,

WHEREAS, Kristin Koeffler has served the citizens of Rock County for 37 years; has worked with a host of elected officials, administrators, prosecutors, law enforcement, defense attorneys, community leaders and concerned citizens in order to make Rock County a safer community; has worked with over 7,750 DPP clients and more than 8,000 DVIP clients; has served on two Governor's commissions, the Sentencing Committee chaired by Prof. Frank Remington, and the Domestic Violence Counsel with Gov. Lee Dryfus; has served as a board of director for the battered womens' shelters and trained volunteers for shelter staff for both Beloit and Janesville; has taught judges, prosecutors and law enforcement around the state on the issues of domestic violence; and,

WHEREAS, Kristin Koeffler will retire from public service on May 2, 2014.

NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors duly assembled this _____ day of _____, 2014, does hereby recognize Kristin Koeffler for her over 37 years of faithful service and recommends that a sincere expression of appreciation be given to Kristin Koeffler along with best wishes for the future.

BE IT FURTHER RESOLVED, that the County Clerk be authorized and directed to furnish a copy of this resolution to Deferred Prosecution Director Kristin Koeffler.

Kurtis L. Yankee

Respectfully submitted,			
PUBLIC SAFETY & JU	STICE COMMITTEE	COUNTY BOARD STAFF CO	MMITTEE
Ivan Collins, Chair		J. Russell Podzilni, Chair	
Brian Knudson		Sandra Kraft, Vice Chair	
Mary Beaver		Eva Arnold	
Henry Brill		Henry Brill	
Larry Wiedenfeld		Betty Jo Bussie	
		Marilynn Jensen	
		Mary Mawhinney	
		Louis Peer	

Hon. James P. Daley Presiding Judge INITIATED BY



Juelane J. Teubert Circuit Court Office Manager DRAFTED BY

April 1, 2014 DATE DRAFTED

Public Safety & Justice

	BMITTED BY	DATE DRAFTED
JUL		E CHARLES HOLZNECHT
•		
1 2	whereas, Charles Holznecht has gi service; and,	ven the citizens of Rock County 33 years of public
3	service, and,	
4	WHEREAS, Charles Holznecht began h	is career on March 2, 1981, as Court Commissioner for
5	Rock County, and,	
6		
7		ed as Court Commissioner for Rock County until his
8	retirement on April 1, 2014; and,	
9 10	WHEREAS the Rock County Board of	Supervisors, representing the citizens of Rock County,
11		or his achievements and significant contributions to the
12	Rock County Circuit Court and to the ci	tizens of Rock County, and to thank him for his many
13	years of faithful service.	
14	NOW EXERCISE DE LE DECOLU	CTED at a day Day 1 Courter Day 1 of Courter 1 to
15 16		VED, that the Rock County Board of Supervisors duly, 2014 does hereby recognize Charles Holznecht for 33
17	years of service and extends best wishes t	o him in his future endeavors.
18.	J 00000 02 000 1100 0000 0000 0000 110000 0	
19		e County Clerk is hereby authorized and directed to
20	furnish a copy of this resolution to Charle	s Holznecht.
	Respectfully submitted,	
F	PUBLIC SAFETY AND JUSTICE COMP	MITTEE
· T.	Calling Chair	
. 1	Ivan Collins, Chair	
-		
ŀ	Henry Brill, Vice Chair	
N	Mary Beaver	
Ī	Brian Knudson	
-	TYP 1 C11	
Ţ	Larry Wiedenfeld	

TO RECOGNIZE CHARLES HOLZNECHT

COUNTY BOARD STAFF COMMITTEE

J. Russell Podzilni, Chair
Sandra Kraft, Vice Chair
Eva Arnold
Henry Brill
Betty Jo Bussie
Marilynn Jensen
Mary Mawhinney
Louis Peer

Kurtis Yankee

ROCK COUNTY BOARD OF SUPERVISORS

	Board of Health INITIATED BY	STATE OF STA	Timothy Banwell, EH Director DRAFTED BY			
	Board of Health SUBMITTED BY		March 25, 2014 DATE DRAFTED			
	Rock County	Rabies Awa	reness Week			
1 2	WHEREAS, rabies is a disease present in the wildlife of Rock County; and					
3	WHEREAS, once a human or animal con	ntracts rabies, the	e disease is always fatal; and			
4 5	WHEREAS, wildlife is an important rese	ervoir of rabies for	or household pets; and			
6 7 8	WHEREAS, animals in Rock County bit by law enforcement, health care providers	e approximately s, veterinarians, a	400 persons each year, requiring follow-up and the health department; and			
9 10 11	WHEREAS, at least 11 persons were refe 2013; and	HEREAS, at least 11 persons were referred to their health care providers for rabies vaccination in 213; and				
12 13	WHEREAS, approximately 10,000 to 20	,000 dogs and ca	ats are not vaccinated in Rock County; and			
WHEREAS, the control and elimination of rabies in cats and dogs through vaccination r only cost effective way to protect humans from contracting the disease.						
NOW, THEREFORE BE IT RESOLVED, that the Rock County Board of Supervisors duly a on this day of, 2014 does hereby declare the week of April 20 throu April 26, 2014 as 'Rock County Rabies Awareness Week', and encourage all cat and dog owner responsible by having their pets vaccinated for rabies.						
	Respectfully submitted,					
	BOARD OF HEALTH					
	Dandes Kroget		Louis Pen			
	Sandra Kraft, Chair	Louis	Peer, Vice Chair			
	Richard Bostwick	Mike	Rundle			
	Kith Konhol m Dr. Keith Konkol, M.D.		an Leterson, DVM			
	C Winty OD	Lu	dithwade			
	Dr. Connie Winter, DDS	Judith	Wade			
	Eric Gresens, RPH	<i>V</i>				
	Tito Otosons, P.L.U.					

RESOLUTION NO.	14-4A-582

AGENDA NO. 12.K.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Nick Osborne, Assistant to the County Administrator DRAFTED BY

March, 10, 2014 DATE DRAFTED

	RECOGNIZING IVAN COLLINS					
	2002; and,	B, in				
4	,					
5	Standing Committees:					
	Health Services Committee					
	Public Safety and Justice Committee, Chair					
	General Services Committee					
	County Board Staff Committee					
11	•					
12	Other Boards and Commissions:					
13	EMS Advisory Council					
14	Community Action Program					
15	City of Janesville TIF District 26					
16		14.				
17		the £				
18	citizens of Rock County and commends him for his contributions to the betterment of Rock County.	(1				
19		1				
	NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors duly assemb					
	this day of, 2014 does hereby recognize Ivan Collins for his service and extends by	est				
22	wishes in his future endeavors.					
	Respectfully submitted,					
	COUNTY BOARD STAFF COMMITTEE					
	J. Russell Podzilni, Chair Marilynn Jensen					
	Sandra Kraft, Vice Chair Mary Mawhinney					
	Eva Arnold Louis Peer					
	Henry Brill Kurtis Yankee					
	Betty Jo Bussie					
	Delty 10 Dussie					

RESOLUTION NO.	14-4A-583
RESULUTION NO.	14 411 505

AGENDA NO.	12.L.
------------	-------

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Nick Osborne, Assistant
To the County Administrator
DRAFTED BY

	SUBMITTED BY	M		March, 10, 2014 DATE DRAFTED		
	REC	COGNIZING S	STEVE H	OWLAND		
	WHEREAS, Steve Howland was in 2012; and,	s elected to the Roo	ck County F	Board of Supervisors, repre	esenting District 15,	
WHEREAS, Steve has devoted many hours to faithfully serve on the following:						
6	6 Standing Committees: 7 Health Services Committee					
9 10 11 12	Other Boards and Commissions: Local Emergency Planning Comm	mittee				
13 14	WHEREAS, the Rock County Board of Supervisors recognizes Steve Howland for his dedicated service to the citizens of Rock County and commends him for his contributions to the betterment of Rock County.					
NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors duly assemble this day of, 2014 does hereby recognize Steve Howland for his service and extermination best wishes in his future endeavors. Respectfully submitted,						
					Π α ω	
	COUNTY BOARD STAFF CO	MMITTEE				
	J. Russell Podzilni, Chair	_	Marilynn	Jensen		
	Sandra Kraft, Vice Chair	-	Mary Ma	whinney		
	Eva Arnold	-	Louis Pee	r		
	Henry Brill	-	Kurtis Ya	nkee		
	Betty Jo Bussie					

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Nick Osborne, Assistant to the County Administrator DRAFTED BY

March, 10, 2014 DATE DRAFTED

	RECO	OGNIZING MARILYNN JENSEN	
1 2 3	WHEREAS, Marilynn Jensen was 15, in 1986 and was elected to Distr	s elected to the Rock County Board of Supervisors, representing District rict 27 in 2002; and,	
	WHEREAS, Marilynn has devoted	many hours to faithfully serve on the following:	
	Standing Committees: Education and Training Committee Social Services Board	e, Vice Chair	
9	51.42 Board	Chair	
11 12 13	Developmental Disabilities Board, Health Services Committee, Vice of Planning and Development Comm County Board Staff Committee	Chair	
14 15	Other Boards and Commissions:		
17 18	Long Term Support Committee, V Local Emergency Planning Comm Rock County Tourism Council, Ch	ission	
20	EMS Advisory Council Rock Haven Health Care Center B Ad Hoc Reapportionment Commit	tee	+0
22 23 24	Ad Hoc Committee for Redistricting Outdoor Warning System Ad Hoc		
25 26 27		ard of Supervisors recognizes Marilynn Jensen for her dedicated service to mmends her for her contributions to the betterment of Rock County.	
		ESOLVED that the Rock County Board of Supervisors duly assembled 2014 does hereby recognize Marilynn Jensen for her service and extends .	
1	Respectfully submitted,		
	COUNTY BOARD STAFF COM	IMITTEE	
	J. Russell Podzilni, Chair	Marilynn Jensen	
	Sandra Kraft, Vice Chair	Mary Mawhinney	
	Eva Arnold	Louis Peer	
	Henry Brill	Kurtis Yankee	
	Betty Jo Bussie		

RESOLUTION NO. 14–4A–585	

AGENDA NO. 12.N.	AGENDA NO.	12.N.
------------------	------------	-------

County Board Staff Committee INITIATED BY



Nick Osborne, Assistant to the County Administrator

	County Board Staff Committee SUBMITTED BY		DRAFTED BY April 2, 2014 DATE DRAFTED	
	RECOG	NIZING PHILLIP	OWENS JR.	
2 3 4 5 6 7 8	WHEREAS, Phillip Owens Jr. was District 16, in 2006 and subsequently of WHEREAS, Phillip has devoted many Standing Committees: General Services Committee, Chair Human Services Board Planning and Development Committee	elected in 2008; and, y hours to faithfully ser	•	sors, representing
10 11 12	Education, Veterans, and Aging Servi Other Boards and Commissions: Hall of Honor Committee			
15 16 17 18	best wishes in his future endeavors.	nmends him for his con OLVED that the Rock	atributions to the betterment o	f Rock County. 4
ę.	Respectfully submitted, COUNTY BOARD STAFF COMM	ITTEE		
3.	J. Russell Podzilni, Chair	Marilyn	nn Jensen	
	Sandra Kraft, Vice Chair	Mary M	lawhinney	
	Eva Arnold	Louis P	eer	
	Henry Brill	Kurtis	Yankee	
	Betty Jo Bussie			

RESOLUTION NO.	14-4A-586
RESULUTION NO.	14-47-200

AGENDA NO.	12.0.
AUTENDA NU.	12.0.

County Board Staff Committee INITIATED BY

County Board Staff Committee SUBMITTED BY



Nick Osborne, Assistant to the County Administrator DRAFTED BY

April 2, 2014

		N. N.	DATE DRAFTED	
	RE	COGNIZING MIE	KE RUNDLE	
1 2	WHEREAS, Mike Rundle was ap 20, in 2012; and,	pointed to the Rock C	ounty Board of Supervisors, repre	esenting District
3 4	WHEREAS, Mike has devoted ma	ny hours to faithfully s	erve on the following:	
5 6 7 8	Standing Committees: Board of Health Developmental Disabilities Board			
9 10 11				14-4A-5
12 13 14 15	Other Boards and Commissions: Arrowhead Library System Board WHEREAS, the Rock County Boa citizens of Rock County and comm NOW, THEREFORE, BE IT RI this day of	rd of Supervisors recogends him for his contrib	mizes Mike Rundel for his dedicate outions to the betterment of Rock C	ed service to the county.
	NOW, THEREFORE, BE IT RI this day of, wishes in his future endeavors.	ESOLVED that the Ro 2014 does hereby recog	ock County Board of Supervisors gnize Mike Rundle for his service a	duly assembled and extends best
	Respectfully submitted,			
	COUNTY BOARD STAFF COM	MITTEE		
	J. Russell Podzilni, Chair	Mari	lynn Jensen	-
	Sandra Kraft, Vice Chair	Mary	/ Mawhinney	-
	Eva Arnold	Loui	s Peer	-
	Henry Brill	Kurt	is Yankee	-
	Betty Jo Bussie			

DECOLUTION NO	14-4A-587
RESOLUTION NO	14-4A-JO/

	GENDA	NO	13	2	_	Р
4	UFRINIDA	NO.		_	•	-

County Board Staff Committee



Nick Osborne, Assistant

	INITIATED BY County Board Staff Committee SUBMITTED BY	STATE OF THE STATE	to the County Administrator DRAFTED BY March, 10, 2014 DATE DRAFTED	
	RECOG	GNIZING MARV	WOPAT	
	WHEREAS, Marv Wopat was elected to 2008; and,	to the Rock County B	oard of Supervisors, represen	nting District 5, in
3 4 5	WHEREAS, Marv has devoted many ho	ours to faithfully serve	on the following:	
6	Standing Committees: Human Services Board Education, Veterans. And Aging Service	es Committee		
10	Other Boards and Commissions: Criminal Justice Coordinating Council			
13 14 15	WHEREAS, the Rock County Board of citizens of Rock County and commends			
17	NOW, THEREFORE, BE IT RESOI this day of, 2014 wishes in his future endeavors. Respectfully submitted,		County Board of Supervisor te Marv Wopat for his service	
	COUNTY BOARD STAFF COMMIT	TTEE		
	J. Russell Podzilni, Chair	Marilyn	n Jensen	_
	Sandra Kraft, Vice Chair	Mary M	awhinney	_
	Eva Arnold	Louis Pe	eer	_
	Henry Brill	Kurtis Y	ankee	_
	Betty Jo Bussie			
				· · · · · · · · · · · · · · · · · · ·

RESOLUTION NO.	14-4A-588
RESOLUTION NO.	14-4V 200

AGENDA NO.	12.Q.	
AGENDA NO.	12.4.	

County Board Staff Committee INITIATED BY



Nick Osborne, Assistant to the County Administrator

	County Board Staff Committee SUBMITTED BY		DRAFTED BY March, 10, 2014 DATE DRAFTED	
		RECOGNIZING FRED	O YOSS	
2 3 4	County Board of Supervisors, rep	presenting District 29, in 2010;	•	K.
7 8	Standing Committees: Human Services Board Education, Veterans. and Aging Land Conservation Committee	Services Committee		
11 12 13 14	Other Boards and Commissions: Rock County Tourism Council Community Action Program City of Janesville TIF District 8			14
15 16 17 18 19 20 21	citizens of Rock County and company NOW, THEREFORE, BE IT 1	mends him for his contribution RESOLVED that the Rock (zes Fred Yoss for his dedicated service to the ns to the betterment of Rock County. County Board of Supervisors duly assembled ze Fred Yoss for his service and extends bes	-588 1
	Respectfully submitted, COUNTY BOARD STAFF CO	OMMITTEE		. 1464
	J. Russell Podzilni, Chair	Marilynn	Jensen	
	Sandra Kraft, Vice Chair	Mary Ma	whinney	
3 4 1.5 3 4 4 4	Eva Arnold	Louis Pee	er	ď
31 21 41	Henry Brill	Kurtis Ya	ankee	: :
. 3	Betty Jo Bussie			* **

14-4A-589

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Charmian Klyve INITIATED BY

Human Service Board SUBMITTED BY



Carla Haigh DRAFTED BY

April 2, 2014 DATE DRAFTED

TO RECOGNIZE ECONOMIC SUPPORT STAFF

WHEREAS, Economic Support staff administer difficult, complex, and ever-changing public assistance programs to the citizens of Rock County; and,

WHEREAS, our system of delivery has changed to a consortium model as of January 1, 2012 and the staff have adapted to that ever-changing model; and,

WHEREAS, these staff successfully manage extremely high caseloads, determine eligibility and consistently deliver timely and accurate benefits and payments based on various entitlement and non-entitlement programs. Customer contacts are made in a courteous, professional manner and staff continue to maintain a high quality of customer service even during times of increasing caseloads. ES Staff took on the huge challenge of learning and implementing the changes to our medical programs as a result of the Affordable Care Act and continue to adjust as new initiatives are put in place. ES staff meet with individuals and families in crisis every day. In addition to providing services that this agency offers, staff work collaboratively with other community organizations to provide these individuals and families with resources they need to resolve emergency needs as well; and,

2 3 4

5

7

8

9 10

11

12 13

14 15

WHEREAS, these staff work with individuals and families to help provide essential human services, especially for those who are least able to help themselves. Through the conscientious efforts of these staff, more children and adults in our community have medical coverage and a healthier future; and,

21 22 23

24

20

WHEREAS, Economic Support staff play a major role in promoting self-sufficiency, and work toward relieving the effects of poverty and improving the quality of life for residents of Rock County; and,

WHEREAS, the Rock County Board of Supervisors, representing the citizens of Rock County, wishes to recognize Economic Support staff for their overall performance and dedicated service to the citizens of Rock County.

29 30

NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors, duly assembled this _____ day of ______ 2014, does hereby recognize the Economic Support staff for their dedication and excellence in the work they do; and,

34 35

BE IT FURTHER RESOLVED that the County Clerk be authorized and directed to furnish a copy of this resolution to all Economic Support staff.

Page 2	
Respectfully Submitted,	
HUMAN SERVICES BOARD	
Brian Knudson, Chair	Phillip Owens
Sally Jean Weaver-Landers, Vice Chair	Terry Thomas
Terry Fell	Shirley Williams
•	