

Board of Supervisors 51 S. Main Street Janesville, WI 53545 Phone: 608/757-5510 FAX: 608/757-5511

www.co.rock.wi.us

ROCK COUNTY BOARD OF SUPERVISORS' MEETING THURSDAY, APRIL 24, 2014 – 6:00 P. M.

COUNTY BOARD ROOM/COURTROOM H FOURTH FLOOR/COURTHOUSE EAST

Agenda

1	\bigcirc ATT	\mathbf{m}	ODDDD
1	1 · A I I	111	$I \cup I \cup I \cup I \cup I$
1 -			ORDER

- 2. INVOCATION & PLEDGE OF ALLEGIANCE
- 3. ROLL CALL
- 4. ADOPTION OF AGENDA
- 5. APPROVAL OF MINUTES April 10, 2014 and April 15, 2014
- 6. PUBLIC HEARING
- 7. CITIZEN PARTICIPATION, COMMUNICATIONS AND ANNOUNCEMENTS
- 8. NOMINATIONS, APPOINTMENTS AND CONFIRMATION
 - A. Confirmation of Chair's Appointments to Committees, Commissions and Boards

NOTE: Will be mailed no later than Tuesday, April 22, 2014

- 9. INTRODUCTION OF NEW RESOLUTIONS OR ORDINANCES BY SUPERVISORS FOR REFERRAL TO APPROPRIATE COMMITTEE
- 10. REPORTS
- 11. UNFINISHED BUSINESS
- 12. NEW BUSINESS
 - A. Supplementary Appropriations and Budget Changes Roll Call
 - 1. Accepting High Intensity Drug Trafficking Area (HIDTA) Grant and Amending the Sheriff's Budget
 - 2. Accepting Hazardous Materials Emergency Preparedness (HMEP) Sub-Grant and Amending the Sheriff's Budget
 - 3. 2013 Budget Amendment Winter Maintenance
 - 4. Amending the Council on Aging Budget for LightenUp! Project
 - 5. 2013 Supplemental Appropriations and Budgetary Transfers

ROCK COUNTY BOARD OF SUPERVISORS April 24, 2014 Page 2

12. NEW BUSINESS

- B. Bills Over \$10,000 No Roll Call
- C. Encumbrances Over \$10,000 Roll Call
- D. Contracts Roll Call
 - 1. Approval to Purchase Specialized Transit Vehicles
- E. Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (Chapter 4 Part 11) (Second Reading and Adoption)
- F. Amending Various Sections of the Rock County Storm Water Management Ordinance (Chapter 4 Part 8) (Second Reading and Adoption)
- G. Recognizing Wilson Meadows for Service to Rock County
- H. Recognizing Ross Jacobson for Service to Rock Haven

NOTE: Item 12. H. will be considered by the County Board Staff Committee on April 22, 2014

- I. Recognizing Stephanie Ann Nickols
- J. To Recognize Steve Polglaze

NOTE: Items 12.I. and 12.J. will be considered by the County Board Staff Committee on April 22, 2014 and Human Services Board on April 23, 2014

K. Recognizing HSD Administrative Professionals and Paraprofessionals

NOTE: Item 12.K. will be considered by the Human Services Board on April 23, 2014

13. ADJOURNMENT

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Sheriff Robert D. Spoden INITIATED BY

Public Safety and Justice Committee
SUBMITTED BY

1

2

4

5 6

7

8 9

15



Diane Michaelis DRAFTED BY

April 1, 2014 DATE DRAFTED

Accepting High Intensity Drug Trafficking Area (HIDTA) Grant and Amending the Sheriff's Budget

WHEREAS, the Sheriff's Office has been awarded a \$59,000 grant from the High Intensity Drug Trafficking Area (HIDTA) Program; and,

WHEREAS, the HIDTA Program is a program administered by the Office of National Drug Control Policy (ONDCP); and,

WHEREAS, the purpose of the Program is to reduce drug trafficking and drug production in the United States; and,

NOW, THEREFORE, BE IT RESOLVED by the Rock County Board of Supervisors duly assembled this _____ day of _____, 2014 to approve and authorize the acceptance of \$59,000 of HIDTA grant funds and to authorize the Sheriff to sign the award documents; and,

BE IT FURTHER RESOLVED, that the 2014 Sheriff's budget be amended as follows:

16 Account/ 17 Budget Increase Amended Description 04/01/14 18 (Decrease) **Budget** 19 Source of Funds 20 21-2140-2014-42100 21 \$0 \$59,000 \$59,000 22 Federal Aid 23 Use of Funds 24 21-2140-2014-61210 25 \$0 \$40,000 \$40,000 Overtime 26 27 21-2140-2014-63908 \$0 28 \$5.000 \$5,000 Investigative Expenses 29 30 21-2140-2014-64200 31 \$0 \$4,000 \$4,000 Training Expense 32 33 21-2140-2014-67160 \$0 34 \$10,000 \$10,000 35 Capital Assets \$500-\$4,999

Accepting High Intensity Drug Trafficking Area (HIDTA) Grant and Amending the Sheriff's Budget

Page 2

Respectfully submitted,

Public Safety and Justice Committee

Ivan Collins, Chair

Mary Beaver

Henry Brill

Brian Knudson

Larry Wiedenfeld

Finance Committee Endorsement

Reviewed and approved on a vote of

4.0

Mary Mawhinney. Chair

FISCAL NOTE:

This resolution authorizes the acceptance and expenditure of \$59,000 in Federal Aid for the HIDTA program. No County matching funds are required.

Sherry Oja
Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65.90(5)(a), Wis. Stats

Jeffrey S. Kuglitsch corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

Accepting High Intensity Drug Trafficking Area (HIDTA) Grant and Amending the Sheriff's Budget

Page 3

Executive Summary

The Sheriff's Office was awarded a \$59,000 grant from the High Intensity Drug Trafficking Area (HIDTA) Program. The HIDTA program is administered by the Office of National Drug Control Policy (ONDCP). The notification was received from Michael Gottlieb, the National HIDTA Director.

The purpose of the HIDTA Program is to reduce drug trafficking and drug production in the United States. The HIDTA Program provides funding resources to joint initiatives of federal, state, local, and tribal agencies in each area designated as a HIDTA to carry out activities that address the specific drug threats of those areas.

The grant funds will be used for overtime, investigative expenses, training, and equipment. The equipment purchased will be used for observation and undercover operations. Specific equipment to be purchased has not been determined at this time

Overtime	\$40,000
Investigative Expenses	\$5,000
Training	\$4,000
Equipment	<u>\$10,000</u>
Total	\$59,000

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Sheriff Robert D. Spoden INITIATED BY

Public Safety and Justice Committee SUBMITTED BY

16 17



Sergeant Shena Kohler DRAFTED BY

April 1, 2014 DATE DRAFTED

<u>Accepting Hazardous Materials Emergency Preparedness (HMEP) Sub-</u> <u>Grant and Amending the Sheriff's Budget</u>

WHEREAS, the Sheriff's Office – Emergency Management Bureau has been awarded a
 \$11,400 grant from Wisconsin Emergency Management; and,

WHEREAS, the HMEP sub-grant is a grant program administered by the State of Wisconsin Department of Military Affairs through funding provided by the United States Department of Transportation; and,

WHEREAS, the purpose of the program is to improve the development and implementation of the Community Right-to-Know Act (EPCRA) and enhance planning efforts for hazardous material responses; and,

NOW, THEREFORE, BE IT RESOLVED by the Rock County Board of Supervisors duly assembled this _____ day of _____, 2014 to approve and authorize the acceptance of \$11,400 of HMEP grant funds and to authorize the Sheriff to sign the award documents; and,

BE IT FURTHER RESOLVED, that the 2014 Sheriff's budget be amended as follows:

18 Account/ **Budget** Increase **Amended** 19 Description 04/01/14 (Decrease) Budget 20 21 Source of Funds 22 21-2534-2014-42200 \$0 \$11,400 \$11,400 23 State Aid 24 25 26 Use of Funds 21-2534-2014-64200 \$0 \$11.400 \$11,400 27 Training Expense 28

Accepting Hazardous Materials Emergency Preparedness (HMEP) Sub-Grant and Amending the Sheriff's Budget Page 2

Respectfully submitted,

Public Safety and Justice Committee

Ivan Collins, Chair

Mary Beaver

Henry Brill

Bran Khudsi

Brian Knudson

Larry Wiedenfeld

Finance Committee Endorsement

Reviewed and approved on a vote of

4-0

Mary Mawhinney, Chair

FISCAL NOTE:

This resolution authorizes the acceptance and expenditure of \$11,400 in State Aid for Hazardous Materials Emergency Preparedness training. No County funds are required.

Sherry Oja
Finance Director

LEGAL NOTE:

The County Board is authorized to accept grant funds pursuant to sec. 59.52(19), Wis. Stats. As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. $6\frac{\pi}{4}.90(5)$ (a), Wis. Stats.

Jeffrey S. Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended

Craig Knutson County Administrator Accepting Hazardous Materials Emergency Preparedness (HMEP) Sub-Grant and Amending the Sheriff's Budget

Executive Summary

The Sheriff's Office has been awarded an \$11,400 grant from the Hazardous Materials Emergency Preparedness (HMEP) Grant, a program administered by the Wisconsin Department of Military Affairs – Division of Emergency Management through funding provided by the United States Department of Transportation. The purpose of the Program is to improve the development and implementation of the Community Right-to-Know Act (EPCRA) and enhance planning efforts for hazardous material responses.

The HMEP Program provides funding resources to local Emergency Management agencies to provide hazmat training and planning support that will improve hazardous material awareness and response.

The grant funds will be used to purchase two Hazmat IQ training programs, contracted and instructed by Federal Resources, of Stevensville Maryland. The contracted instructors will provide a full day of instruction for the Rock County Hazmat Team and two 4-hour sessions for first responders. These sessions are being offered at no cost to agencies or first responders, and Blackhawk Technical College will be hosting the sessions at their Central Campus in Janesville, Wisconsin.

The training programs include:

Total	\$11.400.00
Hazmat IQ – First Responder Offensive (4-hour course – 2 sessions)	\$5,450.00
Hazmat IQ – Above the Line/Below the Line (1 day session)	\$5,950.00

RESOLUTION

ROCK COUNTY BOARD OF SUPERVISORS

Public Works Committee
INITIATED BY
Public Works Committee
SUBMITTED BY

Eva M. Arnold



Ben Coopman, Director of Public Works
DRAFTED BY

March 11, 2014 DATE DRAFTED

WHEREAS, the winter weat of weather events; and,	ther of 2013 has been	i above average in t	terms of severity and r
WHEREAS, said winter wea	ather has necessitated	d the expenditure of	f funds by the Departn
Public Works for labor, mac	hinery and materials	for winter mainte	nance in excess of bu
amounts.			
NOW, THEREFORE, BE	IT RESOLVED, b	y the Rock County	y Board of Supervisor
assembled this day or	f, 2014	, that the 2013 De	epartment of Public V
budget is hereby amended t	to increase Departm	ent funding for w	inter maintenance as
below.			
Account No.	Budget at	Increase	Amended
Description	12/31/13	(Decrease)	Budget
Source of Funds:	***	*	
19-1921-0000-47010	\$35,450	\$448,000	\$483,450
Supplemental Appropriation f	rom General Fund		
Use of Funds:			
11-4300-4322-61171	612,000	100,000	712,000
Field Wages		•	,
41-4300-4322-63702	148,000	40,000	188,000
Sand			
41-4300-4322-63703	395,000	108,000	503,000
Sodium Chloride			
41-4300-4322-65341	691,000	200.000	901 000
Machinery Lease	091,000	200,000	891,000
viacinnery Lease			
Respectfully submitted,			
PUBLIC WORKS COMMIT	TEE		
		Λ ι	
- i) ' ./		/ 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	,
Kurtis, Yankoe, Chair		HOSENT	

14-4C-00

Page 2

Finance Committee Endorsement:

Reviewed and approved on a vote of ______

Mary Mawhinney, Chair

FISCAL NOTE:

This resolution authorizes a \$448,000 transfer from the General Fund to DPW for winter maintenance. The estimated unassigned General Fund balance at 12/31/13 is \$25,000,000.

Sherry Oja Finance Director

LEGAL NOTE:

As an amendment to the adopted 2013 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65.90(5)(a),

Jeffrey Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson

County Administrator

- Executive Summary -

The winter weather in 2013 has been more severe than anticipated. There were several freezing rain events that are very labor intensive and require the use of larger amounts of sand or salt than normal snowfalls. Many events also happened on weekends when labor costs are higher due to overtime pay rates. The 2013 Public Works Department budget request was based on an "average" winter, plus a small inflationary adjustment.

Costs for winter maintenance for 2013 through December 31, 2013 show the Winter Maintenance budget deficit is approximately \$635,000. There were offsetting gains in the Machinery Cost Pool revenue that generated an estimated favorable variance from budget of \$87,000 and an estimated favorable variance from budget for routine maintenance of approximately \$100,000. This budget amendment requests a supplemental appropriation to the Public Works Department Winter Maintenance Budget for the net amount of these budget variances, \$448,000.

The source of funds requested is the County's General Fund. These funds will be allocated proportionally among labor, machinery and material line expense items.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Education, Veterans & Aging Services Committee INITIATED BY



Joyce Lubben DRAFTED BY

April 9, 2014 DATE DRAFTED

Education, Veterans & Aging Services Committee SUBMITTED BY

	AMENDING THE COUN	NCIL ON AGING E	BUDGET FOR LIGHT	ΓENUP! PROJECT	
1	WHEREAS, the Aging and Disab	oility Resource Cente	er of Kenosha County ha	as received grants to	
2	continue a research project titled L	ightenUp!; and,	•	C	
3					
4	WHEREAS, Kenosha County has		lock County Council or	Aging partner with them	
5	on the second phase of this research	ch project; and,			
6					
7	WHEREAS, the purpose of this p				
8	adults and adults with disabilities l	by promoting mental	health and preventing	exacerbation of chronic	
9	conditions; and,				
0					
1	WHEREAS, the Rock County Co				a
2	class facilitators, scheduling classe		ment, screening and em	collment of local	
3	participants, and maintaining class	data.			
4					
5	NOW, THEREFORE, BE IT RI	ESOLVED that the l	Rock County Board of S	Supervisors duly assemble	Ć
6	this day of	, 2014 does ame	end the Council on Agi	ng budget as follows.	
7					
8					
9	Account/Description	Budget at	<u>Increase</u>	Amended	
0		<u>1/1/2014</u>	(Decrease)	Budget	
1.	LightenUp! Grant				
2	Source of Funds			•	
3	30-3932-0000-46002	0	20,000	20,000	
4	Other Grants and Contracts				

19	Account/Description	Budget at	<u>Increase</u>	Amended
20		<u>1/1/2014</u>	(Decrease)	Budget
21	LightenUp! Grant			
22	Source of Funds			
23	30-3932-0000-46002	0	20,000	20,000
24	Other Grants and Contracts			
25	Use of Funds			
26	30-3932-0000-62119	0	20,000	20,000
27	Other Contracted Services			

Respectfully submitted,

Education, Veterans & Aging Services Committee	Finance Committee Endorsement
Terry Thomas	Reviewed and approved on a vote of
Terry Thomas, Chair	40

Mary Mawhinney, Chair

Rick Richard

${\bf Amending\ the\ Council\ on\ Aging\ Budget\ for\ Lighten Up!\ Project.}$

Page 2

FISCAL NOTE:

This resolution authorizes the expenditure of \$20,000 in grant funds passed through Kenosha County for the LightenUp! program. No County matching funds are required.

Sherry Oja Finance Director

LEGAL NOTE:

As an amendment to the adopted 2014 County Budget, this Resolution requires a 2/3 vote of the entire membership of the County Board pursuant to sec. 65/90(5)(a), Wis. Stats.

Jeffre 8. Kuglitsch Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

Executive Summary

The Rock County Council on Aging has an opportunity to partner with the Aging and Disability Resource Center of Kenosha County on the second phase of a research project called LightenUp!. Kenosha County has received two-year grants from the Wisconsin Department of Health Services and the Wisconsin Partnership Project to continue this research. The purpose of the project is to reduce depression and improve well-being and sleep among older adults. Many older persons are isolated by geography, disability, and low income, placing them at greater risk for depression and low well-being. Psychological distress can reduce quality of life and add to the difficulty of living independently, managing chronic disease and participating in programs that promote healthy aging. Preliminary results from the first year of the project show a significant decline in depressive symptoms and improved well-being among the older adults and adults with disabilities who participated in the initial phase of the project.

Participants will participate in eight 90-minute sessions of 12-15 people each. In-person sessions will be held in comfortable, accessible community settings, each facilitated by a trained leader. Class content involves theories of well-being, cognitive behavioral therapeutic perspectives on emotion, group discussion and brainstorming. Daily homework is the maintenance of a well-being diary.

Research will be done on what marketing strategies encourage older adults and adults with disabilities to participate in health promotion workshops. The information gained will be valuable for marketing all of the Council on Aging's health promotion activities.

No county tax levy is required for this project.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Finance Committee	
INITIATED BY	

Finance Committee
SUBMITTED BY

44

Housing Grant Cost Allocations



Sherry Oja, Finance Director DRAFTED BY

April 15, 2014 DATE DRAFTED

2013 SUPPLEMENTAL APPROPRIATIONS AND BUDGETARY TRANSFERS

1 2	WHEREAS, adjustments must be	made to close the 20	013 General Ledger; ar	ıd,	
3	WHEREAS, the Finance Committ	ee has reviewed and	approved the suppler	nental appropriations and	
4	transfers.	co mas roviowed and	a approved the suppren	nontar appropriations and	
5					
6	NOW, THEREFORE, BE IT F				
7	assembled this day of	f,	2014 does hereby an	nend the 2013 Budget as	
8	follows:				
9		CUDDENT		A NATION DISCUSS	
10	A/C DESCRIPTION	CURRENT	CHANCE	AMENDED	
11 12	Source of Funds:	BUDGET	CHANGE	BUDGET	
13	00-0000-0001-46900				
14	Refund of Prior Year Expense	0	35,478	35,478	
15	19-1921-0000-47010	O	33,476	33,470	
16	General Fund Application	35,450	730,700	766,150	
17	21-2200-0000-61210	33,130	730,700	700,130	_
1,8	Corrections – Wages	5,583,092	(258,658)	5,324,434	4
19	21-2200-0000-61610	, ,	(====,===)	-,,	4C-
20	Corrections-Health Insurance	2,308,937	(187,432)	2,121,505	14-40-005
21	33-3310-0000-42210		, , ,	, ,	
22	DD Board-Revenue from State	1,798,123	238,782	2,036,905	
23	36-3668-0000-47020				
24	LTS-COP Risk Reserve	0	118,191	118,191	
25					
26	Use of Funds:				
27	19-1990-0000-64904				
28	Refund of Prior Years Rev	0	62,449	62,449	
29	19-1991-0000-64904	0	11 200	44.000	
30	Additional Expenses from Prior Yrs 21-2100-0000-61210	s. 0	11,209	11,209	
31 32	Sheriff-Overtime Wages	256 250	507.000	054040	
33	33-3310-0000-0000-62604	256,250	597,992	854,242	
34	DD Board–Nursing Home Relocation	nn22 701 150	238,782	22,939,932	
35	36-3603-0000-67200	31122,701,130	230,702	22,939,932	
36	HSD Capital Account	245,350	24,269	269,619	
37	36-3668-0000-64604	2.0,000	21,209	200,010	
38	LTS-COP Program Expense	994,472	118,191	1,112,663	
39	36-3697-0000-68380	,		-,,	
40	HSD_CLTS Allocation	(206,941)	95,117	(111,824)	
41	36-3706-0000-64604		•	` ' '	
42	Community Support Program	300,000	353,132	653,132	
43	64-6460-0000-68000				

(111,109)

68,100

(43,009)

2012 SUPPLEMENTAL APPROPRIATIONS AND BUDGETARY TRANSFERS Page 2

Respectfully submitted,

FINANCE COMMITTEE

Mary Mawhinney, Chair

Sandra Kraft Vias Chair

MarBearer

Ahan-

Brent Fox

J. Russell Podzilni

LEGAL NOTE:

As an amendment to the 2013 County Budget, this resolution requires a 2/3 vote of the entire membership of the County Board, pursuant to Sec. 65.90(5)(a), Wis. Stats.

Eugene R. Dumas

Deputy Opporation Counsel

FISCAL NOTE:

This resolution amends the 2013 Budget for those programs where expenses exceeded budget appropriations. To limit data entry and legal notice publication costs, only selected line items within programs were adjusted. The line items shown contain the net budget adjustment for the program and do not necessarily reflect the overage of that particular line item.

Sherry Oja

Finance Director

ADMINISTRATIVE NOTE:

Recommended

Craig Knutson
County Administrator

Executive Summary

Every April, as we finalize the closing of the books for the previous year, we identify programs where total expenses for the program exceeded total budget appropriations. This resolution adjusts the budgets for those programs. To limit data entry and legal notice publication costs, only one line item for each program is adjusted. This adjustment is a net adjustment and does not necessarily reflect the overage of that particular line item.

The source of funds for these adjustments can come from recognizing the receipt of higher than expected revenues, transfers from other programs or transfers from the General Fund.

This resolution shows a transfer of \$730,700 from the General Fund. This resolution is just a small snapshot of the 2013 books. It does not show all the programs that were under budget for the year. Even with the \$730,700 transfer from the General Fund, we estimate an approximate increase of \$2.5 million dollars to the General Fund as we finalize 2013.

ROCK COUNTY, WISCONSIN

RESOLUTION NO. 14-4C-006

AGENDA NO. 12.B.(1)

INITIATED: FINANCE DIRECTOR

SUBMITTED BY: FINANCE COMMITTEE

DATE: APR 1 7 2014

WHEREAS, THE FINANCE COMMITTEE HAS EXAMINED THE FOLLOWING BILLS OVER \$10,000 AS REQUIRED BY COUNTY BD. RULE H.(3), AND FOUND THEM TO BE PROPER AND WITHIN BUDGET.

NOW THEREFORE REIT RESOLVED. THE ROCK COUNTY BOARD OF SUPERVISORS AT ITS REGULAR MEETING ON APR 2 4 2014 . APPROVES PAYMENT AND AUTHORIZES AND DIRECTS THE COUNTY CLERK AND COUNTY TREASURER TO PAY THE SAME.

Vendor Name	Fund Name	Department Na	me Program Na	me	Amount	Claim Amount
BANDT COMMUNICATIONS INC	CPF-SHER. VEH	SHERIFF	SHERIFF'S VEH	140307204	11,650.00	
						11,650.00
ILLINGWORTH KILGUST MECHANICAL I	CPF-GS	GENERAL SERVI	JAIL.CAP.IMPR	6621	45,278.00	
						45,278.00
ILLINOIS OFFICE SUPPLY	GENERAL FUND	COUNTY CLERK	ELECTIONS	48784	11,932.01	
						11,932.01
WISCONSIN RIVER RAIL TRANSIT COM	SPF-ALL OTHER	PLANNING	RAIL TRANSIT	314	28,000.00	28,000.00

Rock County - Production

04/16/14

APPROVAL OF BILLS OVER \$10,000.00

ROCK COUNTY, WISCONSIN

Page 2

CLAIMS IN THE AMOUNT OF

96,860.01

HAVE BEEN APPROVED AND CHECKED BY THE GOVERNING COMMITTEES.

RESPECTFULLY SUBMITTED,

FINANCE COMMITTEE

5. Braft

LEGAL NOTE:

THE COUNTY BOARD RULE CITED REQUIRES THE COUNTY BOARD

TO EXAMINE AND SETTLE ALL CLAIMS OVER \$10,000.00

JEFFREY B. KUGLITSCH CORPORATION COUNSEL

FISCAL NOTE

ABOVE LISTED CLAIMS ARE FULLY FUNDED.

SHERRY OJA FINANCE DIRECTOR ADMINISTRATIVE NOTE

RECOMMENDED

COUNTY ADMINISTRATOR

APPROVAL OF ENCUMBRANCES OVER \$10,000.00

RESOLUTION NO.	14-4C-007	AGENDA NO.	12.C.	

INITIATED: FINANCE DIRECTOR

SUBMITTED BY: FINANCE COMMITTEE

DATE: APR 1 7 2014

WHEREAS. THE FINANCE COMMITTEE HAS EXAMINED THE FOLLOWING ENCUMBRANCES OVER \$10,000 AS REQUIRED BY COUNTY BD. RULE H.(3), AND FOUND THEM TO BE PROPER AND WITHIN BUDGET.

NOW THEREFORE BE IT RESOLVED, THE ROCK COUNTY BOARD OF SUPERVISORS AT ITS REGULAR MEETING ON APR 2 4 2014 , APPROVES PAYMENT AND AUTHORIZES AND DIRECTS THE COUNTY CLERK AND COUNTY TREASURER TO PAY THE SAME, UPON ACCEPTANCE BY THE DEPARTMENT HEAD.

Vendor Name

Fund Name

Department Name Program Name

PR Number

Claim Amount

STAPLES ADVANTAGE

GENERAL FUND

NOT APPLICABLE BAL.SHEET A/C

R1401939

150.000.00

CLAIMS IN THE AMOUNT OF

150.000.00

HAVE BEEN APPROVED AND CHECKED BY THE GOVERNING COMMITTEES.

FINANCE COMMITTEE

LEGAL NOTE:

THE COUNTY BOARD RULE CITED REQUIRES THE COUNTY BOARD TO EXAMINE, AND SETTLE ALL CLAIMS OVER \$10,000.00

CORPORATION COUNSEL

FISCAL NOTE

COUNTY ADMINISTRATOR

ADMINISTRATIVE NOTE

RECOMMENDED

ABOVE LISTED CLAIMS ARE FULLY FUNDED.

SHERRY OJA FINANCE DIRECTOR

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Education, Veterans & Aging Services Committee INITIATED BY

Education, Veterans & Aging Services Committee SUBMITTED BY

Jeffrey S. Kuglitsch Corporation Counsel



Joyce Lubben DRAFTED BY

April 8, 2014 DATE DRAFTED

APPROVAL TO PURCHASE SPECIALIZED TRANSIT VEHICLES

 WHEREAS, the Council on Aging received a s Wisconsin Department of Transportation to put fleet; and, 	
5 WHEREAS , the vehicles were purchased thro 6 contract # 271989 which was awarded to Atlan 7	ough the Wisconsin Department of Transportation s Bus Sales; and,
8 WHEREAS, federal funds pay for 80% of the	vehicles with a 20% local match, and;
WHEREAS, additional costs are required for v	vehicle titles and conversion costs.
NOW, THEREFORE, BE IT RESOLVED that assembled this day of ssued to the State of Wisconsin in the amoun Bus Sales in the amount of \$12,434.00 for vel specialized transit vehicles. BE IT FURTHER RESOLVED that payment be acceptance by the Rock County Council on Ag	, 2014 does approve that Purchase Orders be 6 t of \$17,682.40 for the local match and to Atlas nicle titles and conversion costs for two e made to the vendor upon receipt and
Respectfully submitted,	
Education, Veterans & Aging Services	FISCAL NOTE:
Terry Thomas, Chair Wayne Gustina Steve Howland	This resolution authorizes the purchase of two specialized transit vehicles using federal grant funds. The 20% required local match and conversion costs will be funded by a transfer in from the E&H Trust fund, which has a current balance of \$87,452.
Steve Howland	My -
Edwin Nash Rick Richard	Sherry Oja Finance Director
LEGAL NOTE:	ADMINISTRATIVE NOTE:
The County Board is authorized to take	Recommended.

Craig Knutson County Administrator

EXECUTIVE SUMMARY

The Rock County Council on Aging was awarded a federal 5310 grant to purchase two new Specialized Transit buses through a bidding process conducted by the Wisconsin Department of Transportation (contract # 271989). This grant provides 80% of the funding for the purchase of each vehicle, with the 20% local match and conversion costs coming from the Elderly & Handicapped Vehicle Replacement Trust Fund.

Conversion costs include: one additional wheelchair position with wheelchair securements for one vehicle and two additional wheelchair positions for the second vehicle, a more durable driver's seat, a Ricon wheelchair lift, foldaway seats to make room for the additional wheelchair position, signage, an upgraded suspension system and a seat belt extension.

Cost breakdown for the vehicles:

\$ 70,729.60 (\$35,364.80 each) – Federal 5310 funding 17,682.40 (\$8,841.20 each) – 20% local match from the E&H Trust Fund 12,434.00 (\$6,137.50 each) – vehicle title and conversion costs from the E&H Trust Fund \$100,846.00 (\$50,423.00 each)

These new vehicles will be replacing two 2008 Ford mini-buses that will be sold at auction.

ORDINANCE ROCK COUNTY BOARD OF SUPERVISORS

LAND CONSERVATION
COMMITTEE
INITIATED BY



ANDREW BAKER DRAFTED BY

MARCH 26, 2014 DATE DRAFTED

LAND CONSERVATION COMMITTEE SUBMITTED BY

1

2 3

4 5

> 6 7

8

9

10

11

12

13

14 15

16

17

18

19

20 21

22 23

24

25

26 27

> 28 29

> 30

31

32

33

34 35

36 37

38 39 40

> 41 42

AMENDING VARIOUS SECTIONS OF THE ROCK COUNTY CONSTRUCTION SITE EROSION CONTROL ORDINANCE (CHAPTER 4 PART 11)

The County Board of Supervisors of the County of Rock does ordain as follows:

I. Chapter 4, Part 11, of the Rock County Ordinances shall be amended to read as follows (new language underscored, deleted language crossed out):


4.1105 Jurisdiction, Applicability and Waivers

- Applicability (2)
 - This ordinance applies to the following land disturbing activities:
 - 9. Land disturbing activities, on a site of any size, that have been observed to cause, or have been determined likely to result in, undue channel erosion, increased water pollution by scouring or the transportation of particulate matter, or endangerment of property or public safety. The <u>LCC LCD</u> shall make this determination after review and recommendation by the Technical Review Committee LCD.
- Waivers (3)
 - The $\overline{\text{Technical Review Committee}}$ LCD shall be responsible for making (B) recommendations to the LCC concerning all waiver applications.

4.1107 Performance Standards

- Erosion and Other Pollutant Control Requirements (1)
 - (B) BMPs shall, by design, reduce pollutants from the construction site to the maximum extent practicable by use of methods including, but not limited to, the following:
 - Prevent gully and bank erosion.
 - Achieve a reduction of 80% of the sediment load carried in runoff, on an average annual basis, as compared with no sediment or erosion controls until the construction site has undergone final stabilization. The LCD may, upon written approval by the DNR, use a standard that is equivalent to an 80% reduction in sediment load. Discharge no more than 5 tons per acre per year, or to the maximum extent practicable, of the sediment load carried in runoff from initial grading to final stabilization. If BMPs cannot be designed to meet the standard in this paragraph, (B)2., the plan shall include a written and site-specific explanation as to why the standard is not attainable and a statement that the sediment load shall be reduced to the maximum extent practicable.
 - (E) Sediment controls shall be implemented to do all of the following:

	4. Prevent the discharge of sediment from soil stockpiles existing for more than 7
	days.
	5. Prevent the transport by runoff into waters of the state of untreated wash water
	from vehicle and wheel washing.
	6. Prevent the transport by runoff into waters of the state of chemicals, cement, and
	other building compounds and materials on the construction site during the
	construction period.
2) Ir	nplementation. The BMPs used to comply with the performance standards must be implemented
	as follows:
	(A) Erosion and sediment control practices shall be constructed or installed before land
	disturbing construction activities begin in accordance with the approved plan
	(B) Final stabilization activity shall commence when land disturbing activities cease and
	final grade has been reached on any portion of the site.
	(C) Temporary stabilization activity shall commence when land disturbing construction
	activities have temporarily ceased and will not resume for a period exceeding 14
	<u>calendar days.</u>
	(D) BMPs that are no longer necessary for erosion and sediment control shall be removed
	by the responsible party.
	
	Maintenance. The permit holder shall maintain all BMPs once a week and within 24 hours of
	each rain of 0.5 inches or more to meet the requirements of this ordinance until the site has
	achieved final site stabilization and a written BMP removal authorization has been received from
	the LCD.
54)	Alternate Requirements.
	(A) The LCD may establish erosion and sediment control requirements more stringent than those
	set forth in this section if the LCD determines that an added level of protection is needed to
	protect sensitive resources.
	protect sensitive resources.
	(B) The <u>LCD</u> Technical Review Committee shall make recommendations to the LCC concerning
	COLUMN TOWARD A TATE OF THE COLUMN TO A STATE OF THE COLUMN TO THE COLUM
	any erosion and sediment control requirements more stringent than those set forth in this
	any erosion and sediment control requirements more stringent than those set forth in this
	any erosion and sediment control requirements more stringent than those set forth in this section.
	any erosion and sediment control requirements more stringent than those set forth in this
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
l . 110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities. 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities. 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements:
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements: a. Preservation of existing vegetation where possible, minimize soil
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements:
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities. 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements: a. Preservation of existing vegetation where possible, minimize soil compaction and preservation of topsoil;
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers
.110	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements: a. Preservation of existing vegetation where possible, minimize soil compaction and preservation of topsoil;
	any erosion and sediment control requirements more stringent than those set forth in this section. 8 Permits and Waivers (4) Erosion and Sediment Control Plans (A) Plan Requirements for Class One Land Disturbing Activities 3. Each plan shall include a description of interim and permanent BMPs that will be implemented at the site to prevent pollutants from reaching waters of the state or adjacent property. The plan shall clearly describe the appropriate control measure(s) for each major activity and the timing during the land disturbing activity. The BMPs shall meet, when appropriate, the following minimum requirements: a. Preservation of existing vegetation where possible, minimize soil compaction and preservation of topsoil;



II. This ordinance shall be effective upon publication.

161

162 163

Respectfully submitted:

LAND CONSERVATION COMMITTEE

Jarry Wiedenfeld, Vice-Chair

Eva Arnold

Norvain Pleasant Jr.

David Rebout, USDA-FSA Representative

Alan Sweeney

FISCAL NOTE:

No fiscal impact.

Sherry Oja

Finance Director

LEGAL NOTE:

The County Board is authorized to take this action by Wisconsin Statutes sections 59.02, 59.692 and 59.693.

Eugene R. Dumas

Deputy Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson

County Administrator

Amending Section 4.11 032614.res

Executive Summary

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8)

and

Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Please note that complete annotated and non-annotated versions of each ordinance, which incorporate each of the proposed amendments, are available at the County Clerk's office.

The County of Rock was authorized by the DNR on November 13, 2006 to discharge stormwater from the County owned Municipal Separate Storm Sewer Systems (MS4) in the Urbanized Area under a general Wisconsin Pollutant Discharge Elimination System (WPDES) MS4 permit. The Urbanized Area is determined by population density based on the most recent census. Under the permit language, MS4 means a conveyance or system of conveyances including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, constructed channels or storm drains, which meets all of the following criteria: Owned or operated by a municipality, designed or used for collecting or conveying storm water, and which is not a combined sewer conveying both sanitary and storm water.

The County's WPDES MS4 General Permit outlines certain minimum programs and documentation that must be developed and submitted by dates certain. Among the requirements is to adopt and enforce construction site erosion control and post-construction storm water management regulations, which the County has had in place since March 2004. These ordinances have been approved by the DNR in the past, but changes to State Administrative Code NR 151 in January of 2011 are required to be incorporated into local ordinances. The recommended action for each ordinance approves those required changes (including various definitions) along with less substantive changes which are recommended by the LCD based on administrative experiences.

The substantive changes are summarized below with reference to the ordinance section(s):

Removal of Technical Review Committee (recommended by the LCD for both ordinances): All references to the Technical Review Committee have been deleted from each Ordinance and changed, where necessary, to LCD and/or LCC. Staff has determined that this additional level of review, requiring input from other departments or local unit of government, is a step in the review process that is not necessary to effectively administer the ordinances. Appeals and/or alternative requirements formerly requiring input from the Technical Review Committee will be processed with a LCD recommendation and LCC decision. The LCD recommendation will still be based on consultation with other entities with jurisdiction over the project.

Post-Construction Storm Water Management (4.8)

Changes to required standards for redevelopment projects:

1. **(4.805(2)(B)1.e.)** Redevelopment projects are no longer entirely exempt from storm water ordinance requirements under NR 151. Redevelopment projects must meet total suspended solid (TSS) reduction standards (40% reduction, compared to 80%

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8) and Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Page 1 of 2

- reduction for new development), however exemptions remain for infiltration and peak discharge standards.
- 2. **(4.807(1)(B))** Maintenance of effort. This section is added, based on NR 151, to address redevelopment sites that were previously approved under the storm water ordinance requirements for new development. This section prevents a redevelopment project from being required to meet lesser standards than what were required when originally permitted.

Changes to the peak discharge rate and volume standards:

- 1. (4.807(2)). The one year, twenty-four hour storm event was added to the design requirements in NR 151.
- 2. (4.807(2)(B)4). The maximum pre-development runoff curve numbers were revised.

Changes to the storm water runoff discharge quality standards (total suspended solids):

1. (4.807(3)). Infill development is no longer exempt from TSS reduction standards under NR 151.

Changes to infiltration standards (4.807(4)):

This section was entirely reorganized based on the changes to NR 151. The level of infiltration that is required is now based on the level of planned impervious surface, rather than land use type. Also, sections formerly titled "Exclusions" and "Exemptions" have been reorganized to clarify the intent of the standards. Generally, the ordinance now includes criteria for Source Area Restrictions (i.e. the area that drains to an infiltration practice(s)) and the Location of Practices.

Changes to certain definitions (4.813): For the most part, the changes to the definitions are directly from NR 151 and are primarily for clarification purposes.

Construction Site Erosion Control (4.11)

Changes to performance standards under NR 151:

- 1. (4.1107(1)(B)2.): The method used to estimate the sediment discharged from a project and, subsequently, design a plan to reduce it has been revised. The 80% reduction standard was changed to a standard which allows a maximum of 5 tons per acre per year from a construction site. This level of allowed discharge is consistent with agricultural standards for most of the soils in Rock County. In terms of actual tolerable soil loss, 80% reduction and 5 tons per acre per year are very similar thresholds. However, the acceptable software tools to estimate soil loss and plan the practices to reduce erosion and sedimentation are simpler to use and not cost prohibitive.
- 2. (4.1107(1)(E)): The addition of other sources of pollutants that must be consideration considered when developing a plan.
- 3. (4.1107(2)): Implementation techniques are specified to avoid any question of what is required. These points were typically included in the permit conditions of approval, but now are added directly to the performance standards section to be consistent with NR 151.

ORDINANCE ROCK COUNTY BOARD OF SUPERVISORS

-	ROCK COUNTY BOARD OF 5	OI ER VISORS
LAND CONSERVATION	STATE	
COMMITTEE		ANDREW BAKER
INITIATED BY		DRAFTED BY
I AND CONCERNATION	ST S	1 0 0014
LAND CONSERVATION		March 26, 2014 DATE DRAFTED
COMMITTEE SUBMITTED BY		DATE DRAFTED
AMENDING VARIOUS S	ECTIONS OF THE ROCK COUN ORDINANCE (CHAPTER 4	TTY STORM WATER MANAGEMENT PART 8)
The County Board of	f Supervisors of the County of Rock	k does ordain as follows:
I. Chapter 4, Part 8, language underscored, delete		all be amended to read as follows (new
4.805 Jurisdiction, Applica	ability and Waivers	
(2) Applicability		
	inance applies to the following lan	d disturbing activities:
		y size, that have been observed to cause,
		moff in excess of the safe capacity of the
		of water, undue channel erosion, increased ion of particulate matter, or endangerment
		hall make this determination after review
	chnical Review Committee LCD.	
(B) Exemption		C-11
	is ordinance does not apply to the	following:
•••••		tion sites with no increase in exposed
	parking lots or roads	
	6 7	1 1 10
	<u>fe.</u> Post-construction sites with	less than 10 percent connected ete development of the post-construction
	site, provided the cumulative are	
	impervious surfaces is less than	
-		
		tion such as water. sewer, and fiber optic
	ground structures associated with	apply to the construction of any above
	ground structures associated with	i unity construction,
(3) Waivers		
	Technical Review Committee LCD	
recon	nmendations to the LCC concerning	g all waiver applications.
4.807 Performance Stand	ards	
(1) General Consid	lerations	

(B) Maintenance of Effort. For redevelopment sites where the redevelopment will be replacing older development that was subject to post-construction performance standards of

this ordinance in effect on or after March 2004, the storm water management plan must

meet the TSS reduction, peak flow control, infiltration, and protective area standards

applicable to the older development or meet the redevelopment standards of the revised ordinance, whichever is more stringent.

- (C) Off-Site Drainage. When designing BMPs, runoff draining to the BMP from off-site shall be taken into account in determining the treatment efficiency of the practice. Any impact on the efficiency shall be compensated for by increasing the size of the BMP accordingly.
- (2) Storm Water Runoff Peak Discharge Rate and Volume. Unless otherwise provided for in this ordinance, all land development activities subject to this ordinance shall establish onsite management practices to control the peak flow rates of storm water discharged from the site as described in this ordinance. Infiltration of storm water runoff from driveways, rooftops, parking lots, and landscaped areas shall be incorporated to the maximum extent practical to provide volume control in addition to control of peak flows
 - (A) The proposed land development shall, by design, not increase peak flow rates of storm water runoff from that which would have resulted from the same storm occurring over the site with the land in its pre-developed conditions for the one (1), two (2), ten (10), and one-hundred (100) year, twenty-four (24) hour storms.
 - (B) All runoff and flow calculations required for peak flow design shall use a hydrograph-producing method such as described in the most recent version of TR-55. The LCD retains approval of the methods used to determine runoff volume. Calculations for determining peak runoffs and volumes must incorporate the following assumptions.
 - 1. The design rainfall storm accumulation for different storm intensities in Rock County shall be based on the following data.
 - a. Rainfall Accumulation for 24 hour Rainfall:

i)	1-Year Storm	2.25 Inches
<u>i ii</u>)	2-Year Storm	2.9 Inches
ii <u>iii</u>)10-Year Storm	4.1 Inches
iii <u>iv</u>)100-Year Storm	6.0 Inches

4. Runoff Curve Numbers for on-site areas shall be based on pre-developed and proposed developed land use conditions. The maximum pre-development runoff curve numbers are shown in Table 1. Runoff Curve Number for off-site areas shall be based on the pre-developed or proposed land use, which ever results in the highest peak flows. Runoff Curve numbers are described in TR-55.

(NEW TABLE)

	Maximum Pr	e-development l	Runoff Curve Num	bers
Land	Hydrologic Soil Group			
Cover				
	A	В	C	D
Woodland	30	55	70	77
Grassland	39	61	71	78
Cropland	55	69	78	83

Table 1

155	
156	
157 158	
158	
159	
160	
161	
162 163	
164	
165	
166	
167	
168	
169	
170	
171	
172	
173 174 175	
175	
176	
177	
178	
179	
180	
181	
182 183	
184	
185	
185 186	
187	
189	
190	
190 191 192 193 194	
192	
194	
195	
196	
197	
198	
199	
200	
201 202	
202 203	
204	
205	
206	
207	
208	
209	
210 211	
212	
213	

- (4) Infiltration. BMPs shall be designed, installed, and maintained to infiltrate runoff to the maximum extent practicable in accordance with the following, except as provided in paragraphs (FE) through (IH).
 - (A) For residential developments one of the following shall be met:
 - 1. Infiltrate sufficient runoff volume so that the post-development infiltration volume shall be at least 90% of the pre-development infiltration volume, based on an average annual rainfall. However, when designing appropriate infiltration systems to meet this requirement, no more than 1% of the project site is required as an effective infiltration area.
 - 2. Infiltrate 25% of the post-development runoff from the 2-year, 24-hour design storm with a type II distribution. Separate curve numbers for pervious and impervious surfaces shall be used to calculate runoff volumes and not composite curve numbers as defined in TR-55. However, when designing appropriate infiltration systems to meet this requirement, no more than 1% of the project site is required as an effective infiltration area.
 - (B) For non-residential development, including commercial, industrial and institutional development, one of the following shall be met:
 - 1. Infiltrate sufficient runoff volume so that the post-development infiltration volume shall be at least 60% of the pre-development infiltration volume, based on an average annual rainfall. However, when designing appropriate infiltration systems to meet this requirement, no more than 2% of the project site is required as an effective infiltration area.
 - 2. Infiltrate 10% of the runoff from the 2-year, 24 hour design storm with a type II distribution. Separate curve numbers for pervious and impervious surfaces shall be used to calculate runoff volumes, and not composite curve numbers as defined in TR-55. However, when designing appropriate infiltration systems to meet this requirement, no more than 2% of the project site is required as an effective infiltration area.
 - (A) Low imperviousness. For development up to 40 percent connected imperviousness, such as parks, cemeteries, and low density residential development, infiltrate sufficient runoff volume so that the post—development infiltration volume shall be at least 90 percent of the pre—development infiltration volume, based on an average annual rainfall. However, when designing appropriate infiltration systems to meet this requirement, no more than one percent of the post—construction site is required as an effective infiltration area.
 - (B) Moderate imperviousness. For development with more than 40 percent and up to 80 percent connected imperviousness, such as medium and high density residential, multi-family development, industrial and institutional development, and office parks, infiltrate sufficient runoff volume so that the post-development infiltration volume shall be at least 75 percent of the pre-development infiltration volume, based on an average annual rainfall. However, when designing appropriate infiltration systems to meet this requirement, no more than 2 percent of the post-construction site is required as an effective infiltration area.
 - (C) High imperviousness. For development with more than 80 percent connected imperviousness, such as commercial strip malls, shopping centers, and commercial downtowns, infiltrate sufficient runoff volume so that the post—development infiltration volume shall be at least 60 percent of the pre—development infiltration volume, based on an average annual rainfall. However, when designing appropriate infiltration systems to meet this requirement, no more than 2 percent of the post—construction site is required as an effective infiltration area.

(DC) Pre-development conditions shall be the same as in paragraph (2).

 $(E\!-\!D)$ Before infiltrating runoff, pretreatment shall be required for parking lot runoff and for runoff from new road construction in commercial, industrial and institutional areas that will enter an infiltration system. The pretreatment shall be designed to protect the infiltration system from clogging prior to scheduled maintenance and to protect groundwater quality in accordance with paragraph $(\underline{I}\!-\!\underline{H})$. Pretreatment options may include, but are not limited to, oil/grease separation, sedimentation, biofiltration, filtration, swales or filter strips.

(FE) Exclusions Source Area Restrictions

- 1. <u>Prohibitions</u>. The runoff from the following areas <u>may not be infiltrated and shall may</u> not be credited toward meeting the requirements of sec. 4.807(4) <u>unless demonstrated to meet the conditions of 4.807(4)(I)</u>. A determination as to whether these exclusions apply to a particular post-construction site must be made as part of the waiver process described in sec. 4.808(3) of this ordinance.
- <u>a</u>¹. Areas associated with tier 1 industrial facilities identified in NR 216.21 (2) (a), Wis. Adm. Code, including storage, loading, rooftop and parking.
- $\underline{b2}$. Storage and loading areas of tier 2 industrial facilities identified in NR 216.21 (2) (b), Wis. Adm. Code.
- <u>c3</u>. Fueling and vehicle maintenance areas. <u>Rooftops of fueling and vehicle</u> maintenance areas may be infiltrated with the concurrence of the LCD.
- 2. Exemptions. The runoff from the following areas may be credited toward meeting the requirement when infiltrated, but the decision to infiltrate runoff from these source areas is optional:
 - a. Parking areas and access roads less than 5,000 square feet for commercial and industrial development not subject to the prohibitions in par 1.
 - b.Except as provided under 4.807(1)(B), redevelopment post-construction sites.
 - c.In-fill development areas less than 5 acres.
 - d.Stand alone roads in commercial, industrial and institutional land uses, and arterial residential roads. Roads that are part of a common plan of development are subject to the standard in this section.

(G) Location of Practices

- 1. Prohibitions. Infiltration practices may not be located in the following areas:
- 4<u>a</u>. Areas within 1000 feet up gradient or within 100 feet down gradient of <u>direct conduits to groundwater karst features</u>.
- b.Areas within 400 feet of a community water system well as specified in NR 811.16 (4) Wis. Adm. Code, or within the separation distances as specified in NR 812.08, Wis. Adm. Code, for any private well or non-community well for runoff infiltrated from commercial, including multi-family residential, industrial and institutional land uses or regional devices for one- and two- family residential development.
- c.Areas where contaminants of concern, as defined in NR 720.03 (2), Wis. Adm. Code are present in the soil through which infiltration will occur.
- 2.Separation Distances. Infiltration practices shall be located so that the characteristics of the soil and the separation distance between the bottom of the infiltration system and the elevation of seasonal high groundwater or the top of

bedrock area in accordance with Table 2. Applicable requirements for injection wells classified under NR 815 shall be followed.

(NEW TABLE)

Separation Distances and Soil Characteristics		
Source Area	Separation Distances	Soil Characteristic
Industrial, Commercial,	5 feet or more	Filtering Layer
Institutional Parking Lots and		
Roads		
Residential Arterial Roads	5 feet or more	Filtering Layer
Roofs Draining to Subsurface	1 foot or more	Native or Engineered Soil with
Infiltration Practices		Particles Finer than Coarse Sand
Roofs Draining to Surface	Not Applicable	
Infiltration Practices		
All Other Impervious Source	3 feet or more	Filtering Layer
Areas		

Table 2

- 3. <u>Infiltration rate exemptions</u>. <u>Infiltration practices located in the following areas may be credited toward meeting the requirements under the following conditions, but the decision to infiltrate under these conditions is optional:</u>
 - a. Where the infiltration rate of the soil measured at the bottom of the proposed infiltration system is less than 0.6 inches/hour using a scientifically credible field test method.
 - b. Where the least permeable soil horizon to 5 feet below the proposed bottom of the infiltration system using the U.S. Department of Agriculture method of soils analysis is one of the following: sandy clay loam, clay loam, silty clay loam, sandy clay, silty clay, or clay.
- 5. Areas with less than 3 feet separation distance from the bottom of the infiltration system to the elevation of seasonal high groundwater or the top of bedrock, except this paragraph does not apply to infiltration of roof runoff.
- 6. Areas with runoff from industrial, commercial and institutional parking lots and roads and residential arterial roads with less than 5 feet separation distance from the bottom of the infiltration system to the elevation of seasonal high groundwater or the top of bedrock.
- 7. Areas within 400 feet of a community water system well as specified in NR 811.16 (4) (d) 3., Wis. Adm. Code, or within 100 feet of a private well as specified in NR 812.08 (4), Wis. Adm. Code, for runoff infiltrated from commercial, industrial and institutional land uses or regional devices for residential development.
- 8. Areas where contaminants of concern, as defined in NR 720.03 (2), Wis. Adm. Code are present in the soil through which infiltration will occur.
- 9. Any area where the soil does not exhibit one of the following soil characteristics between the bottom of the infiltration system and the seasonal high groundwater and top of bedrock: at least a 3-foot soil layer with 20% fines or greater; or at least a 5-foot soil layer with 10 percent fines or greater. This does not apply where the soil medium within the infiltration system provides an equivalent level of protection. This paragraph does not apply to infiltration of roof runoff.

322	(F) Exemptions. The following are not required to meet the requirements of
323	this paragraph. A determination as to whether these exceptions apply to a
324	particular post-construction site must be made as part of the waiver process
325	described in sec. 4.808(3) of this ordinance.
326	
327	1. Areas where the infiltration rate of the soil is less than 0.6 inches/hour
328	measured at the bottom of the infiltration system.
329	
330	2. Parking areas and access roads less than 5,000 square feet for
331	commercial and industrial development.
332	
333	3. Redevelopment post-construction sites.
334	
35	4. In fill development areas less than 5 acres.
336	
337	5. Infiltration areas during periods when the soil on the site is frozen.
338	
339	6. Roads in commercial, industrial and institutional land uses, and arterial
340	residential roads.
341	
342	(\underline{HG}) Where alternate uses of runoff are employed, such as for toilet flushing, laundry or
343	irrigation or storage on green roofs where an equivalent portion of the runoff is captured
344	permanently by rooftop vegetation, such alternate use shall be given equal credit toward
345	the infiltration volume required by this paragraph.
346	
347	(IH) Infiltration systems designed in accordance with this paragraph shall, to the extent
348	technically and economically feasible, minimize the level of pollutants infiltrating to
349	groundwater and shall maintain compliance with the preventive action limit at a point of
350	standards application in accordance with NR 140, Wis. Adm. Code. However, if site-
351	specific information indicates that compliance with a preventive action limit is not
352	achievable, the infiltration BMP may not be installed or shall be modified to prevent
353	infiltration to the maximum extent practicable.
354	
355	(<u>JI</u>) Notwithstanding paragraph (<u>IH</u>), the discharge from BMPs shall remain below the
356	enforcement standard at the point of standards application.
357	
358	(5) Protective Areas.
359	
360	(A) "Protective area" means an area of land that commences at the top of the channel of
361	lakes, streams and rivers, or at the delineated boundary of wetlands, and that is the
362	greatest of the following widths, as measured horizontally from the top of the channel
363	or delineated wetland boundary to the closest impervious surface. However, in this
364	paragraph, "protective area" does not include any area of land adjacent to any stream
365	enclosed within a pipe or culvert, such that runoff cannot enter the enclosure at this
366	location.
367	4 For highly suggestible wetlends 50.75 feet. Highly suggestible wetlends include
368	4. For highly susceptible wetlands, 50 75 feet. Highly susceptible wetlands include the following types: <u>calcareous</u> fens, sedge meadows, <u>open and coniferous bogs</u> , low
369	
370	prairies, coniferous swamps, lowland hardwood swamps, and ephemeral ponds. shrub swamps, other forested wetlands, fresh wet meadows, shallow marshes, deep
371	
372	marshes and seasonally flooded basins. Wetland boundary delineations shall be made
373	in accordance with NR 103.08 (1m) Wis. Adm. Code. This paragraph does not apply
374	to wetlands that have been completely filled in accordance with all applicable state
375	and federal regulations. The protective area for wetlands that have been partially
376	filled in accordance with all applicable state and federal regulations shall be
377	measured from the wetland boundary delineation after fill has been placed.
378	For loss appoint the westlands 10 and of the account of the desired of the first terms of
379	5. For less susceptible wetlands, 10 percent of the average wetland width, but no
380	less than 10 feet nor more than 30 feet. Less susceptible wetlands include degraded
381	wetlands dominated by invasive species such as reed canary grass, <u>cultivated hydric</u>
382	soils, gravel pits or dredged material or fill material disposal sites that take on the
383	attributes of a wetland.

	(D) This paragraph does not apply to:
	1. Except as provided under 4.807(1)(B), redevelopment post-construction sites.
	(9) Alternate Requirements.
	(B) The Technical Review Committee LCD shall make recommendations to the LCC L concerning any storm water requirements more stringent than those set forth in this section. The LCC shall approve or deny alternative requirements.
1.808	Permits and Waivers
•••••	(6) Evaluation and Approval of Applications. Within 10 working days of receipt, the LCD s
	review applications to insure they are complete. Any application found to be incomplete shall returned to the applicant for completion. Upon receiving a complete application, the LCD shall use the following approval/disapproval procedure:
	(B) Completed applications will be evaluated for compliance with the requirements of too ordinance. Other governmental departments or the Technical Review Committee may be consulted during application evaluation.
	(E) Within 20 working days from the receipt of a complete waiver application, or 10 working days from the receipt of additional information requested in accordance with paragraph C, whichever is later, the applicant shall be informed whether the application been approved or disapproved. The LCD shall base the decision in consideration of the recommendations of the Technical Review Committee other governmental departments
	the requirements of this ordinance.
	(J) If the application is disapproved, or if the applicant does not agree with the permit conditions, the applicant may request a review by the Technical Review Committee LCC This request must be made in writing within 30 calendar days from the date of the applic was notified of the LCD decision. The schedule and procedure for a waiver described in paragraph (E) above will be followed for this review.
4.813	Definitions
• • • • • • • • • • • • • • • • • • • •	•
	Average Annual Rainfall: a typical calendar year of precipitation as determined by the DNR users of models such as SLAMM, P8, or equivalent methodology. The average annual rainfall chosen from a DNR publication for the location closest to the municipality a calendar year of precipitation, excluding snow, which is considered typical.
	Connected Imperviousness : an impervious surface that is directly connected to a separate storm sewer or water of the state via an impervious flow path or minimally pervious flow path
	•
	<u>Direct conduits to groundwater</u> : wells, sinkholes, swallets, fractured bedrock at the surface mine shafts, non-metallic mines, tile inlets discharging to groundwater, quarries, or
	depressional groundwater recharge areas over shallow fractured bedrock.
	Existing development: development in existence on March 1, 2004, or development for what a storm water management permit applies in page 3004
	a storm water management permit application was submitted to the LCD by March 1, 2004
	Filtering layer: soil that has at least a 3-foot deep layer with at least 20 percent fines; or at
	least a 5-foot deep layer with at least 10 percent fines; or an engineered soil with an

equivalent level of protection as determined by the regulatory authority for the site. 448 449 Impaired water: a waterbody impaired in whole or in part and listed by the department 450 451 pursuant to 33 USC 1313 (d) (1) (A) and 40 CFR 130.7, for not meeting a water quality standard, including a water quality standard for a specific substance or the waterbody's 452 designated use. 453 454 Impervious Surface: an area that releases as runoff all or a large portion of the precipitation 455 that falls on it, except for frozen soil. Rooftops, sidewalks, gravel or paved driveways, gravel or 456 paved parking lots, and gravel or paved streets are examples of surfaces that typically are 457 458 impervious. 459 In-fill Area: an undeveloped area of land located within existing development. "In-fil area" 460 does not include any undeveloped area that was part of a larger new development plan for 461 462 which a storm water permit has previously been approved by the LCD 463 Maximum Extent Practicable: the highest level of performance that is achievable but is not 464 equivalent to a performance standard in this chapter. Maximum extent practicable applies 465 when a person who is subject to a performance standard of this ordinance demonstrates to the 466 LCD's satisfaction that a performance standard is not achievable and that a lower level of 467 performance is appropriate. In making the assertion that a performance standard is not 468 achievable and that a level of performance different from the performance standard is the 469 470 maximum extent practicable, an applicant shall take into account the best available technology, cost effectiveness, geographic features, and other competing interests such as protection of 471 public safety and welfare, protection of endangered and threatened resources, and preservation 472 473 of historic properties. a level of implementing BMPs in order to achieve a performance standard specified in this chapter which takes into account the best available technology, cost 474 475 effectiveness and other competing issues such as human safety and welfare, endangered and 476 threatened resources, historic properties and geographic features, "Maximum extent practicable" allows flexibility in the way to meet the performance standards and may vary based 477 on the performance standard and site conditions. 478 479 Technical Review Committee: a committee comprised of the Director of the Land 480 Conservation Department, a representative of the Planning and Development Agency, a 481 representative of the Land Conservation Department, and a representative of the Public Works, 482 483 Highway and Parks Department, and a representative of the town where the site of a permit or waiver application is located. If the application site is located within the extraterritorial area of 484 485 a city or village a representative of that city or village will be invited to participate as a member 486 of the committee for that application. If groundwater concerns are among issues the committee 487 must address, the Public Health Department will be invited to participate as a member of the 488 committee for that application. 489 490 Total maximum daily load or TMDL: the amount of pollutants specified as a function of one 491 or more water quality parameters, that can be discharged per day into a water quality limited 492 segment and still ensure attainment of the applicable water quality standard. 493

II. This ordinance shall be effective upon publication.

494

Res	pectfully	submitt	ed
TCOD	pectuary	Suchinic	···

LAND CONSERVATION COMMITTEE

Larry Wiedenfeld Larry Wiedenfeld, Vice-Chair

Eva Arnold

David Rebout, USDA-FSA Representative

Alan Sweeney

FISCAL NOTE:

No fiscal impact.

Sherry Oja

Finance Director

LEGAL NOTE:

The County Board is authorized to take this action by Wisconsin Statutes sections 59.02, 59.692 and 59.693.

Eugene R. Dumas
Deputy Corporation Counsel

ADMINISTRATIVE NOTE:

Recommended.

Craig Knutson County Administrator

Amending Section 4.8 020314.res

Executive Summary

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8)

and

Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Please note that complete annotated and non-annotated versions of each ordinance, which incorporate each of the proposed amendments, are available at the County Clerk's office.

The County of Rock was authorized by the DNR on November 13, 2006 to discharge stormwater from the County owned Municipal Separate Storm Sewer Systems (MS4) in the Urbanized Area under a general Wisconsin Pollutant Discharge Elimination System (WPDES) MS4 permit. The Urbanized Area is determined by population density based on the most recent census. Under the permit language, MS4 means a conveyance or system of conveyances including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, constructed channels or storm drains, which meets all of the following criteria: Owned or operated by a municipality, designed or used for collecting or conveying storm water, and which is not a combined sewer conveying both sanitary and storm water.

The County's WPDES MS4 General Permit outlines certain minimum programs and documentation that must be developed and submitted by dates certain. Among the requirements is to adopt and enforce construction site erosion control and post-construction storm water management regulations, which the County has had in place since March 2004. These ordinances have been approved by the DNR in the past, but changes to State Administrative Code NR 151 in January of 2011 are required to be incorporated into local ordinances. The recommended action for each ordinance approves those required changes (including various definitions) along with less substantive changes which are recommended by the LCD based on administrative experiences.

The substantive changes are summarized below with reference to the ordinance section(s):

Removal of Technical Review Committee (recommended by the LCD for both ordinances): All references to the Technical Review Committee have been deleted from each Ordinance and changed, where necessary, to LCD and/or LCC. Staff has determined that this additional level of review, requiring input from other departments or local unit of government, is a step in the review process that is not necessary to effectively administer the ordinances. Appeals and/or alternative requirements formerly requiring input from the Technical Review Committee will be processed with a LCD recommendation and LCC decision. The LCD recommendation will still be based on consultation with other entities with jurisdiction over the project.

Post-Construction Storm Water Management (4.8)

Changes to required standards for redevelopment projects:

1. (4.805(2)(B)1.e.) Redevelopment projects are no longer entirely exempt from storm water ordinance requirements under NR 151. Redevelopment projects must meet total suspended solid (TSS) reduction standards (40% reduction, compared to 80%

Amending Various Sections of the Rock County Storm Water Management Ordinance (4.8) and Amending Various Sections of the Rock County Construction Site Erosion Control Ordinance (4.11)

Page 1 of 2

- reduction for new development), however exemptions remain for infiltration and peak discharge standards.
- 2. **(4.807(1)(B))** Maintenance of effort. This section is added, based on NR 151, to address redevelopment sites that were previously approved under the storm water ordinance requirements for new development. This section prevents a redevelopment project from being required to meet lesser standards than what were required when originally permitted.

Changes to the peak discharge rate and volume standards:

- 1. (4.807(2)). The one year, twenty-four hour storm event was added to the design requirements in NR 151.
- 2. (4.807(2)(B)4). The maximum pre-development runoff curve numbers were revised.

Changes to the storm water runoff discharge quality standards (total suspended solids):

1. (4.807(3)). Infill development is no longer exempt from TSS reduction standards under NR 151.

Changes to infiltration standards (4.807(4)):

This section was entirely reorganized based on the changes to NR 151. The level of infiltration that is required is now based on the level of planned impervious surface, rather than land use type. Also, sections formerly titled "Exclusions" and "Exemptions" have been reorganized to clarify the intent of the standards. Generally, the ordinance now includes criteria for Source Area Restrictions (i.e. the area that drains to an infiltration practice(s)) and the Location of Practices.

Changes to certain definitions (4.813): For the most part, the changes to the definitions are directly from NR 151 and are primarily for clarification purposes.

Construction Site Erosion Control (4.11)

Changes to performance standards under NR 151:

- 1. (4.1107(1)(B)2.): The method used to estimate the sediment discharged from a project and, subsequently, design a plan to reduce it has been revised. The 80% reduction standard was changed to a standard which allows a maximum of 5 tons per acre per year from a construction site. This level of allowed discharge is consistent with agricultural standards for most of the soils in Rock County. In terms of actual tolerable soil loss, 80% reduction and 5 tons per acre per year are very similar thresholds. However, the acceptable software tools to estimate soil loss and plan the practices to reduce erosion and sedimentation are simpler to use and not cost prohibitive.
- 2. (4.1107(1)(E)): The addition of other sources of pollutants that must be consideration considered when developing a plan.
- 3. (4.1107(2)): Implementation techniques are specified to avoid any question of what is required. These points were typically included in the permit conditions of approval, but now are added directly to the performance standards section to be consistent with NR 151.

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Robert Leu INITIATED BY

The General Services Committee SUBMITTED BY



Robert Leu DRAFTED BY

March 19, 2014 DATE DRAFTED

	Recognizing Wilson Meadows for Service to Rock County
2	WHEREAS, Wilson Meadows has served the citizens of Rock County for over thirty-two (32) years as a dedicated and valued employee of Rock County; and,
3 4 5 6	WHEREAS, Wilson Meadows began his career on September 21, 1981, as a Maintenance Worker II in the General Services Department, at the Rock County Courthouse; and,
7 8 9	WHEREAS, Wilson Meadows worked at the Courthouse in Janesville until August 31, 1998, the County Building in Beloit until February 25, 2002, and the Youth Services Center /911 Communications Center, until his retirement on March 12, 2014, as a Maintenance Worker IV in the General Services Department.
	WHEREAS, Wilson was honest, dedicated, laid-back, and well-liked by the people he came in contact with, and truly cared about the buildings he maintained.
14 15	NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors duly assembled this day of, 2014, does hereby recognize Wilson Meadows for his 32 years of service, and wishes him the best in his future endeavors; and,
18	BE IT FURTHER RESOLVED that the County Clerk be authorized and directed to furnish a copy of this resolution to Wilson Meadows.
	Respectfully Submitted:
	General Services Committee: Absent Phillip Owens, Chair County Board Staff Committee: J.Russell Podzilni, Chair
	Henry Brill, Vice Chair Sandra Kraft, Vice Chair
	Ivan Collins Jung Sussie Betty Johnseie
	Jason Heidenreich Eva Arnold
0	Edwin Nash Mary Mawhinney
	Marilynn Jensen
	Kurtis Yankee
	Henry Brill
	Loui Per

Louis Peer

RESOLUTION

ROCK COUNTY BOARD OF SUPERVISORS

<u>Health Services Committee</u> INITIATED BY



Sue Prostko DRAFTED BY

Health Services Committee SUBMITTED BY March 13, 2014 DATE DRAFTED

RECOGNIZING ROSS JACOBSON FOR SERVICE TO ROCK HAVEN

	•	
1 2 3	WHEREAS, Ross Jacobson has served the citizens dedicated and valued employee of Rock County; and,	of Rock County over the past 20 years, 8 months as a
4 5	WHEREAS, Ross Jacobson began his career with Roand,	ck Haven as a Master Social Worker on October 5, 1993;
6 7 8	WHEREAS, Ross Jacobson has worked diligently in	that position until his retirement on July 7, 2014; and,
9	WHEREAS, the Rock County Board of Supervisor commend Ross Jacobson for his long and faithful serv	rs, representing the citizens of Rock County, wishes to ice.
1 2 3 4 5		Rock County Board of Supervisors duly assembled this gnize Ross Jacobson for his 20 years, 8 months of service vors; and,
6 7	BE IT FURTHER RESOLVED, that the County C resolution to Ross Jacobson.	llerk be authorized and directed to furnish a copy of this
	Respectfully submitted,	
	HEATTH SERVICES COMMITTEE	COUNTY BOARD STAFF COMMITTEE
)	Betty of Bussie, Chair	J. Russell Podzilni, Chair
	Mary Beaver, Vice Chair	Sandra Kraft, Vice Chair
	Terry Fell	Betty Jo Bussie
	Billy Bob Grahn	Eva Arnold
	Steve Howland	Mary Mawhinney
		Marilynn Jensen
		Kurtis Yankee
•		Hank Brill
		Louis Peer

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Charmian Klyve INITIATED BY

Human Service Board SUBMITTED BY



Denise Hegberg DRAFTED BY

April 16, 2014 DATE DRAFTED

RECOGNIZING STEPHANIE ANN NICKOLS

WHEREAS, Stephanie Ann Nickols has served the citizens of Rock County for over twenty-three (23)
 years as a dedicated and valued employee of Rock County; and,

3

WHEREAS, Ms. Nickols began her career on April 25, 1991, as a Social Worker in the Child Protective Services Division. During her time served, she assisted in both the Initial Assessment and Ongoing Service Units. Ms. Nickols was originally hired in 1991 as a Limited Term Employee (LTE) to investigate Child Abuse & Neglect concerns. Over the course of time, her position became more permanent and included Case Management roles and responsibilities. In August 2003, Ann was officially offered permanent employment at Rock County, with the CPS Ongoing Services Division. While functioning as a Social Worker in that capacity, she maintained an ongoing caseload with the goal to achieve permanency. Over the years, Ms. Nickols worked hard to establish trust and build relationships with the families she served. Ms. Nickols supported families with the goal of uniting them as an intact family. Ms. Nickols had great success in this role as many of the families she served were able to successfully reunify. Ms. Nickols found her work to be rewarding and gratifying. She was compassionate with families and driven to assist them achieve positive outcomes. Over the course of time, Ms. Nickols has dutifully advocated for the child(ren) and parent(s) best interest; and,

16 17 18

19

20

10

11 12

13 14

15

WHEREAS, Ms. Nickols went into the Profession of Social Work to protect children and assist families; providing quality and superb case management; attaining client and family centered services to meet their needs, collaborating with community agencies, as well as engaging, building and maintaining relationships; and,

21 22 23

24

WHEREAS, Ms. Nickols has demonstrated through her actions her belief in the mission of the Social Work profession; rooted in core values to include: service delivery, social justice, dignity & self-worth, importance of human relationships, integrity and competence; and,

25 26 27

28

WHEREAS, Ms. Nickols has proven herself to be a dedicated and outstanding employee, serving on behalf of Rock County residents; and will be retiring from Rock County Department of Human Services on Thursday, May 1, 2014; and,

29 30 31

WHEREAS, the Rock County Board of Supervisors, representing the citizens of Rock County, wishes to recognize Stephanie Ann Nickols for her achievements and significant contributions to the citizens of Rock County and her lifelong and faithful service.

32

NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors, duly assembled this _____ day of _____, 2014, does hereby recognize Stephanie Ann Nickols for her 23 years of service and extend best wishes to her in her future endeavors; and,

37 38 39

BE IT FURTHER RESOLVED, that the County Clerk be authorized and directed to furnish a copy of this resolution to Stephanie Ann Nickols.

14-4C-01

Page 2			
HUMAN SERVICES BOARD			
Brian Knudson, Chair	_		
Sally Jean Weaver-Landers, Vice Chair			
Sairy Sean Weaver-Landers, Vice Chair			
Terry Fell	_		
William Grahn	-		
Ashley Kleven	_		
Terry Thomas	-		
Shirley Williams	_		
	_		
COUNTY BOARD STAFF COMMITTEE			
J. Russell Podzilni, Chair			
J. Russell Podzilni, Chair			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney			
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie			

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

Charmian Klyve INITIATED BY

Human Service Board



Jenna Singer DRAFTED BY

April 16, 2014 DATE DRAFTED

TO RECOGNIZE STEVE POLGLAZE

WHEREAS, Steve Polglaze has served the citizens of Rock County for over thirty-nine (39) years as a dedicated and valued employee of Rock County; and,

3 4

5

6 7

8

9

10

11

12

WHEREAS, Steve Polglaze began his career on September 1, 1975 as a Certified Nursing Assistant (CNA) at Rock Haven where he worked for one year. Then in 1976 he began work at the County's Youth Home which was a stand alone non-secure facility. He worked there for about 13 years. Next he worked with Adolescent Day Treatment as a psychiatric technician for one year before going to work for one year at Economic Support. By 1991, Mr. Polglaze found a permanent position with Child Protective Services (CPS) where he has worked as a Family Skills Specialist. For the last 13 years Mr. Polglaze has supported families in their efforts to stay united and make lasting positive changes. He has done so by fostering genuine and trusting relationships with families and staff at the Department. He has been a leader in facilitating much change within the Department along with families. This change came from his ability and willingness to be so open and humble; and,

13 14 15

16

17

18

19

WHEREAS, Mr. Polglaze wanted to work with families because he understands they are the mechanism for change. He identified strengths in every family and has worked to build on those strengths. He advocated not only for what was best for each family, but also, so they might have a voice in the child welfare system. Mr. Polglaze stated, "I believe I worked for the people of Rock County." Mr. Polglaze will be retiring from Rock County Department of Human Services on May 1, 2014; and,

20 21 22

WHEREAS, Steve Polglaze has proven himself to be a compassionate and caring employee, advocating on behalf of Rock County residents; and,

23¹ 24¹ 25¹

WHEREAS, the Rock County Board of Supervisors, representing the citizens of Rock County, wishes to recognize Steve Polglaze for his achievements and significant contributions to the citizens of Rock County and his lifelong and faithful service.

NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors, duly assembled this ______ day of ______, 2014, does hereby recognize Steve Polglaze for his 39 years of service and extend best wishes to him in his future endeavors; and.

31 32 33

34

30

BE IT FURTHER RESOLVED, that the County Clerk be authorized and directed to furnish a copy of this resolution to Steve Polglaze.

14-4C-012

Brian Knudson, Chair Sally Jean Weaver-Landers, Vice Chair Terry Fell William Grahn Ashley Kleven Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney Louis Peer	12.J.(2)	1:				nize Steve Polglaze	To Recognize Page 2
Sally Jean Weaver-Landers, Vice Chair Terry Fell William Grahn Ashley Kleven Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney					D	SERVICES BOARI	HUMAN SE
Terry Fell William Grahn Ashley Kleven Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						ıdson, Chair	Brian Knudso
William Grahn Ashley Kleven Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney					Vice Chair	Weaver-Landers, V	Sally Jean W
Ashley Kleven Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney							Terry Fell
Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						ìrahn	William Gral
Terry Thomas Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						even	Ashley Kleve
Shirley Williams COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney							
COUNTY BOARD STAFF COMMITTEE J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						mas	Terry Thoma
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						illiams	Shirley Willia
J. Russell Podzilni, Chair Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney		•	÷				
Sandra Kraft, Vice Chair Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney					OMMITTEE	BOARD STAFF CO	COUNTY BO
Eva Arnold Henry Brill Betty Jo Bussie Mary Mawhinney						Podzilni, Chair	J. Russell Po
Henry Brill Betty Jo Bussie Mary Mawhinney				•		aft, Vice Chair	Sandra Kraft,
Betty Jo Bussie Mary Mawhinney						d	Eva Arnold
Mary Mawhinney						11	Henry Brill
						ussie	Betty Jo Buss
Louis Peer						vhinney	Mary Mawhi
Louis Peer					A		
						r	Louis Peer
Kurtis L. Yankee					· ·		Kurtis I Var

RESOLUTION ROCK COUNTY BOARD OF SUPERVISORS

<u>Charmian Klyve</u> INITIATED BY

Human Services Board SUBMITTED BY



Sara Mooren DRAFTED BY

April 14, 2014 DATE DRAFTED

Recognizing HSD Administrative Professionals and Paraprofessionals

WHEREAS, April 20-26, 2014 is observed as Administrative Professionals Week and April 23, 2014 is declared Administrative Professionals Day; and,

WHEREAS, the Rock County Board of Supervisors, representing the citizens of Rock County, wish to commend the Administrative Professionals and Paraprofessionals in the Rock County Human Services Department for their excellence in administering services to the citizens of Rock County; and,

WHEREAS, the Human Services Department has a great number of administrative professionals and paraprofessionals in all divisions throughout the Department, serving in a wide variety of positions and assisting every Rock County Human Services program area; and,

WHEREAS, administrative professional and paraprofessional positions include Accountants, Account Clerks, Administrative Assistants, Application Support Specialists, Clerks, Clerk-Typists, Data Processing Operators, HSD Support Specialists, Information Processing Operators, Job Center Support Specialists, Legal Stenographers, Medical Record Technicians, Program Analysts, Release of Information Technicians, Secretaries, and Word Processing Operators; and,

WHEREAS, HSD administrative professionals and paraprofessionals have many responsibilities that are crucial to the efficient functioning and smooth running of day-to-day operations which include, but are not limited to, taking meeting minutes, transcribing reports, managing records, setting up and maintaining databases, data entry, producing statistics and reports, completing mandated state reports, issuing statements, paying bills, greeting visitors, answering telephones, inventorying forms, ordering and maintaining supplies and equipment, troubleshooting equipment problems, scheduling appointments, collecting information, and covering many other administrative functions for the Human Services Department.

NOW, THEREFORE, BE IT RESOLVED that the Rock County Board of Supervisors duly assembled this ______ of _______, 2014 commends all Rock County Human Services Administrative Professionals and Paraprofessionals for their diligent efforts which make possible the delivery of services to the citizens of Rock County.

BE IT FURTHER RESOLVED, that the County Clerk be authorized and directed to furnish a copy of this resolution to the Rock County Human Services Department.

2.K.(
-
-
-
-
-